

PRIMARY CORNER DESCRIPTION NE Cor. Sec. 1

Alias _____ Description _____
 Alias _____ Description _____
 Alias _____ Description _____
 Alias _____ Description _____


GLO survey by S.C. Flint, Contract #454, dated June 19, 1882
 (DCSO records Vol. 12 Page(s) 4979)

 Set Cedar post 4 ft. long, 4" sq., firmly in the ground for
 standard cor. to T27S R2 and 3 W., with a mound of stones
 around post, and mkd. SC T27S on N., R2W S31 on E., and R3W
 S36 on W. faces, with 6 notches on N. E. and W. faces, from
 which

- A Fir 12" dia., bears N.43°E., 70 lks. dist. mkd. SC T27S
 R2W S31 BT.
- A Fir 30" dia., bears N.55°W., 46 lks. dist. mkd. SC T27S
 R3W S36 BT.
- A Fir 36" dia., bears S.25°W., 42 lks. dist. mkd. SC T28S
 R3W S1 BT.

Douglas Co. Surveyors Office - James Byron, Deputy - John
 Powell & Wm. Stoffel, crew - Aug. 1962 - C.S. File 52/126-42

 Found all orig. BTs. All are now stumps. NE. BT, shows good
 scribing "3". Also find rock mound at corner.
 Set brass cap at cor. mkd. County Surveyors Office 1962



- New BTs- 16" Cedar bears S.27°W., 72.0 ft. scribed S1 T28S
 R3W CS BT.
- 17" Laurel bears S.3°E., 17.0 ft. scribed S6 T28S
 R2W CS BT.
- 4" R.Fir bears N.10°W., 19.8 ft. scribed S36 CSBT
- 9" R.Fir bears N.87°E., 50.1 ft. scribed S31 CS BT
 T27S R2W.

Fd. OK, Oct. 1968 by DCSO C.S 54/40-100

Survey by Ronald A. Quimby - For: U.S. Forest Service - March
 1980 - M 79-37

 Found - 1" Iron pipe with 1962 DCSO brass cap.
 11" D.Fir N.14°W., 19.7 ft., good scar.
 14" Madrone snag, S.3°E., 17.0 ft., visible scribes.
 22" Cedar S.27°W., 72.8 ft., visible scribes.
 New BT - 7" D.Fir N.27°E., 35.3 ft. "T27S R2W S31 BT".
 Set fiberglass post 3.0 ft. South. BT has brass washer RLS
 1005 in face.

(Cont. Next Page)

PRIMARY CORNER DESCRIPTION NE Cor. Sec. 1

Alias	Description
Alias	Description
Alias	Description
Alias	Description

Survey by Ronald G. Geisler - For: Champion International -
June/Aug. 1985 - M 90-71

-
- Found - 1962 DCSO brass cap on an iron post.
27" Fir stump bears N.40°E., 46.9 ft. (Rec. N.43°E.,
46.2 ft.) scribing partly visible. (Orig. BT)
44" Fir stump bears N.52°W., 29.9 ft. (Rec. N.55°W.,
30.4 ft.) No scribing visible. (Orig. BT)
Badly decayed stump bears S.25°W., 27.7 ft. (Orig.)
11" broken-top Fir bears N.10°W., 19.7 ft. closed
face. (1962)
22" Cedar bears S.27°W., 71.6 ft. (Rec. 72.0 ft.)
Closed face. (1962)
16" Madrone snag 17 ft. tall, bears S.06°E., 17.0
ft. (Rec. S.03°E.) Scribing visible (1962)
9" down and uprooted Fir bears N.87°E., 50.0 ft. No
scribing found. (1962)
10" Fir bears N.27°E., 35.1 ft. (Rec. 35.3 ft.)
Closed face. (1980)
- New BT - 5" Fir bears S.79°E., 5.9ft. scribed X BT.