

County Surveyor's Record, Douglas County, Oregon

Subdivisions of T. 26 S., R. 3 W.


CHAINS

from which

A W. oak, 12 ins. diam., bears S.40*W., 34 lks.
dist.

A fir, 10 ins. diam., bears N.25*W., 10 lks.
dist.

- 40.50 East Bank of North Umpqua River. Set flag on opposite bank and from a point due N took the angle S.62*W., to opposite flag, then took the angle S.62*E., and marked the point of intersection of line measured this distance which was 3.75 chs.



- 44.25 West Bank Falls about 5 chs. below this point of crossing.

- 80.00 Set fir post, 5 ft. long, 20 ins. in ground, 5 ins. diam., from which

A fir, 20 ins. diam., bears N.48*E., 58 lks. dist.

An oak, 10 ins. diam., bears S.88*E., 180 lks. dist.

A fir, 20 ins. diam., bears S.88*W., 66 lks. dist.

A fir, 60 ins. diam., bears N.45*W., 150 lks. dist.

Cor. to secs. 1, 2, 11 and 12.

Land, E part sloping to the river, hilly, 3d rate. W part rolling hilly, 2d rate.

Timber, principally fir, cedar and pine.

Underbrush, same, with hazel, vine maple and tasselwood.

South, bet. secs. 11 and 12.

Va.18*E.

- 5.50 Logging Road, course E and W.

January 28, 1879.

- 39.00 Top of spur, logging road, course N.20*E.