

25

Supplemental Field Notes of,
Subdivisions of T. 29 S., R. 1 W.,

CHAINS	
	North 0*3'W. bet. secs. 28 and 29.
	Over mountainous land heavily timbered and covered with dense undergrowth.
0.30	The cor. which I established in my original survey under contract No. 757 at the cor. of secs. 28, 29, 32 and 33, bears E. 44 lks. dist. I destroy the cor. and marks on bearing trees.
16.50	Creek, 1 lk. wide, course SE.
34.25	Leave heavy timber. Enter brushy opening, known as Horseshoe Burn.
40.00	Set a porphyry stone, 18x10x8 ins. 12 ins. in the ground for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face, from which. A fir, 6 ins. diam., bears N.13*E., 17 lks. dist., marked $\frac{1}{4}$ S 28 B. T. A fir, 5 ins. diam., bears S.7*W., 62 lks. dist., marked $\frac{1}{4}$ S 29 B. T.
40.15	The cor. which I established in my original survey under contract No. 757 as the $\frac{1}{4}$ sec. cor. bet. secs. 28 and 29, bears E. 22 lks. dist. I destroy the cor. and marks on bearing trees.
50.00	Summit of ridge, bears E. and W.
52.50	Enter heavy timber, bears NW. and SE. Descend steep NE. slope.
61.00	Creek, 5 lks. wide, in canyon, course SE.
76.50	Leave heavy timber, bears NW. and SE.
80.00	The cor. of secs. 20, 21, 28 and 29, which I established in my original survey under contract No. 757. Land, mountainous. Soil, loam and stoney, 2nd. and 3rd. rate. Timber, red and white fir, yellow and sugar pine and cedar. Undergrowth, arrowwood, willow, vine maple and hazel. Mountainous or heavily timbered land or land covered with dense undergrowth. 80.00 chs.
	November 13, 1907.

SEE ADJOINING PAGE
FOR NOTES FOR SEC. COR. 20-21-28-29

County Surveyor's Record, Douglas County, Oregon

0083

Supplemental Notes Subdivision of T. 29 S., R. 1 W.

CHAINS

76.50

Leave heavy timber, bears NW and SE.

80.00

Set a basalt stone 18x12x10 ins, 12 ins. in the ground for corner of Secs. 20, 21, 28 and 29, marked with 2 notches on S., and 4 notches on E edge; from which

A Red Fir 10ins. diam., bears N. 50° E. 229 lks. dist. marked T 29 S R 8 W S 21 B T.

A Red Fir 24 ins. diam. bears S. 75° E. 170 lks. dist. marked T 29 S R 1 W S 28 B T.

A Cedar 8 ins. diam., bears S. 50° W. 72 lks. dist. marked T 29 S R 1 W S 29 B T.

A Red Fir 14 ins. diam., bears N. 81° W., 81 lks. dist. marked T 29 S R 1 W S 20 B T.

Land, mountainous.


Soil, loam and stony, 2nd and 3rd rate.

Timber, red & white fir, sugar pine, cedar; undergrowth, vine maple, chinquapin, arrowwood, willow.

Mountainous or heavily timbered land or land covered with dense undergrowth, 80.00 chs.

August 21; At this corner, I set off 12°10' N. on the decl. arc and at 12h 3m, l. m. t., observe the sun on the meridian. The resulting lat is 43°2' or nearly the proper lat.

SEE NOTES IN CROSS. JAN. 1964



UNITED STATES
DEPARTMENT OF THE INTERIOR

BUREAU OF LAND MANAGEMENT
State Office
710 N. E. Holladay
Portland, Oregon 97232

100.45
9100

January 28, 1964

Fred M. Darby
County Surveyor, Douglas County
Court House
Roseburg, Oregon

Dear Sir:

It appears that Fred Menach improperly surveyed the line between Sections 28 and 29, T. 29 S., R. 1 W., and was sent back to correct it. The field notes to which your letter of January 27, 1964, refers, are apparently the handwritten correction notes which do not describe the corner of Sections 20, 21, 28 and 29. It is hard to describe what happened by narrative. Therefore, we are enclosing a xerox copy of the first notes of the line, which were crossed out in red except for the corner description, and also a xerox copy of the later correction notes. This should help to make the matter clear.

Sincerely yours,

Thomas A. Tillman
Thomas A. Tillman
Chief, Branch of Cadastral
Engineering