


# County Surveyor's Record, Douglas County, Oregon

THIS PAGE OF LINE NOTES WAS NOT TYPED WHEN THE REST OF THIS SURVEY WAS.  
 THE PREVIOUS PAGE ENDED WITH 13.30 CHAINS AND THE FOLLOWING PAGE STARTED WITH 103.50  
 ADDED 2/9/2015 PER RESEARCH BY JC DCSO

East Boundary of T. 25 S., R. 3 E.,

Chains.

- 23.70 Spur, slopes E., desc. 171 ft. over NE. slope.
- 31.40 Draw, drains E., asc. 124 ft. over SE. slope.
- 39.20 Spur, slopes E., "Little Dome Rock", a rock peak, 150 ft. high, about 4.00 chs. long, N. and S., and about 1.75 chs. wide, bears W. 1.00 ch. dist., desc. 54 ft. over NE. slope.
- 40.00 Set an iron post, 3 ft. long, 1 in. diam., 27 ins. in the ground, for  $\frac{1}{4}$  sec. cor., with brass cap mkd.




from which

A fir, 48 ins. diam., bears N.18°W., 63 lks. dist., mkd.  $\frac{1}{4}$  S 1 B T

A fir, 24 ins. diam., bears S.40°E., 42 lks. dist., mkd.  $\frac{1}{4}$  S 6 B T

Along broken E. slope.

- 43.70 Asc. 287 ft. over SE. slope.
- 59.70 Spur, slopes E., desc. 301 ft. over NE. slope.
- 73.10 Draw, drains E., asc. 87 ft. over SE. slope.
- 78.50 Spur, slopes E., desc. 171 ft. over N. slope.
- 80.00 Set an iron post, 3 ft. long, 1 in. diam., 28 ins. in the ground, for cor. of lots 8 and 9, sec. 1, and lots 5 and 12, sec. 6, with brass cap mkd.



from which

A fir, 18 ins. diam., bears N.36°E., 46 lks. dist., mkd. S 6 L 5 B T

A fir, 16 ins. diam., bears S.38°W., 47 lks. dist., mkd. S 1 L 9 B T

Desc. 725 ft. over broken NE. slope.

- 86.10 Draw, drains NE.,
- 96.00 Spur, slopes NE.,