

Subdivision of T. 26 S., R. 3 E.

CHAINS

N.0*01'W., bet. secs. 35 and 36.

Over nearly level top of mountain, through heavy young timber and medium undergrowth.


5.50 Top of descent bears NW. and SE., desc. 567 ft. over N. slope.

30.20 Clearwater Way Trail, bears NW. and SE.

34.10 Left bank of Clearwater River, course NW.

35.40 Right bank of river, over nearly level land.

40.00 Set an iron post, 3 ft. long, 1 in. diam., 28 ins. in the ground, for $\frac{1}{4}$ sec. cor., with brass cap mkd.



A fir, 48 ins. diam., bears S.74*E., 25 lks. dist., mkd. $\frac{1}{4}$ S 36 B T

A pine, 15 ins. diam., bears S.32*W., 59 lks. dist., mkd. $\frac{1}{4}$ S 35 B T

Asc. 12 ft. along broken W. slope.

48.00 Small spur, slopes W., desc. 55 ft. over NW. slope.


51.50 Left bank of North Umpqua River, course S.15*W.,

59.20 Right bank of river, asc. 274 ft. over broken SE. slope.

60.00 Mountain Meadows Trail, and forest service telephone line bears NE. and SW.,

72.20 Creek, 1 lks. wide, course SE.

80.00 Set an iron post, 3 ft. long, 2 ins. diam., 28 ins. in the ground, for the cor. of secs. 25, 26, 35 and 36 with brass cap mkd.



A pine, 12 ins. diam., bears N.57*E., 17 lks. dist., mkd. T 26 S R 3 E S 25 B T

A fir, 20 ins. diam., bears S.59*E., 57 lks. dist., mkd. T 26 S R 3 E S 36 B T.