

County Surveyor's Record, Douglas County, Oregon

Subdivision of T. 29 S., R. 2 E.

CHAINS

72.40 Dry creek bed, 10 lks. wide, course S. Ascend gradually over SE. slope.

79.92 The cor. of secs. 10, 11, 14 and 15. Land, mountainous., Not very rough Soil, clay loam and rocky; 2nd rate. Timber, Douglas fir, white fir, cedar and pine. Undergrowth, rhododendron, vine maple, dogwood and reproduction of forest trees.

N. 0* 2' W., bet. secs. 10 and 11. Over mountainous land, through heavy timber and medium undergrowth. Ascend 210 feet over SE. slope.


17.92 "Emerson Trail" bears N. 60* W., and S. 60* E. 20.00 Divide between Buckeye Creek and Fish Lake Creek, bears E. and W. Descend 210 ft. over N. slope, to 40.00 Set an iron post, 3 ft. long, 1 in. dia., 27 ins. in the ground, for 1/4 sec. cor., with brass cap marked



A Douglas fir, 18 ins. dia., bears S. 52 * E., 26 1/2 lks. dist., marked 1/4 S 11 BT. A white fir, 24 ins. dia., bears S. 83* W., 40 lks. dist., marked 1/4 S 10 BT.

Descend 550 ft. over general N. slope, to sec. cor.

63.30 Brook, 3 lks. wide, course N. 35 * W. 80.00 Set an iron post, 3 ft. long, 2 ins. dia., 27 ins. in the ground, for cor. of secs. 2, 3, 10 and 11, with brass cap marked



A Douglas fir, 40 ins. dia., bears N. 20* E., 34 lks. dist., marked T 29 S R 2 E S 2 BT. A Douglas fir, 14 ins. dia., bears S. 1 1/8* E., 29 lks. dist., marked T 29 S R 2 E S 11 BT.