

County Surveyor's Record, Douglas County, Oregon

Township 30 South, Range 3 East.
East Boundary.

CHAINS


A Red Fir, 24 ins. dia., bears S.54*E., 46 lks.
dist., mkd. 1/2 S 30 B T.
A Red Fir, 28 ins. dia., bears S.81*W., 31 lks.
dist., mkd. 1/4 S 25 B T.

52.00 Desc. 100 ft. over NW slope.

57.55 Left bank of Castle Creek, 40 lks. wide, C. W., asc.
90 ft. over S. slope.

65.60 Top of asc.; thence over level land.

80.00 Set an iron post, 3 ft. long, 2 ins. dia., 26 ins. in
the ground, for cor. of Secs. 19, 24, 25 and 30,
with brass cap mkd.



from which

A Red Fir, 42 ins. dia., bears N.43*E., 28 lks.
dist., mkd. T 30 S R 4 E S 19 B T.

A White Fir, 20 ins. dia., bears S.53*E., 45 lks.
dist., mkd. T 30 S R 4 E S 30 B T.

A Pine, 26 ins. diam., bears S.56*W., 20 lks.
dist., mkd. T 30 S R 3 E S 25 B T.

A Red Fir, 26 ins. dia., bears N.68*W., 13 lks.
dist., mkd. T 30 S R 3 E S 24 B T.

Land, level and rolling.

Soil, sandy, 2nd rate.

Timber, Fir, Pine and Hemlock.

Undergrowth, snow brush, hazel, small fir and pine.

North, bet. Secs. 19 and 24.

Over rolling land, through heavy timber and medium
undergrowth.

40.00 Set an iron post, 3 ft. long, 1 in. dia., 28 ins. in
the ground, for 1/4 sec. cor., with brass cap mkd.