

County Surveyor's Record, Douglas County, Oregon

Subdivision of Section 5, T. 22 S., R. 8 W.

CHAINS

from which

A fir, 35 ins. diam., bears N. $24\frac{1}{2}^\circ$ E., 108 lks. dist., mkd. S5 CC BT.

A fir, 14 ins. diam., bears S. 82° W., 340 lks. dist., mkd. S5 CC BT.

From this point the N. cor. of Claim No. 49, bears N. $39^\circ 25'$ E., 3.36 chs. dist.

Continue on a blank line, over patented land.

20.35 Point for the center N 1/16 sec. cor. of sec. 5. No permanent monument established.

39.90 Point for the center $\frac{1}{4}$ sec. cor. of sec. 5, at intersection with the E. and W. center line.

Set an iron post, 28 ins. long, $2\frac{1}{2}$ ins. diam., 24 ins. in the ground, with brass cap marked

C $\frac{1}{4}$ S 5
1963

from which

A maple, 13 ins. diam., bears N. 36° E., 63 lks. dist., mkd. C $\frac{1}{4}$ S5 BT.

A fir, 16 ins. diam., bears S. 9° E., 61 lks. dist., mkd. C $\frac{1}{4}$ S5 BT.

77.93 The $\frac{1}{4}$ sec. cor. of secs. 5 and 8.

From the $\frac{1}{4}$ sec. cor. of secs. 4 and 5.


N. $89^\circ 59'$ W., on the E. and W. center line of sec. 5.

Descend 140 ft. over SW. slope, through scattering timber and dense undergrowth.

5.00 Creek, 5 lks. wide, course S. 15° E.; asc. 490 ft. over NE. slope, changing to SE. slope.

20.00 Point for closing cor., at intersection with the NE. bdy. of Claim No. 49.

Set an iron post, 28 ins. long, $2\frac{1}{2}$ ins. diam., 24 ins. in the ground, with brass cap marked



from which

A fir, 5 ins. diam., bears N. $37\frac{1}{2}^\circ$ E., 279 lks. dist., mkd. S5 CC BT.

A maple, 5 ins. diam., bears S. 56° E., 239 lks. dist., mkd. S5 CC BT.

Set a 7 ft. steel fence post, 24 ins. in the ground, alongside the iron post.

From this point the N. cor. of Claim No. 49, bears N. $40^\circ 44'$ W., 30.36 chs. dist.