

# County Surveyor's Record, Douglas County, Oregon

16607

Dependent Resurvey, Portion of Subdivisional Lines,  
T. 33 S., R. 5 W., Willamette Meridian, Oregon

16607

**CHAINS**

A madrone, 7 ins. diam., bears S. 34° E., 21 lks. dist., with decayed blaze, no marks visible.

A madrone, 7 ins. diam., bears S. 53° W., 19 lks. dist., with decayed blaze, no marks visible. (Record, S. 55° W.)

A madrone, 14 ins. diam., bears N. 75° W., 16 lks. dist., with healed blaze.

and bearing trees mkd. by Aanrud

A fir, 22 ins. diam., bears N. 50 1/2° E., 38 lks. dist., with illegible scribe marks visible on partially healed blaze. (Record, N. 53° E.)

A fir, 20 ins. diam., bears S. 86° E., 31 lks. dist., with healed blaze.

A fir, 13 ins. diam., bears S. 84° W., 81 lks. dist., with healed blaze.

A fir, 19 ins. diam., bears N. 60° W., 47 lks. dist., with healed blaze.

Land, mountainous.  
Soil, rocky clay.  
Timber, fir, pine, cedar, madrone, and oak; undergrowth, poison oak, hazel, manzanita, and young timber.

From the cor. of secs. 27, 28, 33, and 34.


S. 89° 49' W., bet. secs. 28 and 33.

Descend 250 ft. over broken SW. slope. through scattering timber and moderate undergrowth, across partially logged area.

- 3.25 Dirt road, 15 lks. wide, bears S. 70° E., and W.
- 5.00 Leave road, bears E. and N. 70° W.
- 14.25 Head of ravine, drains SW.; asc. 230 ft. over SE. slope.
- 20.40 Dirt road, 15 lks. wide, bears N. 30° E. and S. 30° W.
- 28.92 Intersect line 1-4 of St. Peters Quartz Lode, Mineral Survey No. 142.

Point for the crossing closing cor. of secs. 28 and 33 with line 1-4 of St. Peters Quartz Lode.

Set an iron post, 28 ins. long, 2 1/2 ins. diam., 24 ins. in the ground, with brass cap mkd.



from which a bearing tree of which I have no record

A white oak, 11 ins. diam., bears N. 8 1/4° W., 11 lks. dist., with scribe marks S 1 visible on opened blaze.