



# United States Department of the Interior




BUREAU OF LAND MANAGEMENT  
Oregon State Office  
P.O. Box 2965, Portland, Oregon 97208  
<http://www.blm.gov/or>

**AUG - 4 2014**

IN REPLY REFER TO:  
9632 (OR957)

## Memorandum

To: Chief, Cadastral Survey Section 1

From: Mary J.M. Hartel   
Chief, Branch of Geographic Sciences

Subject: Correction to Official Field Notes, Group 2286, Tps. 20 & 21 S., R. 9 W.,  
Willamette Meridian, Oregon

An error has been discovered on the official field notes approved April 20, 2011, in Tps. 20 & 21 S., R. 9 W., Willamette Meridian, Oregon. The headers on pages 12 to 24 have erroneously been labeled as being located in T. 20 S.

Accordingly, you are hereby authorized to prepare amended field notes that correct the headers to read T. 21 S. on pages 12 to 24 of the official field notes approved April 20, 2011, in Tps. 20 & 21 S., R. 9 W., Willamette Meridian, Oregon.

The field note record will contain a statement explaining the reason for the amendment to the official record.

For the Director  
Bureau of Land Management

**T. 21 S., R. 9 W., Willamette Meridian, Oregon**

The following amended field notes are those of the dependent resurvey of a portion of the subdivisional lines and the subdivision of section 2, Township 21 South, Range 9 West, Willamette Meridian, Oregon.

The purpose of these amended field notes is to correct an error in the field notes of the official survey approved April 20, 2011.

These amended field notes correct the header from T. 20 S., R. 9 W. to T. 21 S., R. 9 W., as authorized by memorandum from the Chief Cadastral Surveyor of Oregon, dated August 4, 2014, File 9632 (OR957), a copy of which follows these field notes.

**PAGES 22337-22349 ARE BEING REPLACED TO CORRECT THIS PROBLEM 12/23/2014 – JC, DCSO**

---

**Dependent Resurvey of a Portion of the Subdivisional Lines,  
T. 21 S., R. 9 W., Willamette Meridian, Oregon**

---

The cor. of secs. 1, 2, 11, and 12, remonumented by Peterson in 1966-67, and rehabilitated by Smalley, PLS No. 2354, in 1997; monumented with an iron post, 2 1/2 ins. diam., firmly set, with top 22 ins. below the surface of the ground, with a brass cap mkd.

T 21 S	R 9 W
S 2	S 1
S 11	S 12
1966	

from which the bearing trees mkd. by Peterson

A fir, 24 ins. diam., bears N. 3° E., 58.7 ft. dist., with a healed blaze.

A fir, 37 ins. diam., bears S. 34° W., 54.8 ft. dist., with a healed blaze.

and the bearing trees mkd. by Smalley, PLS No. 2354

A fir, 10 ins. diam., bears S. 9° E., 20.3 ft. dist., with a healed blaze.

A fir, 7 ins. diam., bears N. 26 1/2° W., 17.9 ft. dist., with a healed blaze.

An aluminum fence post with International Paper Company sign is alongside the cor.

Corner is located in the fill bank of an overgrown graveled road, 6 ft. wide, extending N. 65° E. and S. 80° W., and E., 735 ft. dist., of Scare Creek, 15 ft. wide, course N. 5° W., near W. edge of bottom land, 200 ft. wide.

---

**Subdivision of Section 2,  
T. 21 S., R. 9 W., Willamette Meridian, Oregon**

The 1/4 sec. cor. of secs. 1 and 2, remonumented by Peterson in 1966-67, and rehabilitated by Baker, PLS No. 1978, in 1990; monumented with an iron post, 2 1/2 ins. diam., firmly set, projecting 4 ins. above ground, with a brass cap mkd.

1/4  
S 2 | S 1  
T 21 S R 9 W  
1967

from which the remains of the original bearing trees

A decayed fir pile, size indeterminate, bears S. 85° E., 5.9 ft. dist., with scribe marks 1/4 S visible on detached remains.

A decayed fir pile, size indeterminate, bears S. 67° W., 7.3 ft. dist., no marks visible.

and the remains of a bearing tree mkd. by Peterson

A shattered decayed fir stump, size indeterminate, bears S. 54° E., 15.2 ft. dist., no marks visible.

and the bearing trees mkd. by Baker, PLS No. 1978

A fir, 45 ins. diam., bears S. 15 1/2° E., 30.4 ft. dist., with a healed blaze and nail left side center.

A fir, 18 ins. diam., bears S. 88° W., 17.5 ft. dist., with a healed blaze and nail right side center. A second fir is growing from the same base to the S.

An aluminum fence post with International Paper Company sign is alongside the cor.

Corner is located N., 370 ft. dist., of a creek, 4 ft. wide, course W., on the N edge of bottom land, 20 ft. wide.

---

**Subdivision of Section 2,  
T. 21 S., R. 9 W., Willamette Meridian, Oregon**

The N 1/16 sec. cor. of secs. 1 and 2, established by Peterson in 1966-67, and rehabilitated by Baker, PLS No. 1978, in 1990; monumented with an iron post, 2 1/2 ins. diam., firmly set, projecting 1 in. above ground, with a brass cap mkd.

N 1/16  
S 2 | S 1  
1967

from which the remains of a bearing tree mkd. by Peterson

A roothole bears N. 46° E., 11.2 ft. dist., alongside of which is a down fir, 22 ins. diam., with a healed blaze.

and the remains of the bearing trees mkd. by Baker, PLS No. 1978

A fir snag, 21 ins. diam., bears S. 64 3/4° E., 33.3 ft. dist., with a healed blaze.

A fir, 36 ins. diam., bears N. 78 1/2° W., 73.2 ft. dist., with a healed blaze.

and a new bearing tree

A hemlock, 26 ins. diam., bears S. 57 1/2° E., 26.0 ft. dist., mkd. N1/16 S1 BT.

An aluminum fence post with International Paper Company sign is alongside the cor.

---

**Subdivision of Section 2,  
T. 21 S., R. 9 W., Willamette Meridian, Oregon**

The 1/16-80 sec. cor. of secs. 1 and 2, established by Peterson in 1966-67, and utilized by Baker, PLS No. 1978, in 1990; monumented with an iron post, 2 1/2 ins. diam., firmly set, projecting 3 ins. above ground, with a brass cap mkd.

1/16  
S 2 | S 1  
80  
1967

from which the remains of the bearing trees mkd. by Peterson

A fir, 63 ins. diam., bears N. 85° E., 35.0 ft. dist., with a healed blaze.

A decayed fir high stump, 30 ins. diam., bears S. 75° W., 16.5 ft. dist., with a healed blaze on detached pieces of bark. Add scribe marks BT at breast height.

and a new bearing tree

A fir, 16 ins. diam., bears S. 82° W., 12.2 ft. dist., mkd. 1/16-80 S2 BT. Tree leans slightly S.

An aluminum fence post with International Paper Company sign is alongside the cor.

Corner is located S., 115 ft. dist., of a boulder, 30 x 30 x 30 ft.

---

**Subdivision of Section 2,  
T. 21 S., R. 9 W., Willamette Meridian, Oregon**

The 1/16-100 sec. cor. of secs. 1 and 2, established by Peterson in 1966-67; monumented with an iron post, 2 1/2 ins. diam., firmly set, tilted N., with top 3 ins. below the surface of the ground, with a brass cap mkd.

1/16  
S 2 | S 1  
100  
1967

from which the remains of a bearing tree mkd. by Peterson

A fir stump, 71 ins. diam., bears S. 21 1/2° W., 46.9 ft. dist., no marks visible.  
(Record, S. 27° W.)

and new bearing trees

A cedar, 37 ins. diam., bears S. 58 1/2° E., 36.1 ft. dist., mkd. 1/16-100 S1 BT on root.

A fir, 7 ins. diam., bears S. 77 1/2° W., 30.5 ft. dist., mkd. X BT.

Corner is located N., 130 ft. dist., of creek, 2 ft. wide, course S. 55° W.

---

**Subdivision of Section 2,  
T. 21 S., R. 9 W., Willamette Meridian, Oregon**

The 1/4 sec. cor. of secs. 2 and 11, reestablished by proportionate measurement by Peterson in 1966-67; monumented with an iron post, 2 1/2 ins. diam., firmly set, projecting 2 ins. above ground, with a brass cap mkd.

S 2  
1/4 ———  
S 11  
T 21 S R 9 W  
1967

from which the bearing tree mkd. by Peterson

A fir, 28 ins. diam., bears S. 61° E., 4.6 ft. dist., with a healed blaze.

and a new bearing tree

A fir, 25 ins. diam., bears N. 23° W., 11.9 ft. dist., mkd. 1/4 S2 BT.

Corner is located at the base of a boulder, 3 ft. high, 6 ft. wide.

---

**Subdivision of Section 2,  
T. 21 S., R. 9 W., Willamette Meridian, Oregon**

The W 1/16 sec. cor. of secs. 2 and 11, established by Peterson in 1966-67; monumented with an iron post, 2 1/2 ins. diam., firmly set, tilted W., projecting 8 ins. above ground, with a brass cap mkd.

S 2  
W 1/16 ———  
S 11  
1967

from which the remains of the bearing trees mkd. by Peterson

A decayed fir stump, 36 ins. diam., bears S. 52° W., 66.2 ft. dist., no marks visible.  
(Record, 68.0 ft. dist.)

A decayed fir stump, 17 ins. diam., bears N. 59° W., 97.7 ft. dist., with the bottom of a decayed healed blaze.

and new bearing trees

A fir, 20 ins. diam., bears S. 12 1/2° W., 30.7 ft. dist., mkd. W1/16 S11 BT.

A fir, 16 ins. diam., bears N. 14° W., 25.4 ft. dist., mkd. W1/16 S2 BT.

Corner is located in the steep cutbank on the E side of a graveled road, 15 ft. wide, extending N. and S.

---

**Subdivision of Section 2,  
T. 21 S., R. 9 W., Willamette Meridian, Oregon**

The cor. of secs. 2, 3, 10, and 11, remonumented by McDonald in 1963, and rehabilitated by Peterson in 1966-67; monumented with an iron post, 2 1/2 ins. diam., firmly set, projecting 7 ins. above ground, with a brass cap mkd.

T 21 S	R 9 W
S 3	S 2
S 10	S 11
1963	

from which the remains of the original bearing trees

- A roothole bears S. 41° E., 26.4 ft. dist., alongside of which is a down fir, 45 ins. diam., with a healed blaze.
- A decayed fir pile, size indeterminate, bears N. 44° W., 27.7 ft. dist., no marks visible.

and the remains of a bearing tree mkd. by McDonald

- A very decayed shattered fir stump, size indeterminate, bears S. 72 1/2° E., 12.5 ft. dist., alongside of which is a down decayed fir, size indeterminate, with remains of a healed blaze on detached remains.

and new bearing trees

- A fir, 13 ins. diam., bears N. 9 1/4° E., 24.9 ft. dist., mkd. T21S R9W S2 BT.
  - A fir, 20 ins. diam., bears S. 60 1/4° E., 59.1 ft. dist., mkd. T21S R9W S11 BT.
  - A fir, 13 ins. diam., bears S. 76° W., 42.3 ft. dist., mkd. T21S R9W S10 BT. Mag Nail on left side center.
  - A fir, 27 ins. diam., bears N. 6 3/4° W., 50.1 ft. dist., mkd. T21S R9W S3 BT.
-

**Subdivision of Section 2,  
T. 21 S., R. 9 W., Willamette Meridian, Oregon**

The S 1/16 sec. cor. of secs. 2 and 3, established by Peterson in 1966-67; monumented with an iron post, 2 1/2 ins. diam., firmly set, with top flush with the surface of the ground, with a brass cap mkd.

S 1/16  
S 3 | S 2  
1967

from which the remains of a bearing tree mkd. by Peterson

A decayed fir stump, 53 ins. diam., bears N. 65 1/2° W., 106.3 ft. dist., with a healed blaze. (Record, N. 69° W.)

and new bearing trees

A fir, 32 ins. diam., bears S. 68 1/2° E., 27.5 ft. dist., mkd. S1/16 S2 BT.

A fir, 24 ins. diam., bears N. 82° W., 26.9 ft. dist., mkd. S1/16 S3 BT.

Corner is located on N edge of overgrown skid road, 6 ft. wide, extending S. 85° E. and N. 85° W.

---

**Subdivision of Section 2,  
T. 21 S., R. 9 W., Willamette Meridian, Oregon**

The 1/4 sec. cor. of secs. 2 and 3, remonumented by McDonald in 1963, utilized by Peterson in 1966-67, and rehabilitated by the Douglas County Surveyor in 1971; monumented with an iron post, 2 1/2 ins. diam., firmly set, with top 2 ins. below the surface of the ground, with a brass cap, oriented NE., mkd.

T 21 S R 9 W  
1/4  
S 3 | S 2  
1963

from which the remains of an original bearing tree

A decayed fir stump, 64 ins. diam., bears N. 20 1/4° W., 60.1 ft. dist., no marks visible.

and the remains of a bearing tree mkd. by the Douglas County Surveyor

A decayed maple stump, size indeterminate, bears S. 78 3/4° E., 38.7 ft. dist., no marks visible.

and new bearing trees

A fir, 20 ins. diam., bears S. 74 1/4° E., 34.0 ft. dist., mkd. 1/4 S2 BT.

A fir, 12 ins. diam., bears S. 85 1/2° W., 73.1 ft. dist., mkd. 1/4 S3 BT.

A steel fence post, broken off, found lying loose NE., 10 ft. dist.

Corner is located on the N. edge of a triangular shaped stand of alder, 150 ft. wide by 150 ft. long, bounded to the SE. by an abandoned graveled road, 10 ft. wide, extending N. 55° E. and S. 75° W., and to the SW. by a graveled road, 12 ft. wide, extending N. 35° W. and S. 10° E.

---

**Subdivision of Section 2,  
T. 21 S., R. 9 W., Willamette Meridian, Oregon**

**Subdivision of Section 2,  
T. 21 S., R. 9 W., Willamette Meridian, Oregon**

---

Point for the center 1/4 sec. cor. of sec. 2, at intersection of the N. and S. and the E. and W. center lines.

Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 22 ins. in the ground, with brass cap mkd.

T 21 S R 9 W  
C 1/4 S 2  
2010

from which

A fir, 12 ins. diam., bears N. 50 3/4° E., 29.0 ft. dist., mkd. C1/4 S2 BT.

A fir, 12 ins. diam., bears S. 63° W., 18.1 ft. dist., mkd. X BT, with Mag Nail left side center.

Deposit a magnet in a white plastic case at the base of the stainless steel post.

Corner is located E., 1 1/2 ft. dist., of a fir, 1 ft. diam., and E., 60 ft. dist., of draw, drains N. 25° W.

From this cor., a point established by person(s) unknown, bears N. 63° 50' 04" W., 3.50 ft. dist., determined at record distances from the faces of the remains of the bearing trees mkd. by person(s) unknown utilizing information documented on a corner card held at the BLM Coos Bay District Office

A burned cedar stump, 42 ins. diam., bears N. 50 3/4° E., 27.2 ft. dist., no marks visible.

A burned fir stump with metal cap, 54 ins. diam., bears S. 14 1/2° W., 12.4 ft. dist., no marks visible.

There is no filed survey or other known record documenting who established this point or how it was established, therefore this point was not utilized for control during this survey.

---

**Subdivision of Section 2,  
T. 21 S., R. 9 W., Willamette Meridian, Oregon**

Point for the center W 1/16 sec. cor. of sec. 2.

Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 24 ins. in the ground, with brass cap mkd.

$$\begin{array}{c} \text{W 1/16} \\ \text{C} \text{-----} \text{C} \\ \text{S 2} \\ \text{2010} \end{array}$$

from which

A fir, 13 ins. diam., bears N. 86° E., 18.6 ft. dist., mkd. CW1/16 S2 BT.

A fir, 9 ins. diam., bears S. 3 1/4° W., 38.9 ft. dist., mkd. X BT.

Deposit a magnet in a white plastic case at the base of the stainless steel post.

Corner is located W., 495 ft. dist., of a spur, 15 ft. high, 35 ft. wide, slopes N. 20° E., between a creek to W., 2 ft. wide, course N. 30° E., and a creek to E., 2 ft. wide, course N.

From this cor., a point established by person(s) unknown, bears N. 41° 55' 56" W., 3.50 ft. dist., monumented with an iron pipe, 1/2 in. diam., firmly set, projecting 7 ins. above ground, from which the remains of the bearing trees mkd. by person(s) unknown

A decayed fir stump, 27 ins. diam., bears N. 56 1/4° E., 37.4 ft. dist., no marks visible.

A decayed fir stump, 27 ins. diam., bears S. 1 1/4° W., 13.7 ft. dist., no marks visible.

There is no filed survey or other known record documenting who established this point or how it was established, therefore this point was not utilized for control during this survey.

---

**Subdivision of Section 2,  
T. 21 S., R. 9 W., Willamette Meridian, Oregon**

Point for the SW 1/16 sec. cor. of sec. 2, at its calculated position.

Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 23 ins. in the ground, with brass cap mkd.

SW 1/16 S 2  
2010

from which

A maple, 21 ins. diam., bears N. 71 1/2° E., 19.8 ft. dist., mkd. SW1/16 S2 BT.

A fir, 20 ins. diam., bears S. 76° W., 28.2 ft. dist., mkd. SW1/16 S2 BT.

Deposit a magnet in a white plastic case at the base of the stainless steel post.

Corner is located E., 110 ft. dist., of a graveled road, 10 ft. wide, extending N. 40° E. and S. 25° W., and S., 110 ft. dist., of the same road, extending N. 50° E. 100 ft. to a three-way junction and S. 50° W.; also S., 220 ft. dist., of an abandoned dirt road, 8 ft. wide, extending N. 50° W. and S. 75° E. 100 ft. to the same three-way junction.

From this cor., a point established by person(s) unknown, bears S. 44° 17' 03" W., 5.04 ft. dist., monumented with an iron pipe, 1 in. diam., firmly set, projecting 8 ins. above ground, from which the remains of a bearing tree mkd. by person(s) unknown

A very decayed metal-capped fir stump, 34 ins. diam., bears N. 15 3/4° W., 14.9 ft. dist., no marks visible.

There is no filed survey or other known record documenting who established this point or how it was established, therefore this point was not utilized for control during this survey.

---