

**UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT**

FIELD NOTES  
OF THE  
DEPENDENT RESURVEY OF PORTIONS OF THE EAST BOUNDARY,  
WEST BOUNDARY, SUBDIVISIONAL LINES,  
AND SUBDIVISION OF SECTION LINES OF SECTIONS 9, 11, AND 15,  
AND THE SUBDIVISION OF SECTIONS 2, 10, AND 13,  
TOWNSHIP 26 SOUTH, RANGE 2 WEST,  
OF THE WILLAMETTE MERIDIAN,  
IN THE STATE OF OREGON

---

**EXECUTED BY**

***Jeffrey O. Covington, Cadastral Surveyor***

Under Special Instructions approved May 24, 2018,  
which provided for the surveys included under Group No. 2923,  
and Assignment Instructions dated May 24, 2018.

***Survey commenced July 16, 2018***

***Survey completed March 31, 2020***

**T. 26 S., R. 2 W., Willamette Meridian, Oregon**

FEET	
	<p>The following field notes are those of the dependent resurvey of portions of the east boundary, west boundary, subdivisional lines, and subdivision of section lines of sections 9, 11, and 15, and the subdivision of sections 2, 10, and 13, Township 26 South, Range 2 West, Willamette Meridian, Oregon.</p> <p>The history of the official surveys pertaining to this survey is as follows:</p> <p>In 1855, Addison R. Flint, U.S. Deputy Surveyor, surveyed the east boundary of T. 26 S., R. 3 W., as shown on the official plat of survey approved December 10, 1855.</p> <p>In 1883, John A. McQuinn, U.S. Deputy Surveyor, surveyed the north and east boundaries of the township and a portion of the subdivisional lines, as shown on the official plat of survey approved April 7, 1884.</p> <p>In 1900, Hezekiah H. Johnson, U.S. Deputy Surveyor, retraced the north boundary of T. 26 S., R. 2 W., as shown on the official plat of survey of T. 25 S., R. 2 W., approved May 6, 1901, and accepted March 7, 1902.</p> <p>In 1910, Fred Mensch, U.S. Deputy Surveyor, resurveyed the west boundary of T. 26 S., R. 1 W., as shown on the official plat of survey approved November 11, 1911.</p> <p>In 1913-14, Charles M. Collier, U.S. Surveyor, reestablished portions of the exterior boundaries of the township, as shown on the official plat of survey approved June 21, 1917.</p> <p>In 1916-1918, Fred Mensch, U.S. Cadastral Engineer, dependently resurveyed a portion of the subdivisional lines and surveyed Tract No. 37, as shown on the official plat of survey approved January 4, 1919.</p> <p>In 1959, Irving Zirpel, Jr., and William W. Glenn, Cadastral Surveyors, dependently resurveyed portions of the north boundary, west boundary, and subdivisional lines, and subdivided sections 15 and 17, as shown on the official plat of survey accepted August 29, 1960.</p> <p>In 1962-63, C. Albert White, Cadastral Surveyor, and Donald R. Beck and Patrick J. Reynolds, Surveying Technicians, dependently surveyed a portion of the east boundary and subdivisional lines, and subdivided section 1 of T. 26 S., R 3 W., as shown on the official plat of survey accepted November 19, 1964.</p> <p>In 1968, Lynn M. Roseberry, Cadastral Surveyor, dependently resurveyed a portion of the east boundary and subdivisional lines, as shown on the official plat of survey accepted May 12, 1970.</p> <p>In 1972-75, Daniel L. Berry, Harvey E. Woffard, and G. Steven Popken, Cadastral Surveyors, and Glen S. Baughman, Registered Land Surveyor Number 536, under contract number 52500-CT5-1116, dependently resurveyed a portion of the north boundary of T. 26 S., R. 2 W., as shown on the official plat of survey in T. 25 S., R. 2 W., accepted March 7, 1977. Plat suspended June 16, 1998, and suspension lifted January 9, 2001.</p>

## T. 26 S., R. 2 W., Willamette Meridian, Oregon

FEET

In 1975, G. Stephen Popken, Cadastral Surveyor, dependently resurveyed a portion of the subdivisional lines and subdivided section 23, as shown on the official plat of survey accepted June 23, 1978.

In 1979, Wayne L. Rogers, Cadastral Surveyor, dependently resurveyed a portion of the subdivisional lines and subdivided section 9, as shown on the official plat of survey accepted June 16, 1983.

In 1992-95, Dale T. Bedell and Brian S. Seibold, Cadastral Surveyors, and Robert H. Browning, Surveying Technician, dependently resurveyed a portion of the subdivisional lines and subdivided section 11, as shown on the official plat of survey accepted June 3, 1997.

In 1995-98, Brian S. Seibold, Cadastral Surveyor, and Robert H. Browning, Surveying Technician, dependently resurveyed a portion of the south boundary of T. 25 S., R. 2 W., as shown on the official plat of survey accepted August 4, 2000.

In 2002, Timothy J. Moore, Cadastral Surveyor, and Robert H. Browning, Surveying Technician, rehabilitated certain corner points as described in the official field notes approved November 3, 2004.

In 2010-11, A. Bert Skeesick, Cadastral Surveyor, dependently resurveyed a portion of the south boundary of T. 25 S., R. 2 W., as shown on the official plat of survey accepted December 27, 2011.

In 2018-20, Jeffrey O. Covington, Cadastral Surveyor, dependently resurveyed a portion of the north boundary, as shown on the official plat of survey accepted March 24, 2021.

The following local surveys (M) and county surveyor files (CS), filed in the Douglas County Surveyor's Office are referred to in subsequent corner descriptions and are referenced by surveyor's last name, official title, or Professional Land Surveyor (PLS) No., Professional Engineer (PE) No., and year.

<u>Date</u>	<u>Name and Registration Number</u>	<u>File Number</u>
06/1959	G. R. Lecklider, PE No. 4079	M11-31
12/1959	G. R. Lecklider, PE No. 4079	M16-68
04/1961	Milo Godfrey, Douglas County Deputy Surveyor	CS52/77
10/1961	Milo Godfrey, Douglas County Deputy Surveyor	CS52/77
1963	Milo Godfrey, Douglas County Deputy Surveyor	CS52/77
1967	Douglas County Surveyor's Office	CS54/40-56
1969	Don E. Garrett, PLS No. 544	CS55/111-1
1972	Don E. Garrett, PLS No. 544	M47-7
1975	Glenn S. Baughman, PLS No. 536	M56-17
1977	Frank O. Williams, PLS No. 875	CS58/8-48
1978	Douglas County Surveyor's Office	CS59/46-14
1984	Maurice E. Farr, PLS No. 1181	CS62/15-17
11/1984	Larry E. Monrean, PLS No. 1830	CS62/21-9
12/1984	Larry E. Monrean, PLS No. 1830	CS62/21-10

## T. 26 S., R. 2 W., Willamette Meridian, Oregon

FEET	Date	Name and Registration Number	File Number
	1985	Larry E. Monrean, PLS No. 1830	CS62/29-6
	1987	Larry E. Monrean, PLS No. 1830	CS62/40-15
	1992	Randall W. Smith, PLS No. 2469	CS64/23-14
	1999	Ken W. Hoffine, PLS 2291	M133-59
	2004	Larry E. Monrean, PLS No. 1830	CS65/49-36
	2004	Larry E. Monrean, PLS No. 1830	M144-47
			CS65/49-34 A-F
	2005	Randall W. Smith, PLS No. 2469	CS67/10-24
	2006	Kevin B. Schinnell, PLS No. 65372	M149-35
	2007	Ken W. Hoffine, PLS 2291	M153-43
	2009	David A. Edwards, PLS No. 2339	M159-66
	2011	Gregory D. Lang, PLS No. 2295	M162-46
	04/2015	Ken W. Hoffine, PLS 2291	CS65/89-19
	09/2015	Ken W. Hoffine, PLS 2291	CS65/89-45
	2016	Ken W. Hoffine, PLS 2291	CS65/93-63
<p>The survey was executed in accordance with the specification set forth in the <u>Manual of Surveying Instructions</u> (2009), and the special instructions approved May 24, 2018, for Group No. 2923, Oregon.</p>			
<p>The directions of the lines are based on the true meridian as determined by Global Positioning System (GPS) techniques and direct solar observations and carried forward by sustained angulation using conventional survey techniques. All measurements along the lines were derived through the use of electronic measuring equipment. Measured distances and directions have been adjusted by computer software that incorporates a least squares adjustment routine. The adjusted mean bearings and mean horizontal ground elevation distances are reported to the nearest second and 0.01 foot.</p>			
<p>Preliminary to the resurvey the lines of the official original surveys and resurveys were retraced and search was made for all corners, lines, other calls of the record, and, where available, collateral evidence of local surveys and corners. Identified corners were perpetuated in their original positions. The retracement data was thoroughly verified and only the true line field notes are given herein.</p>			
<p>Each new bearing tree has a 2 1/2 inch x 1/4 inch magnetic nail (Mag Nail) driven at the base on right side center and each monument established or reestablished has a magnet deposited in a white plastic case at the base of the stainless steel post, unless otherwise noted in the corner description. Aluminum angle irons were driven alongside each monument unless a similar marker was already in place.</p>			
<p>Only those lines bounding Federal interest land were blazed.</p>			
<p>The geographic position in NAD 1983 (2011) of the following corners as determined by ties from temporary GPS control points, established utilizing dual frequency, carrier phase GPS receivers, and processed using the National Geodetic Survey's Online Positioning User Service (OPUS):</p>			

**T. 26 S., R. 2 W., Willamette Meridian, Oregon**

FEET

The corner of sections 1 and 12 only, on the east boundary of the township:

Latitude: 43° 19' 44.94" N. Longitude: 122° 52' 25.58" W.

The corner of sections 1, 6, 7, and 12, on the west boundary of the township:

Latitude: 43° 19' 44.75" N. Longitude: 122° 59' 28.27" W.

The corner of sections 13, 14, 23, and 24:

Latitude: 43° 17' 58.20" N. Longitude: 122° 53' 35.43" W.

The corner of sections 2, 3, 10, and 11:

Latitude: 43° 19' 42.06" N. Longitude: 122° 54' 45.53" W.

The corner of sections 15 and 22 only, identical with corner number 8 of Tract 37:

Latitude: 43° 17' 56.87" N. Longitude: 122° 55' 58.23" W.

The corner of sections 10, 11, 14, and 15:

Latitude: 43° 18' 49.71" N. Longitude: 122° 54' 45.90" W.

The corner of sections 8, 9, 16, and 17:

Latitude: 43° 18' 47.75" N. Longitude: 122° 57' 05.53" W.

The corner of sections 4, 5, 8, and 9:

Latitude: 43° 19' 43.09" N. Longitude: 122° 57' 04.25" W.

The corner of sections 5, 6, 7, and 8:

Latitude: 43° 19' 37.77" N. Longitude: 122° 58' 13.97" W.

The 1/4 section corner of sections 9 and 10:

Latitude: 43° 19' 16.01" N. Longitude: 122° 55' 55.82" W.

---

**Dependent Resurvey of a Portion of the East Boundary,  
T. 26 S., R. 2 W., Willamette Meridian, Oregon**

---

Restoring the survey by McQuinn in 1883, the resurvey by Mensch in 1910,  
the resurvey by Collier in 1913-14, the resurvey by Roseberry in 1968,  
and the resurvey by Skeesick in 2010-11

---

**Dependent Resurvey of a Portion of the East Boundary,  
T. 26 S., R. 2 W., Willamette Meridian, Oregon**

FEET	
	<p>Beginning at the cor. of secs. 13 and 24 only, reported by Mensch in 1916-18; perpetuated by Godfrey, Douglas County Deputy Surveyor, in 1963; subsequently perpetuated by Monrean, PLS No. 1830, in November, 1984; monumented with an iron post, 1 in. diam., firmly set, projecting 15 ins. above ground, in a mound of stone, 2 ft. base, 12 ins. high, with a brass cap mkd.</p> <p style="text-align: center;">COUNTY SURVEYORS OFFICE T 26 S R S 13   2 ———   R 1 W W S 24   1963</p> <p>from which the remains of the bearing trees reported by Mensch</p> <p style="padding-left: 40px;">A fir snag, 23 ins. diam., bears S. 27 1/4° W., 7.9 ft. dist., with no marks visible on open decayed blaze. (Original) (Record, S. 14° W.)</p> <p style="padding-left: 40px;">A fir, 33 ins. diam., bears N. 71 1/2° W., 9.2 ft. dist., with a healed blaze. (Original) (Record, N. 60° W.)</p> <p>and a bearing tree mkd. by Godfrey</p> <p style="padding-left: 40px;">A fir, 13 ins. diam., bears S. 60.3/4° W., 12.5 ft. dist., with a healed blaze.</p> <p>and the remains of a bearing tree mkd. by Monrean</p> <p style="padding-left: 40px;">A roothole bears N. 9 3/4° W., 15.9 ft. dist., alongside of which is a down hemlock, 12 ins. diam., with a healed blaze.</p> <p>N. 1° 19' 36" E., bet. secs. 13 and 18.</p>
1333.34	<p>Point for the S 1/16 sec. cor. of sec. 13 only, on the E. bdy. of the Tp.</p> <p>Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 26 ins. in the ground, with brass cap mkd.</p> <p style="text-align: center;">S 1/16   S 13   2018</p> <p>from which</p> <p style="padding-left: 40px;">A hemlock, 12 ins. diam., bears S. 30 1/2° W., 13.5 ft. dist., mkd. X BT.</p> <p style="padding-left: 40px;">A hemlock, 15 ins. diam., bears N. 61 1/4° W., 17.7 ft. dist., mkd. S1/16 S13 BT.</p>
2545	<p>Graveled road, 8 ft. wide, bears S. 40° E. and N. 65° W.</p>
2353.33	<p>The 1/4 sec. cor. of sec. 18 only, on the W. bdy. of T. 26 S., R. 1 W., reestablished by proportionate measurement by Garrett, PLS No. 544, in 1972. There is no remaining evidence of the original cor., therefore this point is</p>

**Dependent Resurvey of a Portion of the East Boundary,  
T. 26 S., R. 2 W., Willamette Meridian, Oregon**

FEET	
	<p>accepted as a careful and faithful reestablishment of the cor.; monumented with an iron post, 2 1/2 ins. diam., firmly set, with top flush with the surface of the ground, with a brass cap mkd.</p> <p align="center">           T 26 S              1/4 S 18            R 2 W   R 1 W            1972            RPLS 544         </p> <p>from which the bearing trees mkd. by Garrett</p> <p>A fir snag, 25 ins. diam., bears N. 31 1/2° E., 58.5 ft. dist., with a healed blaze.</p> <p>A fir, 30 ins. diam., bears S. 23° E., 60.1 ft. dist., with a healed blaze.</p> <p>and a new bearing tree</p> <p>A cedar, 6 ins. diam., bears N. 55 3/4° E., 24.1 ft. dist., mkd. X BT.</p> <hr/> <p>N. 1° 19' 15" E., beginning new measurement.</p>
313.35	<p>The 1/4 sec. cor. of sec. 13 only, reestablished by proportionate measurement by Garrett, PLS No. 544, in 1972; perpetuated by Farr, PLS No. 1181, in 1984; subsequently perpetuated by Smith, PLS No. 2469, in 1992. There is no remaining evidence of the original cor., therefore this point is accepted as a careful and faithful reestablishment of the cor.; monumented with an iron post, 2 1/2 ins. diam., firmly set, with top 4 ins. below the surface of the ground, with a brass cap mkd.</p> <p align="center">           T 26 S            1/4 S 13              R 2 W   R 1 W            RPLS 544            1972         </p> <p>from which a bearing tree mkd. by Farr</p> <p>A fir, 14 ins. diam., bears N. 80 1/2° E., 116.5 ft. dist., with a healed blaze.</p> <p>and a bearing tree mkd. by Smith</p> <p>A willow, 32 ins. diam., bears N. 1° W., 31.9 ft. dist., no marks visible.</p> <p>and a new bearing tree</p> <p>A maple, 9 ins. diam., bears S. 37 1/2° W., 25.2 ft. dist., mkd. X BT on bark.</p>

Dependent Resurvey of a Portion of the East Boundary,  
T. 26 S., R. 2 W., Willamette Meridian, Oregon

FEET	
	<p>Corner is located in a bamboo thicket, E., 1.0 ft. dist., of a boulder, 3 x 6 x 6 ft. A metal t-post is alongside the cor., with Forest Service signs Nos. 54-2 and 54-4 attached.</p>
	<p>From the cor. of secs. 1 and 12 only, reported by Roseberry in 1968; perpetuated by Monrean, PLS No. 1830, in 1987; monumented with an iron post, 1 in. diam., firmly set, projecting 12 ins. above ground, in a mound of stone, 3 ft. base, to the top, with a brass cap mkd.</p>
	<p style="text-align: center;">COUNTY SURVEYORS OFFICE T 26 S R 2 W S 1   -----  S 12   1961</p>
	<p>from which the remains of the bearing trees reported by Roseberry</p>
	<p>A roothole bears S. 72° W., 29.0 ft. dist., alongside of which is a down fir, 36 ins. diam., no marks visible. (Original)</p>
	<p>A cedar, 17 ins. diam., bears S. 81 1/2° W., 8.3 ft. dist., with a healed blaze.</p>
	<p>A fir, 24 ins. diam., bears N. 33° W., 21.5 ft. dist., with a healed blaze. (Original)</p>
	<p>and the bearing trees mkd. by Monrean</p>
	<p>A cedar, 5 ins. diam., bears S. 47 1/2° W., 30.9 ft. dist., with illegible scribe marks visible on partially healed blaze.</p>
	<p>A cedar, 24 ins. diam., bears N. 58 1/4° W., 26.5 ft. dist., with a healed blaze.</p>
	<p>N. 0° 52' 33" E., bet. secs. 1 and 6.</p>
	<p>20 Creek, 1 ft. wide, course N. 80° E.</p>
	<p>505 Creek, 3 ft. wide, course S. 45° E.</p>
	<p>2328.38 The 1/4 sec. cor. of sec. 6 only, on the W. bdy. of the T. 26 S., R. 1 W., monumented with the remains of the original cor. tree, a fir stump, 33 ins. diam., with a healed blaze on the east face, and axe marks on the north and south faces, from which the remains of an original bearing tree</p>
	<p>A hemlock snag, 10 ins. diam., bears S. 31° E., 13.2 ft. dist., with scribe marks 4 visible on partially healed blaze. (Original)</p>
	<p>At the corner point</p>



**Dependent Resurvey of a Portion of the East Boundary,  
T. 26 S., R. 2 W., Willamette Meridian, Oregon**

FEET	
	<p>Saw the cor. tree stump flush with the surface of the ground and drive an iron rod, 30 ins. long, 5/8 in. diam., 26 ins. in the center of the stump, with aluminum cap mkd.</p> <p align="center">           T 26 S            R 2 W R 1 W                    1/4                    S 6            2019         </p> <p>from which new reference monuments</p> <p>An iron rod, 30 ins. long, 5/8 in. diam., driven 27 ins. in the ground, for a reference monument, bears N. 48° 01' 55" E., 13.78 ft. dist., with aluminum cap mkd. RM1 T26S R1W S6 13.78 FT TO COR 2019 and an arrow pointing to the cor.</p> <p>An iron rod, 30 ins. long, 5/8 in. diam., driven 30 ins. in the ground, for a reference monument, bears S. 50° 17' 06" E., 12.09 ft. dist., with aluminum cap mkd. RM2 T26S R1W S6 12.09 FT TO COR 2019 and an arrow pointing to the cor.</p> <p>The sawed cor. tree stump is laying alongside the cor., with scribe marks S6 visible on opened healed blaze.</p> <hr/> <p>N. 0° 25' 56" W., beginning new measurement.</p>
343.99	<p>The 1/4 sec. cor. of sec. 1 only, perpetuated by Godfrey, Douglas County Deputy Surveyor, in April, 1961; from original evidence no longer in existence; monumented with an iron pipe, 1 1/4 ins. diam., firmly set, projecting 12 ins. above ground, in a collar of stone, with a brass cap mkd.</p> <p align="center">           COUNTY SURVEYORS OFFICE            T 26 S R 2 W            S 1   1/4            1961         </p> <p>from which the remains of the bearing trees mkd. by Godfrey</p> <p>A decayed living hemlock, 16 ins. diam., bears N. 35 3/4° E., 7.8 ft. dist., with scribe marks E1/4 S1 CS visible on partially healed blaze.</p> <p>A hemlock snag, 13 ins. diam., bears S. 53 3/4° E., 11.5 ft. dist., with scribe marks BT visible on partially healed blaze.</p> <p>and new bearing trees</p> <p>A fir, 13 ins. diam., bears S. 69 1/4° W., 33.2 ft. dist., mkd. 1/4 S1 BT.</p> <p>A fir, 7 ins. diam., bears N. 52 1/2° W., 15.5 ft. dist., mkd. X BT.</p> <hr/>

**Dependent Resurvey of a Portion of the East Boundary,  
T. 26 S., R. 2 W., Willamette Meridian, Oregon**

FEET	N. 0° 27' 57" E., beginning new measurement.															
245	Dirt road, 8 ft. wide, bears S. 5° E. and N. 15° W.															
2576.35	The cor. of Tps. 25 and 26 S., R. 2 W., reported by Skeesick in 2010-11, monumented with an iron post, 1 1/4 ins. diam. (Record, 2 ins. diam.), firmly set, projecting 16 ins. above ground, in a mound of stone, 2 ft. base, 12 ins. high, with a brass cap mkd.															
	<p>COUNTY SURVEYORS OFFICE</p> <table style="margin: auto; border-collapse: collapse;"> <tr> <td style="padding: 2px 5px;">T 25 S</td> <td style="padding: 2px 5px;">R</td> <td style="padding: 2px 5px;">R</td> </tr> <tr> <td style="padding: 2px 5px;">S 36</td> <td style="padding: 2px 5px;">2</td> <td style="padding: 2px 5px;">1</td> </tr> <tr> <td colspan="2" style="border-top: 1px solid black; padding: 2px 5px;">S 1 W</td> <td style="padding: 2px 5px;">W</td> </tr> <tr> <td colspan="3" style="padding: 2px 5px;">T 26 S</td> </tr> <tr> <td colspan="3" style="padding: 2px 5px;">1966</td> </tr> </table>	T 25 S	R	R	S 36	2	1	S 1 W		W	T 26 S			1966		
T 25 S	R	R														
S 36	2	1														
S 1 W		W														
T 26 S																
1966																
	from which the remains of the bearing trees reported by Skeesick															
	A fir, 45 ins. diam., bears S. 87 1/4° E., 76.6 ft. dist., no marks visible. (Original)															
	A pine snag, 37 ins. diam., bears S. 44° E., 29.7 ft. dist., no marks visible. (Original)															
	A hemlock, 32 ins. diam., bears S. 51 3/4° W., 7.9 ft. dist., with a healed blaze.															
	A pine snag, 35 ins. diam., bears S. 60° W., 43.6 ft. dist., with a healed blaze. (Original)															
	A fir, 12 ins. diam., bears N. 57 3/4° W., 27.2 ft. dist., with a healed blaze.															
	<hr/> <p><b>Dependent Resurvey of a Portion of the West Boundary, T. 26 S., R. 2 W., Willamette Meridian, Oregon</b></p> <hr/>															
	<p>Restoring the survey by Flint in 1855, the resurvey by Collier in 1913-14, the resurvey by Zirpel, Jr., and Glenn in 1959, and the resurvey by White, Beck, and Reynolds in 1962-63</p> <hr/>															
	From the cor. of secs. 1, 6, 7, and 12, reported by White, Beck, and Reynolds in 1962-63; perpetuated by the Douglas County Surveyor's Office in 1978; monumented with an iron post, 2 1/2 ins. diam., firmly set, projecting 8 ins. above ground, (alongside of which is an iron pipe, 2 ins. diam., firmly set, projecting 30 ins. above ground) with a brass cap mkd.															

**Dependent Resurvey of a Portion of the West Boundary,  
T. 26 S., R. 2 W., Willamette Meridian, Oregon**

FEET	
	
	<p>from which the remains of a bearing tree mkd. by person(s) unknown, reported by the Douglas County Surveyor's Office</p> <p>A decayed fir stump, 24 ins. diam., bears N. 61 1/4° W., 47.4 ft. dist., no marks visible.</p> <p>and the accessories established by the Douglas County Surveyor's Office</p> <p>A cedar, 27 ins. diam., bears N. 81 3/4° E., 19.6 ft. dist., with a healed blaze.</p> <p>A fir, 20 ins. diam., bears S. 23 3/4° E., 127.0 ft. dist., with a healed blaze.</p> <p>A boulder, 20 x 20 x 4 ft. high, bears S. 86 1/2° W., 32.1 ft. dist., with a chiseled X on the E. face.</p> <p>A tan oak, 9 ins. diam., bears N. 52 1/4° W., 71.8 ft. dist., with a healed double blaze.</p> <p>Corner is located N., 65 ft. dist., of a graveled road, 20 ft. wide, bears S. 55° E. and N. 60° W.</p> <p>N. 0° 14' 58" E., bet. secs. 1 and 6.</p>
1323.99	<p>The S 1/16 sec. cor. of secs. 1 and 6, reported by White, Beck, and Reynolds in 1962-63; perpetuated by persons unknown; monumented with an aluminum pipe, 3/4 in. diam., firmly set, bent at a 45 degree angle to the west, projecting 12 ins. above ground, from which the remains of the bearing trees reported by White, Beck, and Reynolds</p> <p>A decayed fir stump, 23 ins. diam., bears S. 44° E., 108.2 ft. dist., with a healed blaze.</p> <p>A hollowed, decayed cedar stump, 46 ins. diam., bears N. 10 1/2° W., 61.4 ft. dist., with lower portion of a healed blaze intact.</p> <p>At the corner point</p> <p>Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 25 ins. in the ground, directly over the aluminum pipe, with brass cap mkd.</p> <p align="center">  </p> <p>from which new bearing trees</p>

**Dependent Resurvey of a Portion of the West Boundary,  
T. 26 S., R. 2 W., Willamette Meridian, Oregon**

FEET																
	<p>A hemlock, 9 ins. diam., bears S. 43 1/2° E., 27.8 ft. dist., mkd. S1/16 S6 BT.</p> <p>A fir, 16 ins. diam., bears S. 79 1/4° W., 18.8 ft. dist., mkd. S1/16 S1 BT.</p> <p>Corner is located W., 40 ft. dist., of a graveled road, 20 ft. wide, bears N. and S.</p> <hr style="width: 20%; margin: 10px auto;"/> <p>N. 0° 16' 53" E., beginning new measurement.</p>															
1325.66	<p>The 1/4 sec. cor. of secs. 1 and 6, reported by White, Beck, and Reynolds, in 1962-63; perpetuated by the Douglas County Surveyor's Office, in 1967; subsequently perpetuated by Schinnell, PLS No. 65372, in 2006; monumented with an iron post, 2 1/2 ins. diam., firmly set, projecting 15 ins. above ground, in a mound of stone, 3 ft. base, 12 ins. high, with a brass cap mkd.</p> <div style="text-align: center; margin: 10px 0;"> <table style="margin: 0 auto; border-collapse: collapse;"> <tr><td></td><td style="text-align: center;">1/4</td><td></td></tr> <tr><td style="text-align: center;">S 1</td><td style="text-align: center;"> </td><td style="text-align: center;">S 6</td></tr> <tr><td style="text-align: center;">R 3 W</td><td style="text-align: center;"> </td><td style="text-align: center;">R 2 W</td></tr> <tr><td></td><td style="text-align: center;">T 26 S</td><td></td></tr> <tr><td></td><td style="text-align: center;">1963</td><td></td></tr> </table> </div> <p>from which the remains of the bearing trees reported by White, Beck, and Reynolds</p> <p style="margin-left: 40px;">A decayed fir stump, 28 ins. diam., bears S. 88° E., 14.5 ft. dist., with a portion of the healed blaze intact. (Original)</p> <p style="margin-left: 40px;">A cedar, 31 ins. diam., bears S. 53 1/2° E., 27.1 ft. dist., with a healed double blaze.</p> <p style="margin-left: 40px;">A fir stump, 57 ins. diam., bears N. 2° W., 31.0 ft. dist., no marks visible.</p> <p>and a bearing tree mkd. by the Douglas County Surveyor's Office</p> <p style="margin-left: 40px;">A hemlock, 16 ins. diam., bears N. 51 1/2° W., 30.2 ft. dist., with no marks visible on partially healed double blaze.</p> <p>and a bearing tree mkd. by Schinnell</p> <p style="margin-left: 40px;">A hemlock, 25 ins. diam., bears S. 78° W., 9.0 ft. dist., with axe marks visible on bark.</p> <p>Corner is located on top of a ridge, bears N. 80° E. and S. 75° W.</p> <hr style="width: 60%; margin: 10px auto;"/>		1/4		S 1		S 6	R 3 W		R 2 W		T 26 S			1963	
	1/4															
S 1		S 6														
R 3 W		R 2 W														
	T 26 S															
	1963															

**Dependent Resurvey of a Portion of the Subdivisional Lines,  
T. 26 S., R. 2 W., Willamette Meridian, Oregon**

FEET	
	<p align="center">Restoring the survey by McQuinn in 1883, the resurvey by Mensch in 1916-1918, the resurvey by Zirpel, Jr., and Glenn in 1959, the resurvey by Roseberry in 1968, the resurvey by Popken in 1975, the resurvey by Rogers in 1979, the resurvey by Bedell, Seibold, and Browning in 1992-95, and the rehabilitation by Moore and Browning in 2002</p> <hr/> <p>From the cor. of secs. 13, 14, 23, and 24, reported by Popken in 1975, monumented with an iron post, 1 1/4 ins. diam. (Record, 1 in. diam.), firmly set, projecting 4 ins. above ground, in a mound of stone, 2 ft. base, to the top, with a brass cap mkd.</p> <p align="center">COUNTY SURVEYORS OFFICE T 26 S R 2 W S 14   S 13 ----- S 23   S 24 1961</p> <p>from which the bearing trees reported by Popken</p> <p>A cedar, 14 ins. diam., bears N. 66° E., 32.7 ft. dist., with a healed blaze.</p> <p>An oak, 11 ins. diam., bears S. 70° E., 22.1 ft. dist., with a healed double blaze.</p> <p>A fir, 41 ins. diam., bears S. 20° E., 19.1 ft. dist., with a healed blaze. (Original)</p> <p>A fir, 20 ins. diam., bears S. 81° W., 35.0 ft. dist., with a healed double blaze.</p> <p>An oak, 8 ins. diam., bears N. 86 1/2° W., 24.4 ft. dist., with a healed double blaze.</p> <p>Corner is located N., 75 ft. dist., of Boundary Road, graveled surface, 14 ft. wide, bears S. 80° E. and N. 75° W.</p> <p>N. 0° 45' 08" W., bet. secs. 13 and 14.</p> <p>1294.69 Point for the S 1/16 sec. cor. of secs. 13 and 14.</p> <p>Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 16 ins. in the ground, in a mound of stone, 2 ft. base, to the top, with brass cap mkd.</p> <p align="center">S 1/16 S 14   S 13 2018</p> <p>from which</p>

**Dependent Resurvey of a Portion of the Subdivisional Lines,  
T. 26 S., R. 2 W., Willamette Meridian, Oregon**

FEET	<p>A fir, 10 ins. diam., bears N. 43 1/2° E., 44.7 ft. dist., mkd. S1/16 S13 BT.</p> <p>A fir, 8 ins. diam., bears N. 66 1/2° W., 32.5 ft. dist., mkd. S1/16 S14 BT.</p>
2589.38	<p>The 1/4 sec. cor. of secs. 13 and 14, reported by Roseberry in 1968, monumented with an iron post, 1 1/4 ins. diam. (Record, 1 in. diam.), firmly set, projecting 28 ins. above ground, in a mound of stone, 3 ft. base, 24 ins. high, with a brass cap mkd.</p> <p style="text-align: center;">COUNTY SURVEYORS OFFICE T 26 S R 2 W 1/4 S 14   S 13 1961</p> <p>from which the remains of the bearing trees reported by Roseberry</p> <p>A decayed fir stump, 20 ins. diam., bears N. 16° E., 46.5 ft. dist., no marks visible. (Original)</p> <p>An oak, 8 ins. diam., bears N. 66° E., 36.3 ft. dist., with a healed double blaze.</p> <p>A decayed fir snag, 40 ins. diam., bears N. 44 1/2° W., 39.6 ft. dist., with scribe marks CS and other illegible scribe marks visible on partially healed double blaze. (Original)</p> <p>and a new bearing tree</p> <p>A madrone, 9 ins. diam., bears N. 30 1/4° W., 33.8 ft. dist., mkd. 1/4 S14 BT on bark.</p> <p>Corner is located on top of a large rock outcropping.</p> <hr/> <p>From the cor. of secs. 1, 2, 11, and 12, reported by Bedell, Seibold, and Browning in 1992-95, monumented with an iron post, 2 1/2 ins. diam., firmly set, projecting 6 ins. above ground, with a brass cap mkd.</p> <p style="text-align: center;">T 26 S R 2 W S 2   S 1 ----- S 11   S 12 1968</p> <p>from which the remains of the bearing trees reported by Bedell, Seibold, and Browning</p> <p>A fir, 32 ins. diam., bears N. 47° E., 8.9 ft. dist., with scribe marks S1 RE 4079 visible on bark and a healed double blaze.</p> <p>A fir snag, 50 ins. diam., bears N. 58° E., 54.8 ft. dist., with a healed blaze. (Original)</p>

**Dependent Resurvey of a Portion of the Subdivisional Lines,  
T. 26 S., R. 2 W., Willamette Meridian, Oregon**

FEET	
	A decayed fir snag, 42 ins. diam., bears S. 65 1/2° E., 29.0 ft. dist., with scribe marks BT visible on bark. (Original)
	A fir, 24 ins. diam., bears S. 18 1/2° E., 5.9 ft. dist., with a healed double blaze.
	A fir, 11 ins. diam., bears S. 56 1/2° W., 10.2 ft. dist., with a healed double blaze.
	A fir, 10 ins. diam., bears N. 30 1/4° W., 16.5 ft. dist., with a healed double blaze.
	N. 1° 18' 46" E., bet. secs. 1 and 2.
160	Creek, 3 ft. wide, course N. 85° W.
485	Spur, slopes N. 60° W.
745	Creek, 5 ft. wide, course N. 85° W.
1335	Creek, 2 ft. wide, course W.
1375.81	Point for the S 1/16 sec. cor. of secs. 1 and 2. Not monumented.
1395	Spur, slopes N. 70° W.
1555	Upper Susan Creek waterfall, 280 ft. drop, 15 ft. wide, course S. 80° W.
1645	Susan Creek, 10 ft. wide, course S. 50° E.
2751.62	The 1/4 sec. cor. of secs. 1 and 2, reestablished by proportionate measurement by Lecklider, PE No. 4079, in June 1959. There is no remaining evidence of the original cor., therefore this point is accepted as a careful and faithful reestablishment of the cor.; monumented with an iron pipe, 1 7/8 ins. diam., firmly set, projecting 19 ins. above ground, in a mound of stone, 3 ft. base, 12 ins. high, from which the bearing trees mkd. by Lecklider  A fir, 13 ins. diam., bears S. 71 3/4° E., 11.5 ft. dist., with a healed blaze.  A fir, 49 ins. diam., bears N. 84° W., 9.2 ft. dist., with a healed double blaze.  At the corner point  Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 24 ins. in the ground, in a mound of stone, 3 ft. base, to the top, with brass cap mkd.  T 26 S R 2 W 1/4 S 2   S 1 2019

**Dependent Resurvey of a Portion of the Subdivisional Lines,  
T. 26 S., R. 2 W., Willamette Meridian, Oregon**

FEET	
	Bury the iron pipe, 32 ins. long, alongside the cor. <hr style="width: 20%; margin: 0 auto;"/>
	N. 1° 07' 10" E., beginning new measurement.
25	Creek, 3 ft. wide, course N. 80° W.
995	Susan Creek, 7 ft. wide, course W.
1270	Spur, slopes S. 70° E.
1355	Creek, 1 ft. wide, course N. 65° E.
1372.71	The N 1/16 sec. cor. of secs. 1 and 2, established by Lecklider, PE No. 4079, in June, 1959; and is accepted as the cor.; monumented with an iron rod, 1/2 in. diam., firmly set, projecting 14 ins. above ground, in a mound of stone, 3 ft. base, 12 ins. high, from which the bearing trees mkd. by Lecklider  A fir, 14 ins. diam., bears N. 26 1/4° E., 13.9 ft. dist., with a healed double blaze.  A fir, 28 ins. diam., bears N. 63 1/4° W., 15.0 ft. dist., with a healed blaze.  At the corner point  Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 12 ins. in the ground to bedrock, directly over the iron rod, in a mound of stone, 3 ft. base, 12 ins. high, with brass cap mkd.  <div style="text-align: center;">N 1/16 S 2   S 1 2019</div> <hr style="width: 20%; margin: 0 auto;"/>
	N. 0° 56' 56" E., beginning new measurement.
40	Creek, 6 ft. wide, course S. 35° E.
1420.92	The cor. of secs. 1 and 2 only, on the N. bdy. of the Tp., reported by Skeesick in 2010-11, monumented with a stainless steel post, 2 1/2 ins. diam., firmly set, projecting 7 ins. above ground, with a brass cap mkd.  <div style="text-align: center;">T 25 S R 2 W S 36 <hr style="width: 20%; margin: 0 auto;"/>S 2   S 1 T 26 S R 2 W 2010</div>
	from which the remains of the bearing trees reported by Skeesick

**Dependent Resurvey of a Portion of the Subdivisional Lines,  
T. 26 S., R. 2 W., Willamette Meridian, Oregon**

FEET									
	<p>A decayed fir stump, size indeterminate, bears N. 55° E., 13.2 ft. dist., alongside of which is a down, decayed fir, size indeterminate, no marks visible. (Original)</p> <p>A fir, 36 ins. diam., bears S. 77 1/2° E., 47.0 ft. dist., with a healed blaze.</p> <p>A fir, 30 ins. diam., bears S. 3 3/4° W., 33.4 ft. dist., with a healed blaze.</p> <p>A fir, 30 ins. diam., bears S. 87° W., 21.9 ft. dist., with a healed blaze.</p> <p>A fir, 18 ins. diam., bears N. 5 1/2° W., 10.6 ft. dist., with a healed blaze.</p> <hr/> <p>From the cor. of secs. 2, 3, 10, and 11, reported by Bedell, Seibold, and Browning in 1992-95, monumented with an iron post, 2 1/2 ins. diam., firmly set, projecting 12 ins. above ground, in a mound of stone, 3 ft. base, to the top, with a brass cap mkd.</p> <div style="text-align: center;"> <table border="1"> <tr> <td>T 26 S</td> <td>R 2 W</td> </tr> <tr> <td>S 3</td> <td>S 2</td> </tr> <tr> <td>S 10</td> <td>S 11</td> </tr> <tr> <td colspan="2">1959</td> </tr> </table> </div> <p>from which the remains of the bearing trees reported by Bedell, Seibold, and Browning</p> <p>A decayed fir stump, 63 ins. diam., bears N. 35 1/2° E., 52.1 ft. dist., with no marks visible on open blaze. (Original)</p> <p>A fir stump, 28 ins. diam., bears N. 55 1/4° E., 29.4 ft. dist., with a healed blaze.</p> <p>A decayed fir stump, 46 ins. diam., bears N. 78 1/2° E., 63.4 ft. dist., with a healed blaze.</p> <p>A fir snag, 46 ins. diam., bears S. 66 1/2° E., 66.0 ft. dist., with a healed blaze and scribe marks T2 R2 S visible on bark above the healed blaze.</p> <p>A fir snag, 13 ins. diam., bears S. 10 1/2° E., 19.8 ft. dist., with a healed blaze.</p> <p>A fir, 26 ins. diam., bears S. 49 1/2° W., 53.8 ft. dist., with a healed blaze.</p> <p>A fir snag, 11 ins. diam., bears N. 59 3/4° W., 37.3 ft. dist., with a healed blaze.</p> <p>and new bearing trees</p> <p>A fir, 5 ins. diam., bears S. 70° E., 18.9 ft. dist., mkd. T26S R2W S11 BT.</p>	T 26 S	R 2 W	S 3	S 2	S 10	S 11	1959	
T 26 S	R 2 W								
S 3	S 2								
S 10	S 11								
1959									

Dependent Resurvey of a Portion of the Subdivisional Lines,  
T. 26 S., R. 2 W., Willamette Meridian, Oregon

FEET	
	<p>A maple, 9 ins. diam., bears N. 48 1/2° W., 22.2 ft. dist., mkd. T26S R2W S3 BT on bark.</p> <p>No new bearing trees available in sec. 2.</p> <p>N. 1° 10' 09" E., bet. secs. 2 and 3.</p>
55	Graveled road, 18 ft. wide, bears N. 60° E. and S. 60° W.
1408.41	Point for the S 1/16 sec. cor. of secs. 2 and 3. Not monumented.
2816.82	<p>The 1/4 sec. cor. of secs. 2 and 3, reported by Zirpel, Jr., and Glenn in 1959; perpetuated by Monrean, PLS No. 1830, in 2004, under CS65/49-36; monumented with an iron post, 2 1/2 ins. diam., firmly set, projecting 1 in. above ground, in a collar of stone, (alongside is an iron pipe, 1 1/2 ins. diam. [(Record, 1 3/4 ins. diam.), firmly set, projecting 7 ins.] with a brass cap mkd.</p> <p style="text-align: center;">T 26 S R 2 W 1/4 S 3   S 2 1959</p> <p>from which the bearing trees reported by Zirpel, Jr., and Glenn</p> <p style="padding-left: 40px;">A fir, 21 ins. diam., bears N. 66 1/2° E., 10.6 ft. dist., with a healed blaze.</p> <p style="padding-left: 40px;">A fir, 32 ins. diam., bears S. 70° W., 9.2 ft. dist., with a healed blaze.</p> <p>and the bearing trees mkd. by Monrean</p> <p style="padding-left: 40px;">A fir, 36 ins. diam., bears S. 5 1/2° W., 20.0 ft. dist., with a healed double blaze.</p> <p style="padding-left: 40px;">A fir, 13 ins. diam., bears N. 46° W., 8.3 ft. dist., with a healed double blaze.</p> <hr style="width: 20%; margin: 20px auto;"/> <p>N. 1° 02' 15" E., beginning new measurement.</p>
1406.97	Point for the N 1/16 sec. cor. of secs. 2 and 3. Not monumented.
2766.46	<p>The cor. of secs. 2 and 3, on the N. bdy. of the Tp., reported by Skeesick in 2010-11, monumented with an iron post, 2 1/2 ins. diam., firmly set, projecting 4 ins. above ground, with a brass cap mkd.</p> <p style="text-align: center;">T 25 S R 2 W S 35 ----- S 3   S 2 T 26 S R 2 W 1959</p>

**Dependent Resurvey of a Portion of the Subdivisional Lines,  
T. 26 S., R. 2 W., Willamette Meridian, Oregon**

FEET																	
	<p>from which the remains of the bearing trees reported by Skeesick</p> <p>A fir stump, 55 ins. diam., bears S. 44 1/2° E., 37.0 ft. dist., with a healed blaze.</p> <p>A rock in place, 3 1/2 X 4 X 3 ft. high, bears S. 20° E., 35.6 ft. dist., with an S chiseled on NW face.</p> <p>A fir, 29 ins. diam., bears S. 1 1/4° E., 50.6 ft. dist., with a healed blaze.</p> <p>A fir, 57 ins. diam., bears S. 83 1/2° W., 165.0 ft. dist., with a healed blaze.</p> <p>A fir, 19 ins. diam., bears N. 43 3/4° W., 14.2 ft. dist., with illegible scribe marks visible on partially healed blaze.</p> <p>The basalt stone, 16 X 10 X 7 ins., established by Collier in 1913-14, mkd. with 2 notches on east and 4 notches on west faces, was found set alongside the cor. Bury the stone alongside the cor.</p> <p>Note: The cor. was incorrectly identified as an original cor. on the Skeesick and the Seibold &amp; Browning 1995-98 plats.</p> <hr/> <p>From the cor. of secs. 15 and 22 only, identical with cor. No. 8 of Tract 37, reported by Zirpel, Jr., and Glenn in 1959, monumented with an iron post, 2 ins. diam., firmly set, projecting 3 ins. above ground, in a collar of stone, with a brass cap mkd.</p> <div style="text-align: center;"> <table border="1"> <tr> <td></td> <td></td> <td>T 26 S</td> <td>R 2 W</td> </tr> <tr> <td></td> <td></td> <td>S 16</td> <td>S 15</td> </tr> <tr> <td>8 TR 37</td> <td></td> <td>S 21</td> <td>S 22</td> </tr> <tr> <td></td> <td></td> <td colspan="2">1918</td> </tr> </table> </div> <p>from which the remains of the bearing trees reported by Zirpel, Jr., and Glenn</p> <p>A pine, 49 ins. diam., bears N. 60° E., 20.5 ft. dist., with a healed blaze.</p> <p>A madrone, 18 ins. diam., bears S. 44° E., 10.6 ft. dist., no marks visible.</p> <p>A fir, 14 ins. diam., bears S. 20 3/4° W., 20.5 ft. dist., with a healed blaze.</p> <p>A decayed fir stump, 12 ins. diam., bears S. 76° W., 7.9 ft. dist., with a healed blaze.</p> <p>A fir, 19 ins. diam., bears N. 74° W., 4.0 ft. dist., with a healed blaze.</p> <p>N. 1° 04' 12" E., bet. sec. 15 and Tract 37.</p>			T 26 S	R 2 W			S 16	S 15	8 TR 37		S 21	S 22			1918	
		T 26 S	R 2 W														
		S 16	S 15														
8 TR 37		S 21	S 22														
		1918															
883.74	<p>Corner No. 1 of Tract 37, on the W. bdy. of sec. 15, reported by Moore and Browning in 2002, monumented with an iron post, 1 in. diam., firmly set, projecting 16 ins. above ground, in a mound of stone, 3 ft. base, 12 ins. high, with a brass cap mkd.</p>																

Dependent Resurvey of a Portion of the Subdivisional Lines,  
T. 26 S., R. 2 W., Willamette Meridian, Oregon

FEET									
	<div style="text-align: center;"> <table border="0"> <tr> <td style="border-right: 1px solid black; padding-right: 5px;">S 16</td> <td style="padding-left: 5px;">T 26 S</td> </tr> <tr> <td style="border-right: 1px solid black; padding-right: 5px;">1</td> <td style="padding-left: 5px;">R 2 W</td> </tr> <tr> <td style="border-right: 1px solid black; padding-right: 5px;">TR 37</td> <td style="padding-left: 5px;">S 15</td> </tr> <tr> <td></td> <td style="text-align: center;">1918</td> </tr> </table> </div> <p>from which the bearing trees reported by Moore</p> <p style="padding-left: 40px;">A cedar, 18 ins. diam., bears S. 59 1/4° W., 40.3 ft. dist., with a healed blaze.</p> <p style="padding-left: 40px;">A decayed fir stump, 22 ins. diam., bears S. 74° W., 33.0 ft. dist., with scribe marks TR 37 visible on open blaze. (Original)</p> <p style="padding-left: 40px;">A fir, 9 ins. diam., bears N. 35° W., 18.7 ft. dist., with a healed blaze.</p> <hr style="width: 20%; margin: 10px auto;"/> <p>N. 1° 07' 29" E., bet. secs. 15 and 16.</p>	S 16	T 26 S	1	R 2 W	TR 37	S 15		1918
S 16	T 26 S								
1	R 2 W								
TR 37	S 15								
	1918								
1757.62	<p>The 1/4 sec. cor. of sec. 15 only, reported by Zirpel, Jr., and Glenn in 1959, monumented with an iron post, 2 1/2 ins. diam., firmly set, projecting 6 ins. above ground, with a brass cap mkd.</p> <div style="text-align: center;"> <table border="0"> <tr> <td style="padding-right: 10px;">T 26 S</td> <td style="padding-right: 10px;">R 2 W</td> </tr> <tr> <td style="border-right: 1px solid black; padding-right: 5px;"></td> <td style="padding-left: 5px;">1/4</td> </tr> <tr> <td style="border-right: 1px solid black; padding-right: 5px;"></td> <td style="padding-left: 5px;">S 15</td> </tr> <tr> <td></td> <td style="text-align: center;">1959</td> </tr> </table> </div> <p>from which the bearing trees reported by Zirpel, Jr., and Glenn</p> <p style="padding-left: 40px;">A fir, 31 ins. diam., bears N. 69 1/2° E., 21.8 ft. dist., with a healed blaze.</p> <p style="padding-left: 40px;">A fir, 20 ins. diam., bears S. 60 1/2° E., 24.1 ft. dist., with a healed blaze.</p> <hr style="width: 20%; margin: 10px auto;"/> <p>N. 1° 08' 48" E., beginning new measurement.</p>	T 26 S	R 2 W		1/4		S 15		1959
T 26 S	R 2 W								
	1/4								
	S 15								
	1959								
1316.18	<p>The N 1/16 sec. cor. of sec. 15 only, reported by Moore and Browning in 2002, monumented with an iron post, 2 1/2 ins. diam., firmly set, projecting 4 ins. above ground, with a brass cap mkd.</p> <div style="text-align: center;"> <table border="0"> <tr> <td style="border-right: 1px solid black; padding-right: 5px;"></td> <td style="padding-left: 5px;">N 1/16</td> </tr> <tr> <td style="border-right: 1px solid black; padding-right: 5px;"></td> <td style="padding-left: 5px;">S 15</td> </tr> <tr> <td></td> <td style="text-align: center;">1959</td> </tr> </table> </div> <p>from which the bearing trees reported by Moore</p> <p style="padding-left: 40px;">A fir, 10 ins. diam., bears N. 55 1/2° E., 16.4 ft. dist., with a healed blaze.</p> <p style="padding-left: 40px;">A pine, 33 ins. diam., bears S. 23 3/4° E., 63.4 ft. dist., with a healed blaze.</p>		N 1/16		S 15		1959		
	N 1/16								
	S 15								
	1959								

**Dependent Resurvey of a Portion of the Subdivisional Lines,  
T. 26 S., R. 2 W., Willamette Meridian, Oregon**

FEET	<p>Corner is located E., 115 ft. dist., of a graveled road, 12 ft. wide, bears N. 10° E. and S. 10° W., and N., 385 ft. dist., of same graveled road, bears S. 55° E. and N. 50° W.</p> <hr/> <p>From the cor. of secs. 10, 11, 14, and 15, reported by Bedell, Seibold, and Browning in 1992-95, monumented with an iron post, 2 1/2 ins. diam., firmly set, projecting 16 ins. above ground, in a mound of stone, 2 ft. base, 12 ins. high, with a brass cap mkd.</p> <div style="text-align: center;"> <table style="margin: auto; border-collapse: collapse;"> <tr> <td style="padding: 2px 5px;">T 26 S</td> <td style="padding: 2px 5px;">R 2 W</td> </tr> <tr> <td style="padding: 2px 5px;">S 10</td> <td style="padding: 2px 5px;">S 11</td> </tr> <tr> <td style="border-top: 1px solid black; padding: 2px 5px;">S 15</td> <td style="border-top: 1px solid black; padding: 2px 5px;">S 14</td> </tr> <tr> <td colspan="2" style="padding: 2px 5px;">1959</td> </tr> </table> </div> <p>from which the remains of the bearing trees reported by Bedell, Seibold, and Browning</p> <ul style="list-style-type: none"> <li>A fir, 12 ins. diam., bears N. 55° E., 23.8 ft. dist., with a healed blaze.</li> <li>A madrone stump, 10 ins. diam., bears N. 72 1/2° E., 48.8 ft. dist., with no marks visible on open blaze.</li> <li>A decayed fir stump, 26 ins. diam., bears S. 22 3/4° E., 65.3 ft. dist., no marks visible. (Original)</li> <li>A fir, 15 ins. diam., bears S. 52° E., 31.0 ft. dist., with a healed blaze.</li> <li>A decayed fir stump, 30 ins. diam., bears S. 27 1/4° W., 37.0 ft. dist., with a healed blaze. (Original)</li> <li>A fir, 18 ins. diam., bears S. 79 3/4° W., 121.4 ft. dist., with a healed blaze.</li> <li>A broken-top lightning-struck living fir, 40 ins. diam., bears N. 40 3/4° W., 10.6 ft. dist., with axe marks visible on bark. (Original)</li> </ul> <p>and a bearing tree mkd. by person(s) unknown</p> <ul style="list-style-type: none"> <li>A fir, 12 ins. diam., bears S. 83 1/2° E., 19.7 ft. dist., no marks visible and a bearing tree tag.</li> </ul> <p>From this cor., the Bureau of Land Management Geodetic Control Station No. EC 41166, bears S. 83° 07' 48" E., 190.28 ft. dist., monumented with an aluminum cap, 3 1/4 ins. diam., cemented in solid bedrock, with top mkd. EC41166 GPS 1992 and a triangle in the center.</p> <p>Corner is located in the bottom of a shallow draw, drains S. 55° E.</p> <p>S. 89° 07' 22" W., bet. secs. 10 and 15.</p> <p>Creek, 3 ft. wide, course S. 15° E.</p>	T 26 S	R 2 W	S 10	S 11	S 15	S 14	1959	
T 26 S	R 2 W								
S 10	S 11								
S 15	S 14								
1959									
1080									

**Dependent Resurvey of a Portion of the Subdivisional Lines,  
T. 26 S., R. 2 W., Willamette Meridian, Oregon**

<p>FEET 1310.14</p>	<p>The E 1/16 sec. cor. of secs. 10 and 15, reported by Zirpel, Jr., and Glenn in 1959; perpetuated by Monrean, PLS No. 1830, in 1985; monumented with an iron post, 2 1/2 ins. diam., firmly set, with top 8 ins. below the surface of a graveled road, with a brass cap mkd.</p> <div style="text-align: center; margin: 10px 0;"> <math display="block">\begin{array}{c} \text{S } 10 \\ \text{E } 1/16 \text{ ---} \\ \text{S } 15 \\ 1959 \end{array}</math> </div> <p>from which the remains of the bearing tree reported by Zirpel, Jr., and Glenn</p> <p style="padding-left: 40px;">A fir stump, 19 ins. diam., bears S. 41 1/4° E., 51.5 ft. dist., with a healed blaze.</p> <p>and the bearing trees mkd. by Monrean</p> <p style="padding-left: 40px;">A cedar, 21 ins. diam., bears S. 29 1/4° W., 27.0 ft. dist., with a healed blaze.</p> <p style="padding-left: 40px;">A fir, 12 ins. diam., bears N. 49 1/4° W., 81.7 ft. dist., with a healed blaze.</p> <p>and a new reference monument</p> <p style="padding-left: 40px;">An iron rod, 30 ins. long, 5/8 in. diam., driven 27 ins. in the ground, for a reference monument, bears S. 24° 00' 45" E., 67.50 ft. dist., with aluminum cap mkd. RM E1/16 67.5 FT TO COR S15 2018 and an arrow pointing to the cor.</p> <p>Corner is located W., 5 ft. dist., of the center line of a graveled road, 16 ft. wide, bears S. 10° E. and N. 30° W.</p> <hr style="border: 0.5px solid black; margin: 10px 0;"/> <p>From the W 1/16 sec. cor. of secs. 9 and 16, reported by Rogers in 1979, monumented with an iron post, 2 1/2 ins. diam., firmly set, projecting 7 ins. above ground, with a brass cap mkd.</p> <div style="text-align: center; margin: 10px 0;"> <math display="block">\begin{array}{c} \text{S } 9 \\ \text{W } 1/16 \text{ ---} \\ \text{S } 16 \\ 1959 \end{array}</math> </div> <p>from which the remains of the bearing trees reported by Rogers</p> <p style="padding-left: 40px;">A decayed hemlock snag, 20 ins. diam., bears N. 17° E., 12.5 ft. dist., with a healed blaze. (Record, fir)</p> <p style="padding-left: 40px;">A hemlock, 16 ins. diam., bears S. 65° W., 2.6 ft. dist., with a healed blaze.</p> <p>and a new bearing tree</p>
-------------------------	--

**Dependent Resurvey of a Portion of the Subdivisional Lines,  
T. 26 S., R. 2 W., Willamette Meridian, Oregon**

FEET	<p>A hemlock, 14 ins. diam., bears N. 20 1/4° W., 20.3 ft. dist., mkd. W1/16 S9 BT.</p> <p>Corner is located W., 85 ft. dist., of a graveled road, 16 ft. wide, bears N. 35° E. and S. 40° W., and W., 110 ft. dist., of Honey Creek, 8 ft. wide, course S. 20° W.</p> <p>S. 88° 21' 34" W., bet. secs. 9 and 16.</p>																				
1254.85	<p>The cor. of secs. 8, 9, 16, and 17, reported by Zirpel, Jr., and Glenn in 1959, monumented with an iron post, 2 ins. diam., firmly set, projecting 13 ins. above ground, with a brass cap mkd.</p> <div style="text-align: center; margin: 10px 0;"> <table style="border-collapse: collapse; margin: auto;"> <tr><td>T 26 S</td><td>R 2 W</td></tr> <tr><td>S 8</td><td>S 9</td></tr> <tr><td colspan="2" style="border-top: 1px solid black;"></td></tr> <tr><td>S 17</td><td>S 16</td></tr> <tr><td colspan="2">1918</td></tr> </table> </div> <p>from which the remains of the bearing trees reported by Zirpel, Jr., and Glenn</p> <p>A fir, 64 ins. diam., bears N. 40° E., 18.5 ft. dist., with illegible scribe marks visible on bark. (Original)</p> <p>A fir, 37 ins. diam., bears S. 20° E., 6.6 ft. dist., no marks visible. (Original)</p> <p>A fir, 51 ins. diam., bears S. 55° W., 25.7 ft. dist., no marks visible. (Original)</p> <p>A chinquapin snag, 14 ins. diam., bears N. 75 1/4° W., 10.6 ft. dist., with a healed blaze.</p> <p>and a new bearing tree</p> <p>An alder, 5 ins. diam., bears N. 64 3/4° W., 34.8 ft. dist., mkd. T26S R2W S8 BT on bark.</p> <hr style="width: 60%; margin: 20px auto;"/> <p>From the cor. of secs. 4, 5, 8, and 9, reported by Zirpel, Jr., and Glenn in 1959, monumented with an iron post, 2 1/2 ins. diam., firmly set, projecting 18 ins. above ground, in a mound of stone, 3 ft. base, to the top, with a brass cap mkd.</p> <div style="text-align: center; margin: 10px 0;"> <table style="border-collapse: collapse; margin: auto;"> <tr><td>T 26 S</td><td>R 2 W</td></tr> <tr><td>S 5</td><td>S 4</td></tr> <tr><td colspan="2" style="border-top: 1px solid black;"></td></tr> <tr><td>S 8</td><td>S 9</td></tr> <tr><td colspan="2">1959</td></tr> </table> </div> <p>from which the remains of the bearing trees reported by Zirpel, Jr., and Glenn</p>	T 26 S	R 2 W	S 8	S 9			S 17	S 16	1918		T 26 S	R 2 W	S 5	S 4			S 8	S 9	1959	
T 26 S	R 2 W																				
S 8	S 9																				
S 17	S 16																				
1918																					
T 26 S	R 2 W																				
S 5	S 4																				
S 8	S 9																				
1959																					

**Dependent Resurvey of a Portion of the Subdivisional Lines,  
T. 26 S., R. 2 W., Willamette Meridian, Oregon**

FEET	
	<p>A decayed fir stump, 39 ins. diam., bears N. 16 1/2° E., 28.2 ft. dist., with a healed blaze. (Record, 30.4 ft. dist.)</p> <p>A decayed fir stump, 31 ins. diam., bears N. 43 3/4° E., 43.2 ft. dist., with scribe marks T26S R2W S4 visible on open blaze.</p> <p>A fir, 27 ins. diam., bears S. 42 1/2° E., 36.6 ft. dist., with a healed blaze. (Record, 38.0 ft. dist.)</p> <p>A fir, 37 ins. diam., bears S. 20 1/2° E., 37.3 ft. dist., with a healed blaze.</p> <p>A fir, 20 ins. diam., bears S. 9 1/4° W., 12.9 ft. dist., no marks visible.</p> <p>A fir, 18 ins. diam., bears S. 57 1/4° W., 22.4 ft. dist., with a healed double blaze.</p> <p>A fir, 30 ins. diam., bears N. 83 1/2° W., 41.9 ft. dist., with a healed blaze.</p> <p>and a new bearing tree</p> <p>A madrone, 12 ins. diam., bears N. 61 1/4° E., 6.9 ft. dist., mkd. T26S R2W S4 BT on bark.</p> <p>N. 0° 03' 32" E., bet. secs. 4 and 5.</p>
2804.87	<p>The 1/4 sec. cor. of secs. 4 and 5, reported by Zirpel, Jr., and Glenn in 1959, monumented with an iron post, 2 1/2 ins. diam., firmly set, projecting 25 ins. above ground, in a mound of stone, 3 ft. base, 12 ins. high, with a brass cap mkd.</p> <p style="text-align: center;">T 26 S R 2 W 1/4 S 5   S 4 1959</p> <p>from which the remains of the bearing trees reported by Zirpel, Jr., and Glenn</p> <p>A hemlock snag, 17 ins. diam., bears N. 78° E., 10.9 ft. dist., with a healed blaze.</p> <p>A hemlock, 15 ins. diam., bears S. 83° W., 10.6 ft. dist., with a healed blaze.</p> <p>and a new bearing tree</p> <p>A hemlock, 18 ins. diam., bears S. 76 1/2° E., 9.3 ft. dist., mkd. 1/4 S4 BT.</p>
2755.60	<p>N. 0° 03' 29" E., beginning new measurement.</p> <p>The cor. of secs. 4 and 5 only, on the N. bdy. of the Tp., reported by Covington in 2018-20, monumented with an iron post, 2 1/2 ins. diam., firmly set, projecting 4 ins. above ground, with a brass cap mkd.</p>

**Dependent Resurvey of a Portion of the Subdivisional Lines,  
T. 26 S., R. 2 W., Willamette Meridian, Oregon**

FEET	<div data-bbox="812 294 1039 483" style="text-align: center;"> <p>T 25 S R 2 W S 33</p> <hr style="width: 50%; margin: auto;"/> <p>S 5   S 4 T 26 S R 2 W 1959</p> </div> <p data-bbox="397 514 1282 546">from which the remains of the bearing trees reported by Covington</p> <ul style="list-style-type: none"> <li data-bbox="446 577 1380 640">A fir, 39 ins. diam., bears N. 65° E., 18.5 ft. dist., with a healed blaze. (Original)</li> <li data-bbox="446 661 1380 724">A hemlock, 9 ins. diam., bears S. 77 1/2° E., 25.6 ft. dist., with scribe marks T26S R2W S4 BT visible on open blaze.</li> <li data-bbox="446 756 1429 819">A cedar snag, 9 ins. diam., bears S. 10 1/4° E., 57.0 ft. dist., with illegible scribe marks visible on partially healed blaze.</li> <li data-bbox="446 850 1291 913">A tin capped, decayed fir stump, 25 ins. diam., bears S. 10° E., 14.5 ft. dist., with axe marks visible. (Original)</li> <li data-bbox="446 945 1372 1008">A cedar snag, 7 ins. diam., bears S. 24° W., 38.9 ft. dist., with scribe marks T26S R2W S5 BT visible on partially healed blaze.</li> <li data-bbox="446 1039 1372 1102">A fir, 6 ins. diam., bears S. 45 1/4° W., 5.9 ft. dist., with scribe marks T26S R2W S5 BT visible on open blaze.</li> <li data-bbox="446 1134 1299 1197">A tin capped, decayed fir stump, 40 ins. diam., bears S. 55° W., 3.3 ft. dist., with a healed blaze. (Original)</li> <li data-bbox="446 1228 1388 1291">A roothole bears S. 60° W., 33.7 ft. dist., alongside of which is a down decayed yew, 12 ins. diam., with a healed blaze.</li> </ul> <hr style="width: 80%; margin: 10px auto;"/> <p data-bbox="397 1344 1437 1470">From the 1/4 sec. cor. of secs. 7 and 8, reported by Zirpel, Jr., and Glenn in 1959; perpetuated by Smith, PLS No. 2469, in 2005; monumented with an iron post, 1 in. diam., firmly set, projecting 12 ins. above ground, in a collar of stone, with a brass cap mkd.</p> <div data-bbox="852 1501 990 1596" style="text-align: center;"> <p>1/4 S 7   S 8 1918</p> </div> <p data-bbox="397 1617 1429 1648">from which the remains of the bearing trees reported by Zirpel, Jr., and Glenn</p> <ul style="list-style-type: none"> <li data-bbox="446 1680 1412 1711">A fir, 42 ins. diam., bears N. 59 3/4° E., 9.9 ft. dist., with a healed blaze.</li> <li data-bbox="446 1743 1372 1806">A decayed fir snag, 18 ins. diam., bears S. 72° E., 5.3 ft. dist., with a healed double blaze. (Original)</li> <li data-bbox="446 1837 1421 1900">A fir, 23 ins. diam., bears N. 33 1/2° W., 7.9 ft. dist., with a healed blaze. (Original)</li> </ul>
------	---

Dependent Resurvey of a Portion of the Subdivisional Lines,  
T. 26 S., R. 2 W., Willamette Meridian, Oregon

FEET	
	<p>and the bearing trees mkd. by Smith</p> <p>A cedar, 9 ins. diam., bears N. 48° E., 32.3 ft. dist., with scribe marks 1/4 S8 CS BT visible on partially healed double blaze.</p> <p>A fir, 9 ins. diam., bears S. 43 1/2° W., 18.2 ft. dist., with a healed double blaze.</p> <p>N. 3° 34' 42" E., bet. secs. 7 and 8.</p>
1326.56	<p>The N 1/16 sec. cor. of secs. 7 and 8, established by Baughman, PLS No. 536, in 1975; and is accepted as the cor.; monumented with an iron rod, 5/8 in. diam., firmly set, projecting 8 ins. above ground, from which the bearing trees mkd. by Baughman</p> <p>A fir, 10 ins. diam., bears N. 35 1/4° E., 12.0 ft. dist., with a healed blaze.</p> <p>A fir, 17 ins. diam., bears N. 32° W., 10.6 ft. dist., with a healed blaze.</p> <p>At the corner point</p> <p>Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 24 ins. in the ground, directly over the iron rod, with brass cap mkd.</p> <div style="text-align: center;"> <p>N 1/16 S 7   S 8 2018</p> </div> <p>Corner is located E., 60 ft. dist., of a spur, slopes S.</p> <hr style="width: 20%; margin: 10px auto;"/>
1325.64	<p>N. 3° 35' 29" E., beginning new measurement.</p> <p>The cor. of secs. 5, 6, 7, and 8, reported by Zirpel, Jr., and Glenn in 1959; perpetuated by Williams, PLS No. 875, in 1977; monumented with an iron post, 2 1/2 ins. diam., firmly set, projecting 10 ins. above ground, with a brass cap mkd.</p> <div style="text-align: center;"> <p>T 26 S R 2 W S 6   S 5 ----- S 7   S 8 1959</p> </div> <p>from which the remains of the bearing trees reported by Zirpel, Jr., and Glenn</p> <p>A decayed fir stump, size indeterminate, bears N. 25° E., 85.8 ft. dist., with a healed blaze.</p> <p>A decayed fir stump, 13 ins. diam., bears S. 71 1/2° E., 59.4 ft. dist., with scribe marks T26S R2W S8 BT visible on open blaze.</p>

**Dependent Resurvey of a Portion of the Subdivisional Lines,  
T. 26 S., R. 2 W., Willamette Meridian, Oregon**

FEET	
	<p>A decayed fir stump, 23 ins. diam., bears S. 40 1/2° W., 57.4 ft. dist., no marks visible.</p> <p>A decayed fir stump, 36 ins. diam., bears N. 21 1/2° W., 36.6 ft. dist., with a healed blaze.</p> <p>A decayed fir stump, 39 ins. diam., bears N. 12 1/2° W., 38.3 ft. dist., with illegible scribe marks visible on open blaze. (Original)</p> <p>and the remains of the bearing trees mkd. by Williams</p> <p>A decayed fir stump, 45 ins. diam., bears N. 55 1/4° E., 60.1 ft. dist., no marks visible.</p> <p>A decayed fir stump, 48 ins. diam., bears N. 63 1/2° E., 66.8 ft. dist., no marks visible.</p> <p>and new bearing trees</p> <p>A fir, 10 ins. diam., bears N. 69° E., 19.7 ft. dist., mkd. T26S R2W S5 BT.</p> <p>A fir, 13 ins. diam., bears S. 67 1/4° E., 34.8 ft. dist., mkd. T26S R2W S8 BT.</p> <p>A fir, 14 ins. diam., bears S. 11 1/4° W., 24.8 ft. dist., mkd. T26S R2W S7 BT.</p> <p>A fir, 13 ins. diam., bears N. 11 1/2° W., 14.8 ft. dist., mkd. T26S R2W S6 BT.</p>
155	<p>N. 82° 42' 22" W., bet. secs. 6 and 7.</p> <p>Creek, 3 ft. wide, course S. 10° E.</p>
2777.17	<p>The 1/4 sec. cor. of secs. 6 and 7, reported by Zirpel, Jr., and Glenn in 1959, monumented with an iron post, 2 1/2 ins. diam., firmly set, projecting 5 ins. above ground, with a brass cap mkd.</p> <p style="text-align: center;">T 26 S R 2 W S 6 1/4 ——— S 7 1959</p> <p>from which the remains of the bearing trees reported by Zirpel, Jr., and Glenn</p> <p>A decayed fir stump, 29 ins. diam., bears N. 57° W., 22.4 ft. dist., with a healed blaze.</p> <p>and new bearing trees</p>

**Dependent Resurvey of a Portion of the Subdivisional Lines,  
T. 26 S., R. 2 W., Willamette Meridian, Oregon**

FEET	<p>A fir, 9 ins. diam., bears N. 36 1/2° E., 33.8 ft. dist., mkd. 1/4 S6 BT.</p> <p>A hemlock, 27 ins. diam., bears S. 35 1/4° E., 36.8 ft. dist., mkd. 1/4 S7 BT.</p> <hr/> <p align="center"><b>Dependent Resurvey of a portion of the Subdivision of Section Lines of Section 9, T. 26 S., R. 2 W., Willamette Meridian, Oregon</b></p> <hr/> <p align="center">Restoring the survey by Rogers in 1979</p> <hr/> <p>From the west 1/16 sec. cor. of secs. 9 and 16.</p> <p>N. 1° 15' 27" E., on the N. and S. center line of the SW 1/4 of sec. 9.</p> <p>1387.70 The SW 1/16 sec. cor. of sec. 9, reported by Rogers in 1979, monumented with an iron post, 2 1/2 ins. diam., firmly set, projecting 6 ins. above ground, with a brass cap mkd.</p> <p align="center">SW 1/16 S 9 1979</p> <p>from which the bearing trees reported by Rogers</p> <p>A fir, 13 ins. diam., bears S. 19° W., 19.8 ft. dist., with a healed blaze.</p> <p>A fir, 18 ins. diam., bears N. 31 1/2° W., 11.8 ft. dist., with a healed blaze. (Record, 12.9 ft. dist.)</p> <hr/> <p align="center"><b>Dependent Resurvey of a portion of the Subdivision of Section Lines of Section 11, T. 26 S., R. 2 W., Willamette Meridian, Oregon</b></p> <hr/> <p align="center">Restoring the survey by Bedell, Seibold, and Browning in 1992-95</p> <hr/> <p>From the NE 1/16 sec. cor. of sec. 11, reported by Beddell, Seibold, and Browning in 1992-95, monumented with a stainless steel post, 2 1/2 ins. diam., firmly set, projecting 1 in. above ground, in a collar of stone, with a brass cap mkd.</p> <p align="center">NE 1/16 S 11 1993</p> <p>from which the bearing trees reported by Beddell, Seibold, and Browning</p>
------	---

**Dependent Resurvey of a portion of the  
Subdivision of Section Lines of Section 11,  
T. 26 S., R. 2 W., Willamette Meridian, Oregon**

FEET	
	<p>A fir, 30 ins. diam., bears N. 67° E., 19.1 ft. dist., with a healed blaze.</p> <p>A fir, 17 ins. diam., bears S. 63° E., 20.8 ft. dist., with a healed blaze.</p> <p>Corner is located E., 35 ft. dist., of Susan Creek, 20 ft. wide, course S. N. 0° 58' 31" E., on the N. and S. center line of the NE 1/4 of sec. 11.</p>
170	Susan Creek, 20 ft. wide, course S. 70° W.
1336.77	<p>The E 1/16 sec. cor. of secs. 2 and 11, reported by Beddell, Seibold, and Browning in 1992-95, monumented with a stainless steel post, 2 1/2 ins. diam., firmly set, projecting 7 ins. above ground, with a brass cap mkd.</p> <div style="text-align: center;"> <math display="block">\begin{array}{c} \text{S } 2 \\ \text{E } 1/16 \text{ ---} \\ \text{S } 11 \\ 1993 \end{array}</math> </div> <p>from which the bearing trees reported Beddell, Seibold, and Browning</p> <p>A fir, 10 ins. diam., bears N. 31° E., 16.5 ft. dist., with a healed blaze.</p> <p>A fir, 11 ins. diam., bears S. 48° W., 2.6 ft. dist., with a healed blaze.</p> <hr/> <p style="text-align: center;"><b>Dependent Resurvey of a portion of the Subdivision of Section Lines of Section 15, T. 26 S., R. 2 W., Willamette Meridian, Oregon</b></p> <hr/> <p style="text-align: center;">Restoring the survey by Zirpel, Jr., and Glenn in 1959</p> <hr/> <p>From the center E 1/16 sec. cor. of sec. 15, reported by Zirpel, Jr., and Glenn in 1959, monumented with an iron post, 2 1/2 ins. diam., firmly set, projecting 1 in. above ground, with a brass cap mkd.</p> <div style="text-align: center;"> <math display="block">\begin{array}{c} \text{E } 1/16 \\ \text{C ---} \text{ C} \\ \text{S } 15 \\ 1959 \end{array}</math> </div> <p>from which the bearing trees reported by Zirpel, Jr., and Glenn</p> <p>A cedar, 34 ins. diam., bears S. 41° W., 13.2 ft. dist., with a healed blaze.</p> <p>A cedar, 29 ins. diam., bears N. 28° W., 15.2 ft. dist., with a healed double blaze.</p> <p>N. 1° 35' 50" E., on the N. and S. center line of the NE 1/4 of sec. 9.</p>

**Dependent Resurvey of a portion of the  
Subdivision of Section Lines of Section 15,  
T. 26 S., R. 2 W., Willamette Meridian, Oregon**

FEET	
1327.32	<p>The NE 1/16 sec. cor. of sec. 15, reported by Zirpel, Jr., and Glenn in 1959, monumented with an iron post, 2 1/2 ins. diam., firmly set, projecting 8 ins. above ground, with a brass cap mkd.</p> <p style="text-align: center;">NE 1/16 S 15 1959</p> <p>from which the bearing trees reported by Zirpel, Jr., and Glenn</p> <p style="padding-left: 40px;">A cedar, 24 ins. diam., bears N. 15° E., 21.5 ft. dist., with a healed double blaze.</p> <p style="padding-left: 40px;">A pine, 47 ins. diam., bears S. 75 1/2° W., 22.4 ft. dist., with a healed double blaze. (Record, hemlock.)</p> <hr style="width: 20%; margin: 10px auto;"/> <p>N. 1° 31' 07" E., beginning new measurement.</p>
1328.25	<p>The E 1/16 sec. cor. of secs. 10 and 15.</p> <hr style="width: 80%; margin: 10px auto;"/> <p>From the NE 1/16 sec. cor. of sec. 15.</p> <p>S. 89° 20' 00" W., on the E. and W. center line of the NE 1/4 of sec. 9.</p>
654.92	<p>The C-W-NE 1/64 sec. cor. of sec. 15, established by Edwards, PLS No. 2339, in 2009; and is accepted as the cor.; monumented with an iron rod, 5/8 in. diam., firmly set, projecting 3 ins. above ground, with an aluminum cap mkd.</p> <p style="text-align: center;">ROSEBURG RESOURCES COMPANY C-W-NE 1/64. S 15 LS 2339 2009</p> <p>from which the bearing trees mkd. by Edwards</p> <p style="padding-left: 40px;">A fir, 8 ins. diam., bears S. 69 3/4° E., 13.6 ft. dist., with a healed blaze.</p> <p style="padding-left: 40px;">A fir, 9 ins. diam., bears S. 25 3/4° W., 9.5 ft. dist., with a healed blaze.</p> <hr style="width: 20%; margin: 10px auto;"/> <p>S. 89° 22' 59" W., beginning new measurement.</p>
75	<p>Creek, 3 ft. wide, course S. 50° E.</p>
655.19	<p>The center N 1/16 sec. cor. of sec. 15, reported by Zirpel, Jr., and Glenn in 1959, monumented with an iron post, 2 1/2 ins. diam., firmly set, projecting 5 ins. above ground, with a brass cap mkd.</p>

**Dependent Resurvey of a portion of the  
Subdivision of Section Lines of Section 15,  
T. 26 S., R. 2 W., Willamette Meridian, Oregon**

FEET	
	C N 1/16   S 15 C 1959
	<p>from which the bearing trees reported by Zirpel, Jr., and Glenn</p> <p style="padding-left: 40px;">A fir, 34 ins. diam., bears S. 71° E., 33.0 ft. dist., with a healed blaze.</p> <p style="padding-left: 40px;">A fir, 27 ins. diam., bears N. 26 1/2° W., 23.4 ft. dist., with a healed blaze.</p> <hr/> <p style="text-align: center;"><b>Subdivision of Section 2, T. 26 S., R. 2 W., Willamette Meridian, Oregon</b></p> <hr/> <p>From the 1/4 sec. cor. of secs. 2 and 11, reported by Bedell, Seibold, and Browning in 1992-95; perpetuated by person(s) unknown; monumented with a stainless steel post, 2 1/2 ins. diam., firmly set, projecting 1 in. above ground, in a collar of stone, with a brass cap mkd.</p> <p style="text-align: center;">           T 26 S R 2 W            S 2            1/4 ———            S 11            1992         </p> <p>from which the bearing trees reported by Bedell, Seibold, and Browning</p> <p style="padding-left: 40px;">A fir, 56 ins. diam., bears S. 53 1/2° E., 4.6 ft. dist., with a healed double blaze.</p> <p style="padding-left: 40px;">A cedar, 21 ins. diam., bears N. 45 1/2° W., 19.1 ft. dist., with a healed double blaze.</p> <p>and the bearing trees by person(s) unknown</p> <p style="padding-left: 40px;">A fir, 17 ins. diam., bears N. 15 1/2° E., 27.6 ft. dist., with scribe marks 1/4 S2 BT visible on partially healed blaze.</p> <p style="padding-left: 40px;">A fir, 34 ins. diam., bears S. 43 1/4° W., 14.8 ft. dist., with scribe marks 1/4 S11 BT visible on bark.</p> <p>N. 1° 05' 53" E., on the N. and S. center line of sec. 2.</p>
1392.64	<p>The center S 1/16 sec. cor. of sec. 2, established by Lecklider, PE No. 4079, in June, 1959; perpetuated by Monrean, PLS No. 1830, in 2004, under M144-47 and CS65/49-34B; and is accepted as the cor.; monumented with an iron rod, 5/8 in. diam., firmly set, projecting 3 ins. above ground, in a collar of stone, with an aluminum cap mkd. ROSEBURG RESOURCES C S1/16 S2 C LS1830 2004 COMPANY, from which the bearing trees mkd. by Lecklider</p>

**Subdivision of Section 2,  
T. 26 S., R. 2 W., Willamette Meridian, Oregon**

FEET	
	<p>A fir, 40 ins. diam., bears N. 63 1/4° E., 22.9 ft. dist., with a healed blaze.</p> <p>A fir, 30 ins. diam., bears N. 26° W., 16.6 ft. dist., with a healed blaze.</p> <p>At the corner point</p> <p>Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 26 ins. in the ground, directly over the iron rod, in a mound of stone, 3 ft. base, to the top, with brass cap mkd.</p> <div style="text-align: center; margin: 10px 0;"> <math display="block">\begin{array}{c} C \\ S\ 1/16 \quad   \quad S\ 2 \\ C \\ 2019 \end{array}</math> <hr style="width: 20%; margin: 0 auto;"/> </div>
1388.27	<p>N. 1° 06' 06" E., beginning new measurement.</p> <p>Point for the center 1/4 sec. cor. of sec. 2, at intersection with the E. and W. center line.</p> <p>Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 22 ins. in the ground, with brass cap mkd.</p> <div style="text-align: center; margin: 10px 0;"> <math display="block">\begin{array}{c} T\ 26\ S\ R\ 2\ W \\ C\ 1/4\ S\ 2 \\ 2019 \end{array}</math> </div> <p>from which new bearing trees</p> <p style="padding-left: 40px;">A fir, 4 ins. diam., bears S. 4° E., 8.2 ft. dist., mkd. X BT.</p> <p style="padding-left: 40px;">A fir, 7 ins. diam., bears S. 68 1/4° W., 16.4 ft. dist., mkd. C1/4 S2 BT.</p>
2777.54	<p>The center N 1/16 sec. cor. of sec. 2, established by Monrean, PLS No. 1830, in 2004, under M144-47 and CS65/49-34A; and is accepted as the cor.; monumented with an iron rod, 5/8 in. diam., firmly set, projecting 9 ins. above ground, with an aluminum cap mkd. ROSEBURG RESOURCES C N1/16 S2 C LS1830 2004 COMPANY, from which the bearing trees mkd. by Monrean</p> <p style="padding-left: 40px;">A fir, 22 ins. diam., bears N. 15 3/4° E., 49.9 ft. dist., with a healed blaze.</p> <p style="padding-left: 40px;">A fir, 34 ins. diam., bears N. 79 1/4° W., 33.0 ft. dist., with illegible scribe marks visible on partially healed blaze.</p> <p>At the corner point</p> <p>Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 23 ins. in the ground, directly over the iron rod, in a collar of stone, with brass cap mkd.</p>

Subdivision of Section 2,  
T. 26 S., R. 2 W., Willamette Meridian, Oregon

FEET	
	C N 1/16   S 2 C 2019 <hr style="width: 20%; margin: 10px auto;"/>
1389.86	<p>N. 1° 11' 22" E., beginning new measurement.</p> <p>The 1/4 sec. cor. of sec. 2 only, on the N. bdy. of the Tp., reported by Skeesick in 2010-11, monumented with an iron rod, 5/8 in. diam., firmly set, projecting 6 ins. above ground, firmly set, projecting, 8 ins. above the ground, mkd. 1/4 on the S. face), with an aluminum cap mkd. ROSEBURG RESOURCES T25S R2W 1/4 S2 T26S R2W LS1830 2004 COMPANY, from which the bearing trees reported by Skeesick</p> <p style="padding-left: 40px;">A fir, 48 ins. diam., bears S. 52 1/4° E., 22.4 ft. dist., with a healed double blaze.</p> <p style="padding-left: 40px;">A fir, 39 ins. diam., bears S. 44° E., 27.7 ft. dist., with scribe marks 1/4 S2 visible on bark.</p> <p style="padding-left: 40px;">A fir, 7 ins. diam., bears S. 34 1/4° E., 5.6 ft. dist., with a healed double blaze.</p> <p style="padding-left: 40px;">A fir, 10 ins. diam., bears S. 55 3/4° W., 27.0 ft. dist., with a healed blaze.</p> <p style="padding-left: 40px;">A fir, 21 ins. diam., bears N. 6 1/2° W., 25.0 ft. dist., with a healed blaze.</p> <p>At the corner point</p> <p>Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 24 ins. in the ground, directly over the iron rod, with brass cap mkd.</p> <p style="text-align: center;">           T 25 S R 2 W  <hr style="width: 20%; margin: 5px auto;"/>           1/4 S 2            T 26 S R 2 W            2019         </p> <p>The basalt stone, 14 X 12 X 8 ins., established by Collier in 1913-14, mkd. 1/4 on south face, was found set alongside the cor. Bury the stone alongside the cor.</p> <p>Note: The cor. was incorrectly identified as an original cor. on the Skeesick plat.</p> <hr style="width: 80%; margin: 10px auto;"/> <p>From the 1/4 sec. cor. of secs. 1 and 2.</p> <p>S. 89° 58' 03" W., on the E. and W. center line of sec. 2.</p>

**Subdivision of Section 2,  
T. 26 S., R. 2 W., Willamette Meridian, Oregon**

<p>FEET 1301.88</p>	<p>The center E 1/16 sec. cor. of sec. 2, established by Lecklider, PE No. 4079, in June, 1959; perpetuated by Monrean, PLS No. 1830, in 2004, under M144-47 and CS65/49-34D; and is accepted as the cor.; monumented with an iron post, 3/4 in. diam., firmly set, with top flush with the surface of the ground, with an aluminum cap mkd.</p> <p style="text-align: center;">ROSEBURG RESOURCES E 1/16 C ————— C S 2 LS 1830 2004 COMPANY</p> <p>from which the remains of the bearing trees mkd. by Lecklider</p> <p style="padding-left: 40px;">A decayed fir stump, 38 ins. diam., bears S. 71 3/4° W., 41.2 ft. dist., with a healed blaze.</p> <p>and the remains of the bearing trees mkd. by Monrean</p> <p style="padding-left: 40px;">A hemlock, 32 ins. diam., bears S. 10 1/2° W., 25.3 ft. dist., with scribe marks EC1/16 S2 BT visible on partially healed blaze.</p> <p style="padding-left: 40px;">A fir stump, 14 ins. diam., bears N. 84 1/2° W., 17.5 ft. dist., with a healed blaze.</p> <p>and a new reference monument</p> <p style="padding-left: 40px;">An iron rod, 30 ins. long, 5/8 in. diam., driven 28 ins. in the ground, for a reference monument, bears N. 46° 04' 04" E., 15.3 ft. dist., with aluminum cap mkd. RM CE1/16 15.3 FT TO COR S2 2019 and an arrow pointing to the cor.</p> <p>Corner is located on the W. edge of a graveled road, 12 ft. wide, bears S. 30° E. and N. 65° W.</p> <p style="text-align: center;">_____</p> <p>N. 89° 25' 43" W., beginning new measurement.</p>
<p>1293.69</p>	<p>The center 1/4 sec. cor. of sec. 2.</p>
<p>2588.05</p>	<p>The center W 1/16 sec. cor. of sec. 2, established by Lecklider, PE No. 4079, in June, 1959; perpetuated by Hoffine, PLS No. 2291, in 2016; and is accepted as the cor.; monumented with an iron rod, 5/8 in. diam., firmly set, with top 24 ins. below the surface of the ground, on the west edge of a rocky logging landing, with an orange plastic cap mkd. LONE ROCK TIMBER LS 2291, from which the remains of the bearing trees mkd. by Lecklider</p> <p style="padding-left: 40px;">A fir, 32 ins. diam., bears S. 66 3/4° E., 130.3 ft. dist., with scribe marks CW1/16 BT S2 visible on partially healed blaze.</p>

**Subdivision of Section 2,  
T. 26 S., R. 2 W., Willamette Meridian, Oregon**

FEET	
	<p>A fir stump, 26 ins. diam., bears S. 40 1/2° E., 61.9 ft. dist., no marks visible.</p> <p>A fir, 33 ins. diam., bears S. 7° E., 42.6 ft. dist., with scribe marks CW1/16 BT S2 visible on partially healed blaze.</p> <p>and the bearing objects mkd. by Hoffine</p> <p>An iron rod, 5/8 in. diam., firmly set, projecting 3 ins. above ground, bears N. 72° 16' 44" E., 184.20 ft. dist., with an orange plastic cap mkd. LONE ROCK TIMBER LS 2291.</p> <p>An iron rod, 5/8 in. diam., firmly set, projecting 7 ins. above ground, bears N. 89° 47' 12" E., 200.47 ft. dist., with an orange plastic cap mkd. LONE ROCK TIMBER LS 2291.</p> <p>A PK Nail, in the southerly end of a large rock outcropping, bears S. 67° 46' 50" W., 37.36 ft. dist.</p> <p>At the corner point</p> <p>Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 22 ins. in the ground, directly over the iron rod, in a large supporting mound of stone, to the top, with brass cap mkd.</p> <div style="text-align: center;"> <math display="block">\begin{array}{c} \text{W } 1/16 \\ \text{C} \text{ --- } \text{C} \\ \text{S } 2 \\ \text{2019} \end{array}</math> </div> <p>Corner is located W, 125 ft. dist., of an intersection of three graveled roads, each 16 ft. wide, bear S. 70° E., S. 45° W., and N. 10° W.</p> <hr style="width: 20%; margin: 10px auto;"/> <p>N. 89° 41' 02" W., beginning new measurement.</p>
1289.60	<p>The 1/4 sec. cor. of secs. 2 and 3.</p> <hr/> <p>From the N 1/16 sec. cor. of secs. 1 and 2.</p> <p>N. 89° 22' 00" W., on the E. and W. center line of the NE 1/4 of sec. 2.</p>
2595.62	<p>The center N 1/16 sec. cor. of sec. 2.</p> <hr/> <p>From the E 1/16 sec. cor. of secs. 2 and 11.</p> <p>N. 1° 17' 09" E., on the N. and S. center line of the SE 1/4 of sec. 2.</p>
1389.16	<p>The SE 1/16 sec. cor. of sec. 2 established by Lecklider, PE No. 4079, in June, 1959; monumented with an iron rod, 1/2 in. diam., firmly set, projecting</p>

**Subdivision of Section 2,  
T. 26 S., R. 2 W., Willamette Meridian, Oregon**

FEET	
	<p>12 ins. above ground, in a mound of stone, 2 ft. base, to the top, from which the bearing trees mkd. by Lecklider</p> <p style="padding-left: 40px;">A fir, 29 ins. diam., bears S. 17 3/4° E., 5.5 ft. dist., with a healed blaze.</p> <p style="padding-left: 40px;">A fir, 25 ins. diam., bears N. 7 1/2° W., 36.8 ft. dist., with a healed blaze.</p> <p>At the corner point</p> <p>Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 27 ins. in the ground, directly over the iron rod, in a collar of stone, with brass cap mkd.</p> <p style="text-align: center;">SE 1/16 S 2 2019</p> <hr style="width: 20%; margin: auto;"/> <p>N. 0° 59' 20" E., beginning new measurement.</p>
1370.06	<p>The center E 1/16 sec. cor. of sec. 2.</p> <hr/> <p>From the S 1/16 sec. cor. of secs. 1 and 2.</p> <p>N. 89° 47' 06" W., on the E. and W. center line of the SE 1/4 of sec. 2.</p>
1294.10	<p>The SE 1/16 sec. cor. of sec. 2.</p> <hr/> <p>S. 89° 45' 58" W., beginning new measurement.</p>
1296.77	<p>The center S 1/16 sec. cor. of sec. 2.</p> <hr/> <p>From the W 1/16 sec. cor. of secs. 2 and 11, reported by Bedell, Seibold, and Browning in 1992-95, monumented with a cor. tree, a fir, 24 ins. diam., with a healed blaze on the north face and a healed blaze on the south face, from which the remains of the accessories reported by Bedell, Seibold, and Browning</p> <p style="padding-left: 40px;">A cedar stump, 9 ins. diam., bears N. 27 1/4° E., 14.9 ft. dist., with a healed blaze.</p> <p style="padding-left: 40px;">A stainless steel post, 2 1/2 ins. diam., firmly set, projecting 6 ins. above ground, bears S. 45° E., 9.9 ft. dist., with a brass cap mkd. RM W1/16 S11 15 LKS 1995 and an arrow pointing to the cor.</p> <p>and a new reference monument</p> <p style="padding-left: 40px;">A stainless steel post, 28 ins. long, 2 1/2 ins. diam., set 26 ins. in the ground, for a reference monument, bears N. 59° 05' 41" E., 18.92 ft. dist., with brass cap mkd. RM W1/16 S2 18.9 FT. TO COR 2019 and an arrow pointing to the cor.</p>

**Subdivision of Section 2,  
T. 26 S., R. 2 W., Willamette Meridian, Oregon**

FEET	
	N. 1° 05' 48" E., on the N. and S. center line of the SW 1/4 of sec. 2.
1400.81	<p>The SW 1/16 sec. cor. of sec. 2, established by Lang, PLS No. 2295, in 2011; and is accepted as the cor.; monumented with an iron rod, 5/8 in. diam., firmly set, with top flush with the surface of the ground, from which the bearing trees mkd. by Lang</p> <p style="padding-left: 40px;">A fir, 18 ins. diam., bears S. 2 3/4° W., 68.7 ft. dist., with illegible scribe marks visible on partially healed blaze.</p> <p style="padding-left: 40px;">A fir, 15 ins. diam., bears N. 73 1/4° W., 61.3 ft. dist., with illegible scribe marks visible on partially healed blaze.</p> <p>At the corner point</p> <p>Drive the iron rod 5 ins. below the surface of a graveled road and add an aluminum cap mkd.</p> <p style="text-align: center;">SW 1/16 S 2 2019</p> <p>from which a new reference monument</p> <p style="padding-left: 40px;">An iron rod, 30 ins. long, 5/8 in. diam., driven 27 ins. in the ground, for a reference monument, bears N. 29° 07' 38" E., 32.70 ft. dist., with aluminum cap mkd. RM SW1/16 S2 32.7 FT TO COR 2019 and an arrow pointing to the cor.</p> <p>Corner is located E., 5 ft. dist., of the center line of a graveled road, 14 ft. wide, bears N. and S. 15° W.</p> <hr style="width: 25%; margin-left: auto; margin-right: auto;"/> <p>N. 1° 05' 32" E., beginning new measurement.</p>
1401.19	<p>The center W 1/16 sec. cor. of sec. 2.</p> <hr/> <p>From the center S 1/16 sec. cor. of sec. 2.</p> <p>N. 89° 59' 56" W., on the E. and W. center line of the SW 1/4 of sec. 2.</p>
1294.40	<p>The SW 1/16 sec. cor. of sec. 2.</p> <hr/> <p>S. 89° 59' 49" W., beginning new measurement.</p>
1291.69	<p>The S 1/16 sec. cor. of secs. 2 and 3.</p> <hr/> <p>From the center W 1/16 sec. cor. of sec. 2.</p> <p>N. 1° 13' 43" E., on the N. and S. center line of the NW 1/4 of sec. 2.</p>

**Subdivision of Section 2,  
T. 26 S., R. 2 W., Willamette Meridian, Oregon**

FEET	
1393.12	<p>The NW 1/16 sec. cor. of sec. 2, established by Lecklider, PE No. 4079, in June, 1959; perpetuated by Monrean, PLS No. 1830, in 2004, under M144-47 and CS65/49-34E; and is accepted as the cor.; monumented with an iron rod, 1/2 in. diam., firmly set, projecting 3 ins. above ground, in a collar of stone, from which the remains of the bearing trees mkd. by Lecklider</p> <p style="padding-left: 40px;">A fir, 40 ins. diam., bears S. 21° E., 24.3 ft. dist., with a healed blaze.</p> <p>and the remains of a bearing tree mkd. by Monrean</p> <p style="padding-left: 40px;">A burnt fir stump, 25 ins. diam., bears N. 59° W., 42.2 ft. dist., with lower portion of a healed blaze.</p> <p>At the corner point</p> <p>Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 16 ins. in the ground, to bedrock, directly over the iron rod, in a mound of stone, 3 ft. base, to the top, with brass cap mkd.</p> <p style="text-align: center;">NW 1/16 S 2 2019</p> <p>from which a new bearing tree</p> <p style="padding-left: 40px;">A fir, 11 ins. diam., bears N. 20° E., 31.4 ft. dist., mkd. NW 1/16 S2 BT.</p> <hr style="width: 20%; margin: 10px auto;"/> <p>N. 1° 03' 45" E., beginning new measurement.</p>
1376.75	<p>The W 1/16 sec. cor. of sec. 2 only, on the N. bdy. of the Tp., reported by Skeesick in 2010-11, monumented with an iron rod, 5/8 in. diam., firmly set, projecting 8 ins. above ground, with an aluminum cap mkd.</p> <p style="text-align: center;">W 1/16 S 2 2010</p> <p>from which the bearing trees reported by Skeesick</p> <p style="padding-left: 40px;">A fir, 22 ins. diam., bears S. 60 1/4° E., 42.8 ft. dist., with a healed blaze.</p> <p style="padding-left: 40px;">A fir, 16 ins. diam., bears S. 21 1/4° E., 19.2 ft. dist., with a healed blaze.</p> <p>From this cor., a point established as the W 1/16 sec. cor. of sec. 2 only, on the N. bdy. of the Tp., by Lecklider, PE No. 4079, in June, 1959, and rejected by Skeesick, bears N. 23° 53' 16" E., 8.87 ft. dist.; monumented with an iron rod, 1/2 in. diam., firmly set, projecting 6 ins. above ground, from which the bearing trees reported by Skeesick</p> <p style="padding-left: 40px;">A fir, 12 ins. diam., bears S. 24 1/2° E., 17.6 ft. dist., with a healed blaze.</p>

**Subdivision of Section 2,  
T. 26 S., R. 2 W., Willamette Meridian, Oregon**

FEET	
	<p style="text-align: center;">A fir, 24 ins. diam., bears N. 86° W., 2.4 ft. dist., with a healed blaze.</p> <hr/> <p>From the center N 1/16 sec. cor. of sec. 2.</p> <p>N. 89° 15' 27" W., on the E. and W. center line of the NW 1/4 of sec. 2.</p>
1291.16	<p>The NW 1/16 sec. cor. of sec. 2.</p> <hr/> <p>N. 89° 04' 05" W., beginning new measurement.</p>
1294.07	<p>The N 1/16 sec. cor. of secs. 2 and 3.</p> <hr/> <p style="text-align: center;"><b>Subdivision of Section 10, T. 26 S., R. 2 W., Willamette Meridian, Oregon</b></p> <hr/> <p>From the 1/4 sec. cor. of secs. 10 and 15, reported by Zirpel, Jr., and Glenn in 1959; perpetuated by Edwards, PLS No. 2339, in 2009; monumented with an iron post, 2 1/2 ins. diam., firmly set, projecting 4 ins. above ground, in a collar of stone, with a brass cap mkd.</p> <div style="text-align: center;"> <p>T 26 S R 2 W</p> <p style="margin-left: 100px;">S 10</p> <p style="margin-left: 100px;">1/4 ———</p> <p style="margin-left: 100px;">S 15</p> <p style="margin-left: 100px;">1959</p> </div> <p>from which the remains of the bearing trees reported by Zirpel, Jr., and Glenn</p> <p style="margin-left: 40px;">A decayed fir stump, 18 ins. diam., bears S. 67 1/4° E., 90.4 ft. dist., no marks visible. (Record, S. 65 1/4° E.)</p> <p style="margin-left: 40px;">A decayed fir stump, 44 ins. diam., bears N. 27 1/4° W., 29.4 ft. dist., with a healed blaze.</p> <p>and the bearing trees mkd. by Edwards</p> <p style="margin-left: 40px;">A cedar, 7 ins. diam., bears N. 32 1/2° E., 28.1 ft. dist., with scribe marks 1/4 S10 BT visible on partially healed blaze.</p> <p style="margin-left: 40px;">A cedar, 10 ins. diam., bears S. 64 1/4° E., 8.8 ft. dist., with scribe marks 1/4 S15 BT visible on partially healed blaze.</p> <p>N. 0° 53' 57" E., on the N. and S. center line of sec. 10.</p>
2706.66	<p>The center 1/4 sec. cor. of sec. 10, established by Lecklider, PE No. 4079, in December, 1959; and is accepted as the cor.; monumented with an iron post, 5/8 in. diam., firmly set, projecting 3 ins. above ground, in a collar of stone, with an aluminum cap mkd. PROPERTY CORNER, from which the remains of the bearing trees mkd. by Lecklider</p>

**Subdivision of Section 10,  
T. 26 S., R. 2 W., Willamette Meridian, Oregon**

FEET	
1342.34	<p>A fir, 33 ins. diam., bears S. 35 3/4° E., 23.4 ft. dist., with a healed blaze.</p> <p>A fir stump, 25 ins. diam., bears N. 6 1/4° W., 55.0 ft. dist., with a healed blaze.</p> <p>At the corner point</p> <p>Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 26 ins. in the ground, directly over the iron rod, in a collar of stone, with brass cap mkd.</p> <p style="text-align: center;">T 26 S R 2 W C 1/4 S 10 2018</p> <p>from which a new bearing tree</p> <p style="padding-left: 40px;">A fir, 9 ins. diam., bears N. 34 1/2° E., 26.9 ft. dist., mkd. C1/4 S10 BT.</p> <hr style="width: 20%; margin: 10px auto;"/> <p>N. 0° 52' 49" E., beginning new measurement.</p> <p>Point for the center N 1/16 sec. cor. of sec. 10, established by Garrett, PLS No. 544, in 1969; and is accepted as the cor.; as determined at record distances from the remains of the bearing trees mkd. by Garrett</p> <p style="padding-left: 40px;">A broken, decayed fir snag, 12 ins. diam., bears N. 42 1/4° E., 10.9 ft. dist., with the lower portion of a healed blaze visible.</p> <p style="padding-left: 40px;">A decayed cedar snag, 31 ins. diam., bears N. 57° W., 46.9 ft. dist., no marks visible.</p> <p>At the corner point</p> <p>Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 26 ins. in the ground, in a collar of stone, with brass cap mkd.</p> <p style="text-align: center;">C N 1/16   S 10 C 2018</p> <p>from which new bearing trees</p> <p style="padding-left: 40px;">A cedar, 9 ins. diam., bears S. 58 1/2° E., 17.2 ft. dist., mkd. CN1/16 S10 BT.</p> <p style="padding-left: 40px;">A cedar, 5 ins. diam., bears S. 77 1/4° W., 22.8 ft. dist., mkd. X BT.</p> <p>Corner is located in a cut bank, E., 18 ft. dist., of a dirt road, 14 ft. wide, bears S. and N. 15° W.</p> <hr style="width: 20%; margin: 10px auto;"/>

**Subdivision of Section 10,  
T. 26 S., R. 2 W., Willamette Meridian, Oregon**

FEET	
1342.89	<p>N. 0° 50' 03" E., beginning new measurement.</p> <p>The 1/4 sec. cor. of secs. 3 and 10, reported by Zirpel, Jr., and Glenn in 1959; perpetuated by Hoffine, PLS No. 2291, in April, 2015; monumented with an iron post, 2 1/2 ins. diam., firmly set, projecting 4 ins. above ground, with a brass cap mkd.</p> <p style="text-align: center;">T 26 S R 2 W S 3 1/4 ——— S 10 1959</p> <p>from which the bearing tree reported by Zirpel, Jr., and Glenn</p> <p style="padding-left: 40px;">A fir, 23 ins. diam., bears S. 59 1/4° E., 27.7 ft. dist., with a healed blaze.</p> <p>and a bearing tree mkd. by Hoffine</p> <p style="padding-left: 40px;">A hemlock, 9 ins. diam., bears N. 1 3/4° W., 21.4 ft. dist., with scribe marks 1/4 S3 BT visible on partially healed blaze.</p> <p>Corner is located S., 30 ft. dist., of a draw, drains N. 60° W.</p> <hr/> <p>From the 1/4 sec. cor. of secs. 10 and 11, reported by Bedell, Seibold, and Browning in 1992-95, monumented with a stainless steel post, 2 1/2 ins. diam., firmly set, projecting 4 ins. above ground, with a brass cap mkd.</p> <p style="text-align: center;">T 26 S R 2 W 1/4 S 10   S 11 1993</p> <p>from which the bearing trees reported by Bedell, Seibold, and Browning</p> <p style="padding-left: 40px;">A fir, 14 ins. diam., bears N. 87 3/4° E., 15.2 ft. dist., with a healed blaze.</p> <p style="padding-left: 40px;">A fir, 24 ins. diam., bears N. 41 3/4° W., 18.5 ft. dist., with a healed blaze.</p> <p>From this cor., a point erroneously established as the 1/4 sec. cor. of secs. 10 and 11, rejected by Bedell, Seibold, and Browning, bears S. 7° 37' 30" E., 19.73 ft. dist.; monumented with an iron post, 5/8 in. diam. (Record, 1/2 in. diam.), firmly set, projecting 5 ins. above ground, with an aluminum cap mkd. PROPERTY CORNER; from which the bearing trees reported by Bedell, Seibold, and Browning</p> <p style="padding-left: 40px;">A fir, 23 ins. diam., bears N. 47 1/4° E., 15.2 ft. dist., with a healed blaze.</p> <p style="padding-left: 40px;">A fir, 21 ins. diam., bears N. 59° W., 13.2 ft. dist., with a healed blaze.</p> <p>N. 89° 21' 20" W., on the E. and W. center line of sec. 10.</p>

**Subdivision of Section 10,  
T. 26 S., R. 2 W., Willamette Meridian, Oregon**

FEET	
1297.71	<p>The center E 1/16 sec. cor. of sec. 10, established by Lecklider, PE No. 4079, in December, 1959; perpetuated by Hoffine, PLS No. 2291, in September, 2015; and is accepted as the cor.; monumented with an iron rod, 5/8 in. diam., firmly set, projecting 2 ins. above ground, in a collar of stone, with an aluminum cap mkd. LONE ROCK TIMBER E1/16 C-C S10 2015 PLS2291, from which the bearing trees mkd. by Lecklider</p> <p style="margin-left: 40px;">A cedar, 29 ins. diam., bears N. 58 1/4° E., 10.4 ft. dist., with a healed blaze.</p> <p style="margin-left: 40px;">A fir, 35 ins. diam., bears S. 56 1/2° E., 41.9 ft. dist., with a healed blaze.</p> <p>At the corner point</p> <p>Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 26 ins. in the ground, directly over the iron rod, in a collar of stone, with brass cap mkd.</p> <div style="text-align: center; margin: 10px 0;"> <math display="block">\begin{array}{c} \text{E } 1/16 \\ \text{C} \text{-----} \text{C} \\ \text{S } 10 \\ 2018 \end{array}</math> </div> <p>Corner is located S., 22 ft. dist., of a graveled road, 16 ft. wide, bears S. 50° E. and N. 50° W.</p> <hr style="width: 20%; margin: 10px auto;"/> <p style="margin-left: 40px;">N. 89° 57' 07" W., beginning new measurement.</p>
1294.08	<p>The center 1/4 sec. cor. of sec. 10</p> <hr style="width: 20%; margin: 10px auto;"/> <p style="margin-left: 40px;">S. 89° 55' 51" W., beginning new measurement.</p>
2592.38	<p>The 1/4 sec. cor. of secs. 9 and 10, reported by Rogers in 1979, monumented with an iron post, 2 1/2 ins. diam., firmly set, projecting 14 ins. above ground, in a mound of stone, 3 ft. base, 12 ins. high, with a brass cap mkd.</p> <div style="text-align: center; margin: 10px 0;"> <math display="block">\begin{array}{c} \text{T } 26 \text{ S } \text{ R } 2 \text{ W} \\ 1/4 \\ \text{S } 9 \text{   } \text{S } 10 \\ 1959 \end{array}</math> </div> <p>from which the bearing trees reported by Rogers</p> <p style="margin-left: 40px;">A fir, 19 ins. diam., bears S. 48 1/2° E., 4.6 ft. dist., with a healed blaze.</p> <p style="margin-left: 40px;">A fir, 18 ins. diam., bears N. 25 1/4° W., 10.6 ft. dist., with a healed blaze.</p> <p>Corner is located at the top of a rock bluff, edge bears N and S.</p> <hr style="width: 20%; margin: 10px auto;"/> <p>From the center E 1/16 sec. cor. of sec. 10.</p>

**Subdivision of Section 10,  
T. 26 S., R. 2 W., Willamette Meridian, Oregon**

FEET	
1327.13	<p>N. 0° 38' 58" E., on the N. and S. center line of the NE 1/4 of sec. 10.</p> <p>Point for the NE 1/16 sec. cor. of sec. 10, at intersection with the E. and W. center line of the NE 1/4.</p> <p>Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 24 ins. in the ground, in a collar of stone, with brass cap mkd.</p> <p style="text-align: center;">NE 1/16 S 10 2018</p> <p>from which</p> <p style="padding-left: 40px;">A madrone, 14 ins. diam., bears N. 22 1/4° E., 16.0 ft. dist., mkd. NE 1/16 S10 BT.</p> <p style="padding-left: 40px;">A fir, 5 ins. diam., bears N. 44 3/4° W., 21.6 ft. dist., mkd. NE 1/16 S10 BT.</p>
2664.14	<p>The E 1/16 sec. cor. of secs. 3 and 10, reported by Zirpel, Jr., and Glenn in 1959; perpetuated by person(s) unknown; monumented with an iron post, 2 1/2 ins. diam., firmly set, projecting 16 ins. above ground, in a mound of stone, 2 ft. base, 12 ins. high, with a brass cap mkd.</p> <p style="text-align: center;">S 3 E 1/16 ——— S 10 1959</p> <p>from which the remains of the bearing trees reported by Zirpel, Jr., and Glenn</p> <p style="padding-left: 40px;">A fir, 24 ins. diam., bears S. 53 1/4° E., 12.2 ft. dist., with a healed blaze.</p> <p style="padding-left: 40px;">A roothole bears N. 56° W., 22.4 ft. dist., alongside of which is a down decayed fir, 24 ins. diam., with a healed blaze.</p> <p>and the remains of a bearing tree mkd. by person(s) unknown</p> <p style="padding-left: 40px;">A fir snag, 20 ins. diam., bears N. 40° W., 57.4 ft. dist., with illegible scribe marks visible on partially healed blaze.</p> <p>and a new bearing tree</p> <p style="padding-left: 40px;">A maple, 13 ins. diam., bears N. 25 3/4° W., 5.7 ft. dist., mkd. E1/16 S3 BT on bark.</p> <p>Corner is located W., 120 ft. dist., of a ravine, drains N. 5° W.</p> <hr/> <p>From the N 1/16 sec. cor. of secs. 10 and 11, reported by Bedell, Seibold, and Browning in 1992-95, monumented with a stainless steel post, 2 1/2 ins. diam., firmly set, projecting 4 ins. above ground, with a brass cap mkd.</p>

**Subdivision of Section 10,  
T. 26 S., R. 2 W., Willamette Meridian, Oregon**

FEET	<p align="center">N 1/16 S 10   S 11 1993</p> <p>from which the bearing trees reported by Bedell, Seibold, and Browning</p> <p style="padding-left: 40px;">A fir, 19 ins. diam., bears S. 55° E., 48.2 ft. dist., with a healed blaze.</p> <p style="padding-left: 40px;">A fir, 24 ins. diam., bears N. 34 3/4° W., 15.2 ft. dist., with a healed blaze.</p> <p>From this cor., a point erroneously established as the N 1/16 sec. cor. of secs. 10 and 11, rejected by Bedell, Seibold, and Browning, bears S. 7° 36' 00" E., 9.83 ft. dist.; monumented with an iron post, 5/8 in. diam. (Record, 1/2 in. diam.), firmly set, projecting 3 ins. above ground, with an aluminum cap mkd. PROPERTY CORNER; from which the remains of the bearing tree reported by Bedell, Seibold, and Browning</p> <p style="padding-left: 40px;">A pine snag, 35 ins. diam., bears N. 45 1/2° E., 29.0 ft. dist., with a healed blaze.</p> <p>N. 89° 16' 50" W., on the E. and W. center line of the NE 1/4 of sec. 10.</p>
1286.71	The NE 1/16 sec. cor. of sec. 10.
2575.23	The center N 1/16 sec. cor. of sec. 10.
<hr/> <p><b>Subdivision of Section 13, T. 26 S., R. 2 W., Willamette Meridian, Oregon</b></p> <hr/>	
	<p>From the 1/4 sec. cor. of secs. 13 and 24, reported by Mensch in 1916-18; perpetuated by Godfrey, Douglas County Deputy Surveyor, in October, 1961; subsequently perpetuated by Monrean, PLS No. 1830, in December, 1984; monumented with an iron post, 1 1/4 ins. diam., firmly set, projecting 10 ins. above ground, with a brass cap mkd.</p> <p align="center">COUNTY SURVEYORS OFFICE T 26 S R 2 W S 13 1/4 _____ S 24 1961</p> <p>from which the remains of a bearing tree mkd. by Mensch</p> <p style="padding-left: 40px;">A fir stump, size indeterminate, bears S. 18 1/4° W., 32.6 ft. dist., with scribe marks 1/4 S24 visible on open blaze facing east. Determined to be disturbed and out of position. (Record, S. 47 1/2° W., 17.2 ft. dist.)</p> <p>and the bearing trees mkd. by Godfrey</p>

**Subdivision of Section 13,  
T. 26 S., R. 2 W., Willamette Meridian, Oregon**

FEET	
	<p>A cedar, 29 ins. diam., bears N. 30 1/4° E., 38.0 ft. dist., with a healed blaze.</p> <p>A fir, 30 ins. diam., bears S. 10 1/2° W., 50.5 ft. dist., with a healed blaze.</p> <p>and the bearing trees mkd. by Monrean</p> <p>A fir, 20 ins. diam., bears S. 85° W., 94.7 ft. dist., with a healed blaze.</p> <p>A cedar, 6 ins. diam., bears N. 47 1/4° W., 53.9 ft. dist., with illegible scribe marks visible on partially healed blaze.</p> <p>Corner is located W., 50 ft. dist., of Boundary Road, graveled surface, 14 ft. wide, bears N. 20° E. and S. 20° W. and located N., 20 ft. dist., of a dirt road, 8 ft. wide, bears S. 35° E. and N. 35° W.</p> <p>N. 1° 10' 00" W., on the N. and S. center line of sec. 13.</p>
1220	Creek, 5 ft. wide, course S. 35° W.
1348.45	<p>Point for the center S 1/16 sec. cor. of sec. 10.</p> <p>Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 24 ins. in the ground, in a collar of stone, with brass cap mkd.</p> <div style="text-align: center;"> <p>C</p> <p>S 1/16   S 13</p> <p>C</p> <p>2018</p> </div> <p>from which</p> <p>A fir, 9 ins. diam., bears S. 63 1/2° E., 30.2 ft. dist., mkd. X BT.</p> <p>A fir, 14 ins. diam., bears S. 62 3/4° W., 18.4 ft. dist., mkd. CS 1/16 S13 BT.</p> <p>From this cor., a point established by person(s) unknown for unknown purpose, and was not utilized for control in this survey, bears S. 11° 49' 39" W., 11.09 ft. dist.; monumented with an iron pipe, 1 in. diam., firmly set, projecting 22 ins. above ground. Pipe is bent to the northwest.</p> <p>Corner is located W., 85 ft. dist., of a creek, 4 ft. wide, course S. 10° W.</p>
2540	Creek, 4 ft. wide, course S. 80° E.
2696.90	<p>Point for the center 1/4 sec. cor. of sec. 13, at intersection with the E. and W. center line.</p> <p>Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 26 ins. in the ground, in a collar of stone, with brass cap mkd.</p>

**Subdivision of Section 13,  
T. 26 S., R. 2 W., Willamette Meridian, Oregon**

FEET	<p>T 26 S R 2 W C 1/4 S 13 2018</p>
	<p>from which</p> <p style="padding-left: 40px;">A fir, 6 ins. diam., bears S. 70 1/2° E., 3.3 ft. dist., mkd. C1/4 S13 BT.</p> <p style="padding-left: 40px;">A cedar, 7 ins. diam., bears N. 28 1/2° W., 30.8 ft. dist., mkd. C1/4 S13 BT.</p>
3986.49	<p>The center N 1/16 sec. cor. of sec. 13, established by Hoffine, PLS No. 2291, in 2007; and is accepted as the cor.; monumented with an iron rod, 5/8 in. diam., firmly set, projecting 1 in. above ground, with an aluminum cap mkd. LONE ROCK TIMBER C N1/16 S13 C 2007 PLS2291, from which the accessories established by Hoffine</p> <p style="padding-left: 40px;">An iron rod, 5/8 in. diam., firmly set, projecting 3 ins. above ground, bears N. 86° 42' 01" E., 149.81 ft. dist., with a yellow plastic cap mkd. LONE ROCK TIMBER LS 2291.</p> <p style="padding-left: 40px;">A fir, 28 ins. diam., bears S. 48° E., 56.7 ft. dist., with a healed blaze.</p> <p style="padding-left: 40px;">An iron rod, 5/8 in. diam., firmly set, projecting 1 in. above ground, bears S. 1° 04' 02" E., 192.69 ft. dist., with a yellow plastic cap mkd. LONE ROCK TIMBER LS 2291.</p> <p style="padding-left: 40px;">A fir, 46 ins. diam., bears S. 74 1/2° W., 50.8 ft. dist., with a healed blaze.</p> <p>At the corner point</p> <p>Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 25 ins. in the ground, directly over the iron rod, with brass cap mkd.</p> <div style="text-align: center; margin: 10px 0;"> <p>C N 1/16   S 13 C 2018</p> <hr style="width: 20%; margin: 0 auto;"/> </div> <p>N. 1° 09' 29" W., beginning new measurement.</p>
1288.91	<p>The 1/4 sec. cor. of secs. 12 and 13, reported by Roseberry in 1968; perpetuated by Hoffine, PLS No. 2291, in 1999; monumented with an iron post, 2 1/2 ins. diam., firmly set, projecting 6 ins. above ground, with a brass cap mkd.</p> <div style="text-align: center; margin: 10px 0;"> <p>T 26 S R 2 W S 12 1/4 ——— S 13 1968</p> </div>

**Subdivision of Section 13,  
T. 26 S., R. 2 W., Willamette Meridian, Oregon**

FEET	
	<p>from which the remains of the bearing trees reported by Roseberry</p> <p style="padding-left: 40px;">A burnt fir stump, 28 ins. diam., bears N. 85 1/2° E., 199.3 ft. dist., with a healed blaze. (Record, N. 84° E.)</p> <p style="padding-left: 40px;">A fir, 30 ins. diam., bears S. 14° W., 147.8 ft. dist., with a healed double blaze. (Record, S. 12° W.)</p> <p>and the remains of the bearing trees mkd. by Hoffine</p> <p style="padding-left: 40px;">A fir stump, 23 ins. diam., bears S. 34 1/4° E., 32.3 ft. dist., with a healed blaze.</p> <p style="padding-left: 40px;">A fir stump, 24 ins. diam., bears N. 86 1/4° W., 23.6 ft. dist., with a healed blaze.</p> <p>and new bearing trees</p> <p style="padding-left: 40px;">A fir, 8 ins. diam., bears N. 40° E., 63.3 ft. dist., mkd. 1/4 S12 BT.</p> <p style="padding-left: 40px;">A fir, 8 ins. diam., bears S. 45° W., 16.9 ft. dist., mkd. 1/4 S13 BT.</p> <p>Corner is located S., 60 ft. dist., of a graveled road, 18 ft. wide, bears N. 60° E. and S. 50° W.</p> <hr/>
	<p>From the 1/4 sec. cor. of secs. 13 only.</p> <p>S. 86° 28' 51" W., on the E. and W. center line of sec. 13.</p>
2738.01	The center 1/4 sec. cor. of sec. 13.
5363.18	The 1/4 sec. cor. of secs. 13 and 14.
	<hr/> <p>From the S 1/16 sec. cor. of sec. 13 only.</p> <p>S. 86° 04' 37" W., on the E. and W. center line of the SE 1/4 of sec. 13.</p>
2680.99	The center S 1/16 sec. cor. of sec. 13.
	<hr/> <p>From the center S 1/16 sec. cor. of sec. 13.</p> <p>S. 87° 39' 46" W., on the E. and W. center line of the SW 1/4 of sec. 13.</p>
2633.03	The S 1/16 sec. cor. of secs. 13 and 14.
	<hr/>

