

129-5

6-53

Sta.	Dist.	L.	Rt.	Mag.	C.C.
S.W. Cor.	399.8		7°-38'	S 56. W	S 56-11 W
Δ 10 4-15° 30°	273° 299.2		137°-27'	S 49-30 W	S 48-33 W
Δ 9 7-30 159'	157.7	0-52		S 88-30 E	S 88° 54 E
Δ 8	103.4		1° 00	S 88-30 E	S 88° 02 E
Δ 7 13-30 231'	226.2	12°-16'		S 87-30 E	S 89-02 E
Δ 6 6-30 172'	171.5		22-07'	S 76-30 E	S 76-46 E
Δ 5 24-15° 106° att corner	97.2		29°-12'	N 81-30 E	N 81-07 E
Δ 4 37-15 104'	88.3		59-39'	N 53 E	N 51-55 E
Δ 3 15-30 172'	166.1	2°-55		N 7 W	N 7° 44 W
Δ 2 23 204	166.36	0-19'		N 4-30 W	N 4°-49 W
Δ 1 23-30 248'	228.3				N 4-30 W
S.W. Cor.					

6-53

N. L. Epstein
J. H. Walford
A. W. Caswell
G. E. Trask

Δ9 = in Road on line ?
0

supposed
FROM 6 to bc corner of a
corner B bearing to pin N77-24E
" " B. O. N78-30E 29-5
L FROM 5-25 Left.

From Δ4 a 16' B. Oak. Bear N1°W 140'
L From 3 = 54-06 Left

From Δ3 a 4' Madrone B ~ N51-30W
56.

on what line of place N on road
6/53

T29-5

corner lot by Eppstein
& W. S. Creaf.

March 13 1928

N.W. cor of DHC #50

Set corner from old B.T. N24
43 lbs. marker mark for
B.T. Plain, set 1 1/2" x 20 lb.
marked 15" Fir N19E 22 lbs

12" " N57W 16 "

1/4 Cor between Sec 24 & 25

Set 3" x 3" x 3" Cedar post
from Old B.T. N75E 23 lbs.
marker mark for B.T.

Marked NW. B.T.

12" Cedar N50W 87 lbs.


10" Fir N74E 63 " "

J G DICKS 75-517

A W Caswell { ~~84-111~~
85-511

Oscar R Pollard Vol 85-
636

Geo E Trank Vol 50-78
59 171



29-5

C. S. File No. 4/53

Description of a part of D.L.C. No. 50, T 29 S, R 5 W, W.M.

Beginning at the Exterior L Corner of the Hugh Carson D.L.C. No. 50 in T 29 S, R 5 W, W.M., Douglas County, Oregon, thence East 11.37 chains along the North line of said D.L.C. No. 50 to a point 0.63 chains West of the Interior L Corner of said D.L.C. No. 50, thence along the center of the County Road S 47°20'W 8.89 chains and S 56°11'W 5.81 chains to a point on the West line of said D.L.C. No. 50, thence North 9.26 chains to the place of beginning containing 56.62 acres more or less.

County Surveyors office
March 3, 1928
File 6-53

C. S. File No. 6-53

List of All the Registered Voters in Precinct, in County,
 Oregon, for the General Election to be Held in Said Precinct on the Second Day of November, 1926.

	SURNAME AND GIVEN NAME	PARTY	VOTED	BALLOT NUMBER	REMARKS
1	<i>Quaker Weeds</i>				
2	Beginning at pt 2.94 chs S from NW cor of Hugh Carson L. & C. #50 T29-5				
3	Thence S 17.25 ch to the North side of County Road running up S Myrtle Creek,				
4	Thence N 40°-30' E along the North side of road 7.50 ch				
5	Thence N 59°-45' E 3.36 ch along road				
6	Thence North variation 18° 45' E, 9.98 ch				
7	Thence S 85° W 8.46 chain to place beginning containing 12.03 acres				
8					
9					
10					
11	<i>Pollard.</i>				
12	Beginning at the South West Corner of Hugh Carson L. & C. #50 T29-5				
13	Thence East along South line of said C. #50 N				
14	24.19 ch to a stake from which an ash tree 22" dia marked X bears				
15	West 35 lbs, also a ash tree 22" dia marked X bears N 72° E 53 lbs				
16	Thence N 18° W 8 chains to a stake from which an alder 20" dia bears S 21° E 8 lb marked X				
17	Thence N 50-30 W 3 chains to a stake				
18	" N 21° W 12 " to center of County Road				
19	Thence S 40° W along Center of County Road 8.2 to West line of claim thence				
20	South along West line of claim to L corner 7 1/4 links				
21					
22					
23					
24					
25					
26					
27					
28					

C. S. File No. 6/53

Thence West along North line of L 63
miles to center of County Road. Thence South
 49° West along Center of road 10.50 chains
Thence 55° W 4.00 chains to the West line
of the above named claim. Thence
South along West line of claim 5.90
chains to place of beginning containing
28,89 acres

Caswell Deal
Hugh Carson & Co,
Exception, - W T Morrison
commencing at the corner N, W corner
of said L 63 of Carson
Thence East 195 rods
" South 17 " to County Road
" South along County Road
to West line of claim
Thence N 82 rods to place of beginning

Exception W P Johnson & Co

to
Cornet's Cells Vol 47-378.

" Dick to a Manley " 66-366-67
see Pollard Deal

List of All the Registered Voters in Precinct, in County,
Oregon, for the General Election to be Held in Said Precinct on the Second Day of November, 1926.

	SURNAME AND GIVEN NAME	PARTY	VOTED	BALLOT NUMBER	REMARKS
	Dickens Mary				
1	Beginning at the SW corner of Cass				
2	Sec 50, T29S R5W				
3	Thence East along S line 24.19 ch				
4	see Pollack deed,				
5	Johnson lumber Co to Allen				
6					
7	Beginning at N.E. cor Cass Sec 50				
8	42 T29S-4				
9	Thence West along N line said claim				
10	25.25 ch				
11	Thence S 4.7 ch to center of county				
12	Road				
13	Thence along road N 84 1/2° W 8.00 ch				
14	Thence S 4° 48" E 35.20 ch to south				N
15	line of claim				
16	Thence East along south line 30.60 ch				
17	to S.E. corner of claim				
18	Thence North 39° E ch to place				
19	of beginning				
20					
21					
22					
23					
24					
25					
26					
27					
28					

J. S. File No. 6/53

CLERKS OF ELECTION MUST CHECK OFF VOTERS' NAMES IN "VOTED" COLUMN AT TIME OF VOTING

Location

Sheet No.

TRAVERSE SURVEY AND CALCULATION OF AREA

Final Closure

Computed by

Bowker

Checked by

Date *March 3 1928*

Owner

STATION	COURSES BEARINGS DISTANCE	L. COG.	LATITUDE		D. SIN.	DEPARTURE		BALANCED		M. D.	D. M. D.	N AREA	S AREA
			NORTH	SOUTH		EAST	WEST	NORTH	SOUTH				
Mill Cor	East 750.4	(53)				750.4		619.6			750.4		
✓	S49°20'W 587.0	677.68		397.8	735.43		431.7	619.6	14.1		1969.1		
#10	S56°11'W 383.6	556.54		213.5	8308.2		318.7	221.8	332.8		318.7		68,042.45
DL. Cline	North 611.3	9.26	611.3					8.3	14.1		0.0		
Mill Cor			611.3	611.3		750.4	750.4	619.6	14.1				493,330.43
													246,665.21
													56,625.15

Location _____

Sheet No. _____

Dicks Reed

Computed by _____

Checked by _____

Owner _____

Date _____

192

TRAVERSE SURVEY AND CALCULATION OF AREA

STATION	COURSES BEARINGS DISTANCE	L. COS.	LATITUDE		D. SIN.	DEPARTURE		BALANCED		M. D.	D. M. D.	N AREA	S AREA
			NORTH	SOUTH		EAST	WEST	NORTH	SOUTH				
	South 17.25			17.25									
	N48°30'E 7.50	76041			64945	4.87							
	N59°45'E 3.36	56377			86384	2.90							
	North 9.98												
	S85°W 8.46	58716			99619	8.43							
			17.37	17.99		7.77	8.43						
	Coast												

Location Pollock Deed

TRAVERSE SURVEY AND CALCULATION OF AREA

Sheet No. _____

Owner _____

Computed by _____

Checked by _____

Date _____ 192__

STATION	COURSES BEARINGS DISTANCE	L. COS.	LATITUDE		D. SIN.	DEPARTURE		BALANCED		M. D.	D. M. D.	N AREA	S AREA
			NORTH	SOUTH		EAST	WEST	NORTH	SOUTH				
	East 24.19					24.19							
	N18W 8.0	95106	7.61		30902		2.47						
	N5°30W 3.0	99540	2.99		09585		0.29						
	N21W 12.0	93358	11.20		35837		4.30						
	S40W 8.2	76604		6.28	64229		5.27						
	South 0.74				0.74								
	West 0.63				0.63								
	S49W 10.50	65606		6.89	75471		7.92						
	S57W 4.0	54464		2.18	83867		3.35						
	South 5.90				5.90								
			21.80			21.99							
						24.19	24.23						

Location

Sheet No.

Eppsteins Traverse

TRAVERSE SURVEY AND CALCULATION OF AREA

Owner

Computed by

Checked by

Date

192

STATION	BEARINGS	COURSES	DISTANCE	L. COS.	LATITUDE		D. SIN.	DEPARTURE		BALANCED		M. D. N	D. M. D. S	AREA	E	W	AREA
					NORTH	SOUTH		EAST	WEST	NORTH	SOUTH						
SW Co		N43°00'	228.3	99692		227.6	07846							0.0			0.0
1		N4-49W	186.36	99647		185.7	08397							228.2			17.9
2		N74°40'	166.1	99091		164.6	13456										33.5
3		N51°55'E	88.3	61681		54.5	78111										55.8
4		N81°07'E	97.2	15442		15.0	98800										13.6
5		S76°46'E	171.5	22892			97354										109.4
6		S89°02'E	226.2	01687			99986										276.1
7		S88°02'E	103.4	03432			99941										501.8
8		S88°54'E	157.7	01920			99982										604.9
9		S48°33'W	572.2	66197			74953										782.4
10		S56°11'W	399.8	55654			83082										382.8
SW Co																	0.0
																	0.0

$\frac{647.7}{650.8}$
 $\frac{647.7}{647.7}$
 $\frac{647.7}{647.7}$

$\frac{819.6}{816.8}$
 $\frac{819.6}{819.6}$
 $\frac{819.6}{819.6}$

C. S. File No. 653

Begin at the Exterior L corner of ~~D.C. #~~ Hugh Carson
D.C. #50 in T 29 S R 5 W. W.M. Douglas County,
Oregon thence East 11.37 chains along D.L.C.
line to a point in the ^{center} of County Road and 0.63
chains West of the Interior L corner of said
D.C. #50 thence along the center of the
County Road $547^{\circ} 20' W$ 8.89 chains and
 $556^{\circ} 11' W$ 5.81 chains to a point on
the West line of said D.C. #50 thence
North 9.26 chains to the place of
beginning containing 56.62 Acres more
or less.

