

BLAINE H. MCGILLICUDDY
 FOREST ENGINEER
 1970 CHARNELTON STREET
 EUGENE, OREGON

42774

March 5, 1951

Mr. Ben B. Irving
 County Surveyor
 Roseburg, Oregon

Dear Sir:


In reference to the Section corner common to Sections 6,7,1 and 12 Twp. 22 S. R. 4 and 5 West, Douglas County, Oregon.

Found the original bearing tree described as a Fir 20" S 18 E. 68 links distance. This tree is now a windfall and the remaining three trees are defaced and burned by fire. Found the original post in place. I replaced the post with a new post 5"x5"x 5 feet long and an iron 1-1/8" by 16 inches long from which I scribed four new bearing trees i.e;

- 14" Chinquapin S 30° E. 14.5 Feet, marked
 Tp. 22 S.R. 4 W. S 7 B. T.
- 42" Fir S 7° 15' W. 40.1 Feet, marked
 Tp. 22 S.R. 5 W. S 12 B.T.
- 38" Fir N 79° W. 57.9 Feet, marked
 Tp. 22 S.R. 5 W. S 1 B. T.
- 18" Incense Cedar N 15° 30' E. 46.0 Feet, marked
 Tp. 22 S.R. 4 W. S 6 B.T.

The South $\frac{1}{4}$ corner of Section 12 Tp 22 S.R. 5 W., is in.

Very truly yours,


 B.H. McGillicuddy