

RE-NEWED CORNERS

Sec. 4, T.32 S., R.3 W. W. M.

May 10, 1951
June 21, 1951.

The southwest section corner stake being prone and too rotten to withstand redriving, I drove a $\frac{3}{4}$ " o.d. iron pipe 30" long, 24" into the round in the place of the wooden stake.

The south $\frac{1}{4}$ corner, (i.e. bet. sec. 4 and sec. 9) being difficult to recognize. that is the stake being gone and both bearing trees being down, I drove a 4 foot fir post squared to 4 inches at the top end, firmly into the ground at the point S.20°E, 7.92 feet from the hole made by the down, scribed, 10" fir, as given in the original survey notes, from which,

A fir 33" dia. bears S.50°W. 14.2 feet, mkd. $\frac{1}{4}$ S.B.T.

A fir 26" dia. bears N.51°E. 6.1 feet, mkd. $\frac{1}{4}$ S.B.T.

FILED
RECEIVED
JUN 25 1951
COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

