

ARTHUR BOYER
ROSEBURG, OREGON

FILED
RECEIVED

AUG 2 1952

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

1/4 SECTION CORNERS - WITNESS TREES ADDED TO.

Quarter section corner between sections 28 and 29 T.28 S; R.6 W.

As this corner is recorded in "corners renewed" this corner is shown as being N.65°W. 131 from a 28" W.Oak tree or said tree as being S.65° E. 131 and a Black Oak S.67°W. about 350 ft.


The figure 131 as given is 1.31 chains, the bearing is correct; A 48" White Oak tree was blazed and scribed 1/4 S. 28 -1581 B.T. the bearing to this tree is N.67°-30'E. and the distance is 196.0 ft. to the center of the tree measured on the ground on the slope. A 3/4 inch iron pipe is set at this corner which is 18.2 ft north of the north face of a barn and 19.0 ft. from the N.E. cor. of this barn.

July 18, 1952
Arthur Boyer
Don Smith wit.

Quarter section corner between sections 9 and 16, T. 32 S. R.1 W.

Found the original tree, a 4" fir which had not grown since being marked by surveyor, it was properly scribed, the 1/4 S. was O.K. the B.T. was very distinct but was upside down; the figure 16 was not clear: Found the original rock from this tree and piped five other rocks of the size of the corner rock around it, and marked a .24" cedar which is N.63°30'E. 21.0 ft. marked it 1/4 S.9 1581 B.T. This corner is 2657.2 ft. from the N.W. cor. of sec. 16 (the recorded dist. is given as 2654.52 ft) it is at the east side of a flat about 100 ft. W. of the beginning of a slope up toward the east, the ground at the corner is flat and slopes at about a 7° rise to the south which begins about 200' S. there are old growth trees (fir) around this corner and must have been there as big trees when the small wit. trees were marked; the tree in sec 9 was entirely gone. It was a 5" tree.

July 31, 1952
Arthur Boyer
George Hinsdale wit
Don Smith "


Arthur Boyer

CS 41/59