



AFFIDAVIT OF SURVEYOR

Survey to determine the S E. Corner of the Hiram Dixon D. L. C. No. 41 T26S, R5W, of W.M.

I began at the S. W. Corner of said D. L. C. No.41, marked by a 3/4" Iron Pipe, one B. T. standing, the other down but recognizable.

I then ran East on a random the distance given in the original Government field notes and set a temporary S E. Corner.

I then went to the N. E. Corner of Cl. 41 and found both B.T.'s standing and corner marked by an Iron Pipe.

I now ran South on the East line of said Claim No. 41, and found the distance short of falling at my temporary corner. As the original field notes showed a tie on the East boundary of said Claim No. 41, to the $\frac{1}{4}$ corner between Sections 23 and 26, I proceed to try and find said corner.

I found the corner to sections 22,23,26 and 27, T26S, R5W., of W.M., one B. T. Standing and ran East on a Random line finding the Meander Corner, on the left bank of N. Umpqua River, both B. T.'s standing. I set a 3/4" Iron Pipe at this corner.

I then ran over the river and found the Meander Corner on the right bank of said river, one B. T. standing.

I then established the true line between the corner to sections 22,23,26 and 27, T26S, R5W, of W. M. and the two Meander corners found and proceeded on to the $\frac{1}{4}$ corner between sections 23 and 26, same Township and Range, but found B. T.'s gone.

I then set temporary corner at distance shown in original Government field notes and ran an projected line to a tie with East line of D. L. C. #41.


I then figured my distance across the river from the original Government field notes to the left bank of the N. Umpqua River from my tie on the East line of Claim #41 and proceeded from said point to the S. E. Corner of said Claim #41.

I found now the new corner falls very close to the corner set when running the South line of said Claim No. 41 and proceeded to establish the S. E. Corner of said Claim No. 41 at the present fence corner.

This was done because sworn testimony puts it there and my survey which was quite extensive, showed the corner to fall very close to said present fence corner.

As the original survey was done 99 years ago and the precision then was not of the degree required today, I am convinced that the present S. E. fence corner is the one set by the original owners from the old B. T.'s now destroyed.

Signed Edwin S. Woodford
Edwin S. Woodford
Reg. Prof. Eng. #622
Roseburg, Oregon



FILED
RECEIVED

APR 9 1953

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

41/144

AFFIDAVIT

I W. L. Dixon have knowledge that the gate to the Tom Dixon ranch has been located in its present position 40 years.

W. L. Dixon

Subscribed and sworn to before me this 20, day of January 1953

[Signature]

My commission expires Dec. 7, 1955.

AFFIDAVIT

I Claude Shurt have knowledge that the gate to the Tom Dixon ranch has been located in its present position for the past about 40 years.

Claude Shurt

Subscribed and sworn to before me this 13th day of January 1953

My commission expires Dec. 7, 1955 [Signature] **NOTARY PUBLIC FOR OREGON**

AFFIDAVIT

I J. W. Short have knowledge that the gate to the Tom Dixon ranch has been located in its present position for the past 38 years.

J. W. Short

Subscribed and sworn to before me this 13th. day of Jan. 1953

[Signature]

My Commission expires Dec. 7, 1955 NOTARY PUBLIC FOR OREGON