

LESLIE C. RICHARDS
MINING ENGINEER

4203 N. E. 28TH AVENUE
PORTLAND 11, OREGON


August 10, 1953.

County Surveyor
Douglas County Court House
Roseburg, Oregon.

Dear Sir:

I am enclosing a copy of the notes on the remonumenting of corners of Mineral Survey No. 629, Oregon, for filing with your office.

Very truly yours,



Leslie C. Richards

FILED
RECEIVED

AUG 13 1953

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

41/186

REMONUMENTING CORNERS OF SURVEY NO. 629

Bohemia (unorganized) Mining District
Lane and Douglas Counties, Oregon

Sections 10-13-14-15, (suspended) Township 23 S., Range 1 E. of W.M.

JULY 20, 1953

Feet

CALIFORNIA LODE

Beginning at Cor. No. 1.

Set an iron pipe, 30 ins. long, 1 in. diam., 22 ins. in the ground, surrounded by mound of stone, with aluminum cap mkd. 1-4-629. Placed broken rock alongside mkd. 9; from which

The U. S. M. M. No. 1, established in Sur. No. 229, bears S. $84^{\circ}18'$ E., 6584.30 ft. (Record bearing and measurement)

The N. $\frac{1}{4}$ sec. cor. sec. 14 (suspended) T. 23 S., R. 1 E., of the Willamette Meridian, bears N. $40^{\circ}52' 50''$ W., 965.15 ft. (Record bearing and measurement)

A snag, 40 ins. diam., bears N. 10° E., 22.2 ft. dist.,

Thence by record bearing and measurement S. $27^{\circ}51'$ W.

595.23

Cor. No. 2.

Set an iron pipe 30 ins. long, 1 in. diam., 18 ins. in the ground, surrounded by mound of stone, with aluminum cap mkd. 2-3-5-629. Placed 4 x 4 post 4 ft. long mkd. 2-3-5-629 alongside; from which

A fir 20 ins. diam., bears S. 57° E., 30.2 ft. dist., mkd. 2-3-5-629 BT.

Thence by record bearing and measurement N. $79^{\circ}22'$ W.

1496.78

Cor. No. 3.

Set an iron pipe 30 ins. long, 1 in. diam., 22 ins. in the ground, surrounded by mound of stone, with aluminum cap mkd. 3-2-629; from which

A red fir 20 ins. diam., bears N. 85° W., 7.15 ft. dist., mkd. 3-2-629 BT.

Thence by record bearing and measurement N. $27^{\circ}51'$ E.

595.23

Cor. No. 4, identical with Cor. No. 2 Sur. No. 486 Dixie Queen lode.

Set an iron pipe 30 ins. long, 1 in. diam., 18 ins. in the ground, surrounded by mound of stone, with aluminum cap mkd. 4-1-629 and 2-486; from which

FILED

RECEIVED

AUG 12 1953

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

41/86

Feet

A red fir, 18 ins. diam., bears S. 20° W., 15.8 ft. dist.,
mkd. 4-1-629 BT.

A red fir, 10 ins. diam., bears S. 83° E., 27.5 ft. dist.,
mkd. 4-1-629 BT.

A red fir, 28 ins. diam., bears N. 45° E., 19.6 ft. dist.,
mkd. 2-486 BT.

Thence by record bearing and measurement S. 79° 22' E.

1496.78

To Cor. No. 1; the place of beginning.

WHITE GHOST LODGE

Beginning at Cor. No. 1.

Set an iron pipe, 30 ins. long, 1 in. diam., 15 ins. in the
ground, surrounded by mound of stone, with aluminum cap
mkd. 1-4-629. Placed rotten remanent of wood post alongside;
from which

The U. S. M. M. No. 1, established in Sur. No. 229, bears
N. 89° 08' 50" E., 5260.95 ft. (Record bearing and
measurement)

The E. $\frac{1}{4}$ sec. cor. of sec. 14, (suspended) T. 23 S., R.
1 E., of the Willamette Meridian, bears S. 32° 38' 30" E.,
1182.23 ft. (Record bearing and measurement)

A white fir, 20 ins. diam., bears N. 70° E., 32.0 ft. dist.,
mkd. 1-4-629 BT.

A stump 32 ins. diam., bears N. 30° E., 33.0 ft. dist.

Thence by record bearing and measurement S. 27° 51' W.

595.23

Cor. No. 2.

A rock 12 x 14 ins. 10 ins. above ground, mkd. with an X
and 2-3-629; surrounded by a mound of stone; from which

A fir, 30 ins. diam., bears S. 40° W., 23.2 ft. dist.,
mkd. 2-3-629 BT.

A fir, 36 ins. diam., bears N. 25° W., mkd. 2-3-629 BT.

Thence by record bearing and measurement N. 60° 27' W.

1484.47

Cor. No. 3, identical with Cor. No. 2 California lode of this
survey.

Thence by record bearing and measurement N. 27° 51' E.

595.23

Cor. No. 4, identical with Cor. No. 1 California lode of this
survey.

Thence by record bearing and measurement S. 60° 27' E.

1484.47

To Cor. No. 1; the place of beginning.

FILED
RECEIVED

APR 12 1953

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

4/1/86

Feet

MYSTERY LODE

Beginning at Cor. No. 1.

A stone 6 x 8 ins. 18 ins. above ground mkd. 1-629; from which

The U. S. M. M. No. 1, established in Sur. No. 229, bears N. $77^{\circ} 33'$ E., 4146.57 ft. (Record bearing and measurement).

The E. $\frac{1}{4}$ sec. cor. sec. 14 (suspended) T. 23 S. R. 1 E., of the Willamette Meridian, bears S. $72^{\circ} 35' 20''$ W., 601.21 ft. (Record bearing and measurement).

A white fir 25 ins. diam., bears N. 50° E., 14.05 ft., mkd. 1-629 BT.

A white fir 25 ins. diam., bears S. 20° W., 5.3 ft., blazed and grown over.

Thence by record bearing and measurement S. $27^{\circ} 51'$ W.

405.13

Cor. No. 2.

Set an iron pipe, 30 ins. long, 1 in. diam., 20 ins. in the ground, in original mound of rock with rotten remanent of wood post alongside with aluminum cap mkd. 2-629; from which

A fir 40 ins. diam., bears N. 50° W., 12.7 ft., blazed and grown over.

A hemlock 18 ins. diam., bears N. 85° W., 31 ft., blazed and grown over.

Thence by record bearing and measurement N. $63^{\circ} 32'$ W.

1452.33

Cor. No. 3, identical with Cor. No. 2 White Ghost lode of this survey.

Thence by record bearing and measurement N. $27^{\circ} 51'$ E.

595.23

Cor. No. 4, identical with Cor. No. 1 White Ghost lode of this survey.

Thence by record bearing and measurement S. $55^{\circ} 13'$ E.

644.07

Cor. No. 5.

Set an iron pipe 30 ins. long, 1 in. dia., 18 ins. in the ground, surrounded by mound of stone, with aluminum cap mkd. 5-3-629. Original wooden post 6 x 6 with "5" mkd. lying on ground alongside pipe driven in rotten remanent in ground; from which

A fir snag 30 ft. high bears N. 35° E., 29.9 ft. mkd. 5-3-629 BT.

A white fir 24 ins. diam., bears N. 75° W., 67.5 ft., blazed and grown over.

FILED
RECEIVED

AUG 12 1953

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

41/86

Feet
816.22 Thence by record bearing and measurement S. 56°43' E.
To Cor. No. 1; the place of beginning.

AJAX LODE

Beginning at Cor. No. 1.

Set an iron pipe, 30 ins. long, 1 in. diam., 22 ins. in the ground, surrounded by mound of stone, with aluminum cap mkd. 1-629; from which

The U. S. M. M. No. 1 established in Sur. No. 229, bears N. 84°09' E., 3907.17 ft. (Record bearing and measurement).

The E. $\frac{1}{4}$ sec. cor. of sec. 14 (suspended) T. 23 S., R. 1 E., of the Willamette Meridian, bears S. 47°47'30" W., 993.50 ft. (Record bearing and measurement).

A fir 56 ins. diam., bears N. 33° W., 24.5 ft. dist., blazed and grown over.

A fir 45 ins. diam., bears N. 28° E., 21.7 ft. dist., blazed and grown over.

Thence by record bearing and measurement S. 26°10' W.

500.23 Cor. No. 2.

A rock 6 x 10 ins. 18 ins. above the ground, surrounded by a mound of stone mkd. 2-629; from which

A fir 24 ins. diam., bears S. 60° W., 10.5 ft. dist., blazed and grown over.

A fir 32 ins. diam., bears S. 10° W., 15.0 ft., blazed and grown over.

Thence by record bearing and measurement N. 56°43' W.

746.36 Cor. No. 3, identical with Cor. No. 5 Mystery lode of this survey.

Thence by record bearing and measurement N. 26°10' E.

343.16 Cor. No. 4.

Set an iron pipe, 30 ins. long, 1 in. diam., 21 ins. in the ground, surrounded by mound of stone with aluminum cap mkd. 4-629. Pipe driven through rotten remanent of wood post. Rotten post 6 x 6 lying alongside; from which

A fir 72 ins. diam., bears N. 52° W., 28.5 ft. dist., blazed and grown over.

A cedar 36 ins. diam., bears N. 20° E., 43.6 ft. dist., mkd. 4-629 BT.

Thence by record bearing and measurement S. 68°49' E.

743.42 To Cor. No. 1; the place of beginning.

RECEIVED

AUG 12 1953

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

Feet

ALPHARETTA LODGE

Beginning at Cor. No. 1.

Set an iron pipe, 30 ins. long, 1 in. diam., 18 ins. in the ground, surrounded by a mound of stone, with aluminum cap mkd. 1-629. Rotten remanent of wooden post placed alongside; from which

The U. S. M. M. No. 1, established in survey No. 229, bears N. 72° 40' 20" E., 4349.10 ft. (Record bearing and measurement)

The E. $\frac{1}{4}$ sec. cor. of sec. 14 (suspended) T. 23 S. R., 1 E. of the Willamette Meridian, bears N. 64° 49' W., 520.43 ft. (Record bearing and measurement)

A fir, 55 ins. diam., bears N. 10° W., 8.5 ft. dist., blazed and grown over.

A fir, 48 ins. diam., bears S. 60° W., 38.5 ft. dist., blazed and grown over.

Thence by record bearing and measurement S. 10° 59' W.

592.08

Cor. No. 2.

Set an iron pipe, 30 ins. long, 1 ins. diam., 18 ins. in the ground, surrounded by a mound of stone, with brass cap mkd. 2-629. Rotten remanent of wooden post placed alongside; from which

A fir, 52 ins. diam., bears S. 50° W., 29.0 ft. dist., blazed and grown over.

A fir, 45 ins. diam., bears S. 5° W., 52.0 ft. dist., blazed and grown over.

Thence by record bearing and measurement N. 63° 32' W.

1486.51

Cor. No. 3.

Set an iron pipe, 30 ins. long, 1 in. diam., 18 ins. in the ground, surrounded by a mound of stone, with aluminum cap mkd. 3-629; from which

A fir, 21 ins. diam., bears S. 30° E., 46.7 ft. dist., mkd. 3-629 BT.

A fir, 29 ins. diam., bears N. 40° E., 401. ft. dist., mkd. 3-629 BT.

Original corner stone, 6 x 14 x 36 ins. bears N. 35° E., 10.0 ft. dist., mkd. 3-629. Stone has slid down the hill from its original location. Unable to reset stone due to weight.

Thence by record bearing and measurement N. 10° 59' E.

FILED
RECEIVED

MAY 12 1953

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

41/186

Feet

592.08

Cor. No. 4.

Set an iron pipe, 30 ins. long, 1 ins. diam., 15 ins. in the ground, surrounded by a mound of stone, with aluminum cap mkd. 4-629. Pipe driven through the rotten remanent of a stump; from which

A fir, 42 ins. diam., bears S. 80° W., 7.5 ft. dist., mkd. 4-629 BT.

Thence by record bearing and measurement S. 63° 32' E.

1486.51

To Cor. No. 1; the place of beginning.

LOS ANGELES LODGE

Beginning at Cor. No. 1, on line 2-3 White Ghost Lode of this survey.

Set an iron pipe, 30 ins. long, 1 in. diam., 20 ins. in the ground, surrounded by a mound of stone, with aluminum cap mkd. 1-629; from which

The U. S. M. M. No. 1, established in Sur. No. 229, bears N. 86° 59' E., 6051.95 ft. (Record bearing and measurement)

The N. $\frac{1}{4}$ sec. cor. of sec. 14 (suspended) T. 23 S., R. 1 E., of the Willamette Meridian, bears N. 33° 48' 30" W., 2048.40 ft. (Record bearing and measurement)

A fir, 20 ins. diam., bears N. 45° E., 40.0 ft. dist., mkd. 1-629 BT.

A downed snag, bears S. 70° E., 61.9 ft. dist., mkd. 1-629 BT.

Thence by record bearing and measurement S. 4° 51' E.

255.34

Cor. No. 2.

A stone, 9 x 16 ins. 18 ins. above ground, firmly set, surrounded by a mound of rock, mkd. LOS ANGELES 2-; from which

A downed cedar, 7 ins. diam., bears N. 25° W., mkd. 2-629 BT.

A fir, 36 ins. diam., bears N. 82° E., 80.0 ft. dist., blazed and grown over.

Thence by record bearing and measurement N. 79° 22' W.

1426.39

Cor. No. 3.

On inaccessible cliff.

Thence by record bearing and measurement N. 4° 51' W.

17.80

Witness Cor. to Cor. No. 3.

A cross (x) at corner point and W C - 3 - 629 chiseled on the face of the cliff, showing 20 x 100 x 40 ft. above the general surface; from which

- Feet A fir, 10 ins. diam., bears N. 20°W., 18.0 ft. dist., mkd.
WC - 3 - 629 BT.
- 559.37 Cor. No. 4, on line 2-3 California lode, and line 4-1 Defiance lode of this survey.
- Set an iron pipe, 30 ins. long, 1 in. diam., 18 ins. in the ground, surrounded by a mound of stone, with aluminum cap mkd. 4-629; from which
- A white fir, 28 ins. diam., bears N. 10°W., 65.2 ft., dist., mkd. 4-629 BT.
- A stump, 15 ins. diam., bears N. 40° W., 65.5 ft. dist.
- Original corner stone, 6 x 18 x 36 ins., bears N. 55°E., 11.5 ft. dist., mkd. 4-629. Stone lying on flat side, having slid down the hill from its original location. Unable to reset stone due to weight.
- Thence by record bearing and measurement S. 79°22' E.
- 652.59 Cor. No. 5, identical with Cor. No. 2, California lode, and Cor. No. 3, White Ghost lode, of this survey.
- Thence by record bearing and measurement S. 60°27' E.
- 903.78 To Cor. No. 1; the place of beginning.

BUTTE LODE

- Beginning at Cor. No. 1, identical with Cor. No. 2 Sur. No. 486, Dixie Queen lode, and with Cor. No. 4, California lode, of this survey.
- The U. S. M. M. No. 1, established in Sur. No. 229, bears S. 83°23'20" E., 8076.51 ft. (Record bearing and measurement)
- The N. $\frac{1}{4}$ sec. cor. of sec. 14 (suspended) T. 23 S. R. 1 E., of the Willamette Meridian, bears N. 61°37' E., 954.12 ft. (Record bearing and measurement)
- Thence by record bearing and measurement S. 27°51' W.
- 595.23 Cor. No. 2, identical with Cor. No. 3, California lode of this survey.
- Thence by record bearing and measurement N. 65°15' W.
- 594.27 Cor. No. 3, on line 4-1 June lode of this survey.
- Set an iron pipe, 30 ins. long, 1 in. diam., 20 ins. in the ground, surrounded by a mound of stone, with aluminum cap mkd. 3-629; from which
- A fir, 21 ins. diam., bears S. 60°E., 9.0 ft. dist., mkd. 3-629 BT.
- A fir, 26 ins. diam., bears S. 5°W., 17.8 ft. dist., mkd. 3-629 BT.
- Thence by record bearing and measurement N. 27°51' E.

Feet

Set an iron pipe, 30 ins. long, 1 in. diam., 18 ins. in the ground, surrounded by a mound of stone, with aluminum cap mkd. 4-629 and 3-486. Rotten remanent of wooden post placed alongside; from which

A fir, 36 ins. diam., bears N. 10° E., 22.9 ft. dist., mkd. 3-486 - 4-629 BT.

A fir, 26 ins. diam., bears S. 85° E., 4.8 ft. dist., mkd. 3-486 - 4-629 BT.

Thence by record bearing and measurement N. $81^{\circ}44'$ E.

734.56

To Cor. No. 1; the place of beginning.

DEFIANCE LODGE

Beginning at Cor. No. 1.

A rock 13 x 18 ins. 8 ins. above ground, mkd. on the west side 1-629. Firmly set in mound of stone; from which

The U. S. M. M. No. 1 established in Sur. No. 229, bears N. $88^{\circ}52'30''$ E., 6954.41 ft. (Record bearing and measurement)

The N. $\frac{1}{4}$ sec. cor. of sec. 14 (suspended) T. 23 S., R. 1 E. of the Willamette Meridian, bears N. $8^{\circ}37'$ W., 1537.02 ft. (Record bearing and measurement)

A red fir, 21 ins. diam., bears S. 82° E., 31.0 ft. Blazed and grown over.

Thence by record bearing and measurement S. $34^{\circ}06'$ W.

591.44

Cor. No. 2.

A large boulder 30 x 48 ins. 12 ins. above ground, mkd. 2-629; from which

A fir tree, 14 ins. diam., bears N. 45° E. Blazed and grown over.

Thence by record bearing and measurement N. $53^{\circ}27'$ W.

1490.06

Cor. No. 3.

A rock, 8 x 10 ins. 12 ins. above ground, firmly set, surrounded by a mound of stone, mkd. 3-629; from which

A cedar, 26 ins. diam., bears N. 60° E., 11 ft. dist., mkd. 3-629 BT.

A dead snag, 7 ins. diam., bears S. 55° E., 21.9 ft. dist., mkd. 3-629 BT.

Thence by record bearing and measurement N. $34^{\circ}06'$ E.

591.44

Cor. No. 4.

Set an iron pipe, 30 ins. long, 1 in. diam., 16 ins. in the ground, surrounded by mound of stone, with aluminum cap mkd. 4-629; from which

Feet

A red fir, 21 ins. diam., bears N. 50° E., 38.2 ft., dist., mkd. 4-629 BT. - Instead of N. 15° E., 36.55 ft., as by official record.

A red fir, 21 ins. diam., bears N. 80° W., 24.8 ft. dist., mkd. 4-629 BT. - Instead of S. 50° W., 36.55 ft., as according to official record.

Cor, monument with pile of rock and down 4 x 4 posts. No scribing visible. Blazed face corner.

Thence by record bearing and measurement S. $53^{\circ}27'$ E.

1490.06 To Cor. No. 1; the place of beginning.

IDAHO LODE

Beginning at Cor. No. 1.

Set an iron pipe, 30 ins. long, 1 in. diam., 18 ins. in the ground, surrounded by mound of stone, with aluminum cap mkd. 1-629. Rotten remanent of wooden post placed alongside; from which

The U. S. M. M. No. 1, established in Sur. No. 229, bears S. $85^{\circ}27'$ E., 8449.32 ft. (Record bearing and measurement)

The N. $\frac{1}{4}$ sec. cor. of sec. 14 (suspended) T. 23 S., R. 1 E., of the Willamette Meridian, bears N. $60^{\circ}04'14''$ E., 1430 ft. (Record bearing and measurement)

A fir, 33 ins. diam., bears S. 30° W., 19.4 ft. dist., blazed and grown over.

A fir, 37 ins. diam., bears N. 70° W., 28.4 ft. dist., blazed and grown over.

Thence by record bearing and measurement S. $24^{\circ}18'$ W.

600.00 Cor. No. 2.

Set an iron pipe, 30 ins. long, 1 in. diam., 15 ins. in the ground, and surrounded by mound of stone, with aluminum cap mkd. 2-629. Rotten remanent of wooden post placed alongside; from which

A fir, 36 ins. diam., bears N. 40° E., 29.0 ft. dist., blazed and grown over.

A cedar, 13 ins. diam., bears S. 10° W., 27.0 ft. dist., mkd. 2-629 BT.

Thence by record bearing and measurement N. $64^{\circ}51'$ W.

1466.55 Cor. No. 3, identical with Cor. No. 2 Hazel lode of this survey

Set an iron pipe, 30 ins. long, 1 in. diam., 20 ins. in the ground, surrounded by a mound of stone, with brass cap mkd. 3-2-629. A downed wood post mkd. 3-2-629 placed alongside; from which

A snag, 20 ins. diam., bears S. 40° W., 4.6 ft. dist., mkd. 3-2-629 BT.

Feet
 600.00 Thence by record bearing and measurement N. $24^{\circ}18'$ E.
 Cor. No. 4, identical with Cor. No. 1 Hazel lode of this survey.
 Set an iron pipe, 30 ins. long, 1 in. diam., 24 ins. in the
 ground, surrounded by a mound of stone, with aluminum cap
 mkd. 1-4-629; from which
 A fir, 55 ins. diam., bears S. $5^{\circ}E.$, 30.2 ft. dist.,
 blazed and grown over.
 Thence by record bearing and measurement S. $64^{\circ}51'$ E.
 1466.55 To Cor. No. 1; the place of beginning.

JUNE LODGE

Beginning at Cor. No. 1, on lines 2-3 and 3-4 Butte and
 Defiance lodes of this survey.

Set an iron pipe, 30 ins. long, 1 in. diam., 18 ins. in the
 ground, surrounded by a mound of stone, with aluminum cap
 mkd. 1-629; from which

The U. S. M. M. No. 1, established in Sur. No. 229, bears
 S. $87^{\circ}02'10''$ E., 8376.50 ft. (Record bearing and
 measurement)

The N. $\frac{1}{4}$ sec. cor. of sec. 14, (suspended) T. 23 S., R.
 1 E., of the Willamette Meridian, bears N. $51^{\circ}13'19''$ E.,
 1516.08 ft. (Record bearing and measurement)

A red fir, 26 ins. diam., bears S. $30^{\circ}E.$, 31.0 ft. dist.,
 mkd. 1-629 BT.

Thence by record bearing and measurement S. $34^{\circ}06'$ W.

596.14 Cor. No. 2.

Set an iron pipe, 30 ins. long, 1 in. diam., 18 ins. in the
 ground, surrounded by a mound of stone, with aluminum cap
 mkd. 2-629. Rotten remanent of wood post placed alongside;
 from which

A fir, 32 ins. diam., bears N. $10^{\circ}E.$, 54.6 ft. dist.,
 blazed and grown over.

A fir, 26 ins. diam., bears N. $50^{\circ}W.$, 38.0 ft. dist.,
 blazed and grown over.

Thence by record bearing and measurement N. $65^{\circ}15'$ W.

1484.47 Cor. No. 3.

Set an iron pipe, 30 ins. long, 1 in. diam., 20 ins. in the
 ground, surrounded by a mound of stone, with brass cap mkd.
 3-629. Wood post mkd. 3-629 placed alongside; from which

A snag, 29 ins. diam., bears S. $35^{\circ}E.$, 23.0 ft. dist.,
 mkd. 3-629 BT.

A snag, 30 ins. diam., bears S. $60^{\circ}W.$, 34.0 ft. dist.,
 mkd. 3-629 BT.

Feet

Thence by record bearing and measurement N. $34^{\circ}06'$ E.

596.14

Cor. No. 4.

Set an iron pipe, 30 ins. long, 1 in. diam., 22 ins. in the ground, surrounded by a mound of stone, with aluminum cap mkd. 4-629. A wooden post mkd. 4-629 placed alongside; from which

A fir, 42 ins. diam., bears N. 5° E., 31.0 ft. dist., blazed and grown over.

A fir, 40 ins. diam., bears S. 60° E., 6.75 ft. dist., blazed and grown over.

Thence by record bearing and measurement S. $65^{\circ}15'$ E.

1484.47

To Cor. No. 1; the place of beginning.

 HAZEL LODGE

Beginning at Cor. No. 1, identical with Cor. No. 4 Idaho lode of this survey; from which

The U. S. M. M. No. 1, established in Sur. No. 229, bears S. $82^{\circ}26'30''$ E., 9835.61 ft. (Record bearing and measurement)

The N. W. cor. of sec. 14, (suspended) T. 23 S., R. 1 E., of the Willamette Meridian, bears N. $28^{\circ}09'$ W., 119.62 ft. (Record bearing and measurement)

Thence by record bearing and measurement S. $24^{\circ}18'$ W.

600.00

Cor. No. 2, identical with Cor. No. 3 Idaho lode of this survey.

Thence by record bearing and measurement N. $75^{\circ}12'02''$ W.

939.13

Cor. No. 3, identical with Cor. No. 2 Halifax lode of this survey.

Set an iron pipe, 30 ins. long, 1 in. diam., 22 ins. in the ground, surrounded by a mound of stone, with brass cap mkd. 3-2-629; from which

A snag, 36 ins. diam., bears S. 5° W., 17.0 ft. dist.,

A stump, 32 ins. diam., bears S. 70° W., 34.3 ft. dist.,

Thence by record bearing and measurement N. $24^{\circ}18'$ E.

597.24

Cor. No. 4, identical with Cor. No. 1, Halifax lode of this survey.

Set an iron pipe, 30 ins. long, 1 in. diam., 22 ins. in the ground, surrounded by a mound of stone, with brass cap mkd. 4-1-629. Rotten remanent of wood post placed alongside; from which

A fir snag, 30 ins. diam., bears N. 30° W., 12.1 ft. dist., mkd. 1-4-629 BT.

FILED

RECEIVED

AUG 12 1953

COUNTY SURVEYOR

DOUGLAS COUNTY, ORE.

4/1/86

Feet

Thence by record bearing and measurement S. 75° 22' E.

939.60

To Cor. No. 1; the place of beginning.

Louis C. Becklund

FILED
RECEIVED

AUG 12 1953

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.