

Replacement of Northwest corner of Section 34,
Township 23 South, Range 3 West, W.M.

At a point North $0^{\circ} 36'$ East 2596.2 feet from the $1/4$ corner between Sections 33 and 34, Township 23 South, Range 3 West, W.M., and being also South $89^{\circ} 25'$ West 2650.9 feet from the $1/4$ corner between Sections 27 and 34, said Township and Range, placed a 2" iron pipe 48" long set 2" above ground, marked new bearing trees as follows:

- 6" Douglas Fir N $43\frac{1}{2}^{\circ}$ E 31.0 feet, marked S 27 R S BT
- 6" Hemlock bears N 48° W 8.0 feet, marked S 28 R S BT
- 46" Douglas Fir which has old markings "BT", bears S 39° E 16.0 feet, remarked S 34 R S BT
- 6" Douglas Fir bears S $45\frac{1}{2}^{\circ}$ W 27.5 feet, marked S 33 R S BT

This location has been used as a Northwest corner of Section 34 for a number of years and shows surveyor and cruiser marks, and although the BT marked in the 46" Douglas Fir does not face the right direction, the distances and bearings to this location are approximately the same as those given in the original field notes. No evidence of other bearing trees was found, and it is believed that this is the best location possible with available evidence for this corner.


Dec 28, 1953

Present: Robert Barta

FILED
RECEIVED

DEC 29 1953

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.



Gilbert A. Gardner
GILBERT A. GARDNER
NOV. 9, 1951
276

File 41/239