

RICHARD L. TEMPLIN, JR.  
REGISTERED LOGGING ENGINEER

October 28, 1954

County Surveyors  
Josephine County  
Douglas County  
Grants Pass and Roseburg  
Oregon

Gentlemen:

While cruising county timberland in Josephine County, I rehabilitated the following section corner:

The corner common to sections 3, 4, 9, and 10, T.33 S., R. 6 W. WM

Found an old pitch fence corner post common to the intersection of four fences.

Found rotted stump of original 12" Fir B.T. with chooped face and trace of scribing under five inches of rotted wood said stump bearing S 52\* W , 46 links distant.

Other B.T. s completely gone. ( Lake and Hyde 1855 )

Set 1½" Iron Pipe with galvanized cap and Alum. Tag. mkd. "RE3024" on the north side of pitch corner post.

Scribed the following new bearing trees:


14" Fir bears S 55\* W 35.00 feet distant mkd. T33SR6W S9BT

14" Madrone bears N 82\* W 46.3 feet distant mkd T33SR6W S4BT

10" Yellow Pine bears S 17\* W 44.2 feet distant mkd T33SR6W S9BT.

Set BLM Bearing Tree tags on madrone and Yellow Pine BT's.

Respectfully,



R.L. Templin, Jr.

RE 3024

RECEIVED

NOV 4 1954

COUNTY SURVEYOR  
DOUGLAS COUNTY, ORE.