

Township 28 South Range 6 West; WM

$\frac{1}{4}$  Section Corner common to Sections 24 & 25

No mark found at this corner. Original bearing trees were destroyed in clearing the highway right-of-way.

After grading work on the highway was completed the corner was set from ties to the old bearing trees and coordinates from the highway centerline.

A  $\frac{3}{4}$  inch round iron pin set in concrete marks the corner.

A painted white 4" x 4" wood posts set by the corner as a finder.

Bearing trees marked;

A 10 inch Madrone (Mt'n Laurel) N 82°37'E-68.7 ft.

A 10 inch B. oak N 22°03'W - 81.2 ft.

The corner is on the easterly side of the highway at the bottom of an approx. 55 ft. high fill. It is inside the highway right-of-way and approx. 20 ft. from the fence.


REPORTED THAT  
SLIDE HAS  
TAKEN OUT  
CORNER AND  
N.E. WITNESS  
TREE.

FILED  
RECEIVED

MAR 15 1955

COUNTY SURVEYOR  
DOUGLAS COUNTY, ORE.

March 11, 1955



Resident Engineer  
State Highway Department  
Myrtle Creek, Ore.