

North $\frac{1}{4}$ corner section 19, T.32 S., R.5 W.W.M.

Wolf Creek, Oregon.

December 23, 1955.

County Surveyor,
Douglas County,
Roseburg, Oregon.

Dear Sir;-


Between the dates of June 1st and 11th 1955, I ran the north section line of 19, T.32 S., R.5 W.W.M. and found the distance to be 5488.1 feet. On October 6, 1955 I drove a $1\frac{1}{2}$ " pipe at 2633.5 feet ^{from} the east end for the $\frac{1}{4}$ corner, from which;- A fir 8" in dia. bears N.34° W., 2.3' dist. scribed $\frac{1}{4}$ S 18 BT 1543

A madrone 10" in dia. bears S.23° E., 5.4' dist. scribed $\frac{1}{4}$ S 19 BT 1543

Note; My total distance of 5488.1 feet or 83.15 chains is fairly close to the field notes of 1855 survey of 83 chains but no where near the 85 chains of the year 1900 survey. Even so I am closer to the ravine and branch mentioned by 13 feet than given in the field notes. All three $\frac{1}{4}$ corner placements are in the same ravine, there being no other ravine within several hundred

Yours truly,

P.O.Box 105



FILED
RECEIVED

JAN 10 1956

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

Handwritten signature

C.S. File No. 72/78