

CORNER RENEWAL

T 24S, R 7W, W.M.

1/4 CORNER SECTIONS 10/11:

FOUND:

NO EVIDENCE OF CORNER POST
14" YEW-N 90°E-91 LKS.-BADLY ROTTED
36" CEDAR-N 64°W-102 LKS.-DOWN


SET:

12" X 12" X 14" STONE WITH A "+"
ON TOP FOR THE CORNER
FROM WHICH R:

12" CEDAR BEARS N 65°W - 6.4 FT
MKD. 1/4 S 10, B.T.

14" HEMLOCK BEARS S 57°30'E - 30.5 FT.
MKD. 1/4 S 11, B.T. (THIS
TREE FORKS AT ABOUT 30 FT.)

NOTE: ALL FACES WERE PAINTED
WITH ORANGE PAINT.



WITNESS:
A. R. TUCKEY
CARL BROWNSON

FEB. 28, 1957

C.S. File No.

42/232-1

FOR