

T. 24S., R. 2W.

Renewal of $\frac{1}{4}$ S 22 & 27

Before logging I found the marked corner stone and both original bearing trees standing. The B. T. for section 27 was dead.

After logging in both sections, the stone corner is gone, the B. T. for section 27 is broken off near the ground, the B. T. for section 22 is a burned hollow stump showing old scars, and on the inside, the raised overlay of scribe marks. From this stump I determined the position of the corner and drove a $1\frac{1}{2}$ " iron pipe 36" long 24" in the ground, from which;

A hemlock 11" in diam. bears N. 78°E. 92.8 ft.

marked $\frac{1}{4}$ S 22 253 B. T.

A cedar 36" in diam. bears S. 19°E. 53.0 ft.

marked $\frac{1}{4}$ S 27 253 B. T.

This corner is on a steep hillside sloping north, and 20 ft. west of a small stream flowing N. W., which is not shown in the original notes.

Sept. 26, 1957



FILED
RECEIVED

OCT 8 1957

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

C. S. File No. 42/306