

T. 24S., R. 2W.

Renewal of  $\frac{1}{4}$  section corner 14, & 15

Before logging both original bearing trees were in good condition. After logging the B. T. for section 14 is a stump and the B. T. for section 15 is dead and down.

At the true point of the corner I drove a  $1\frac{1}{2}$ " iron pipe 30" long, 18" in the ground, from which;

A hemlock 11" in diam. bears N.  $86^{\circ}$ E. 53.4 ft.

marked  $\frac{1}{4}$ S 14 253 B. T.

A hemlock 36" in diam. bears S.  $62^{\circ}$ W. 58.1 ft.

marked  $\frac{1}{4}$ S 15 253 B. T.

Sept. 13, 1957



FILED  
RECEIVED

OCT 8 1957

COUNTY SURVEYOR  
DOUGLAS COUNTY, ORE.

C. S. File No. 42/306-5