

T. 25S., R. 2W.

Renewal of section corner 20, 21, 28, & 29

After logging in sections 21 & 29 I was unable to find the original marked stone corner. The N. E. B. T. is living. This tree is a white fir, now 18" in diam. The S. E. B. T. is living, now 24" in diam. The S. W. B. T. is a stump with scribing visible. The N. W. B. T. is dead and shows an overgrown scar.

At the true point of the corner I drove a 1½" iron pipe 36" long 24" in the ground, from which;


A hemlock 5" in diam. bears S. 14°W. 60.4 ft.

marked S 29 253 B. T.

A cedar 20" in diam. bears N. 89°W. 33.2 ft.

marked S 20 253 B. T.

Sept. 24, 1957



FILED
RECEIVED



OCT 15 1957

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

300300

W.C. S. File No. 42/308-3