

T. 25S., R. 2W., W.M.

Renewal of $\frac{1}{4}$ section corner 21 & 22

At this corner I found the original bearing tree for section 21 in good condition (now 60" in diam.), the bearing mark was rotted and only dim traces of scribing visible. The original B. T. for section 22 is a badly rotted stub.

At the point of the corner I drove a $1\frac{1}{2}$ " iron pipe 36" long, 24" in the ground, from which;

A fir 16" in diam. bears East 4.6 ft.

marked $\frac{1}{4}$ S 22 253 B. T.

A fir 13" in diam. bears N. $22\frac{1}{2}$ °W. 19.7 ft.

marked $\frac{1}{4}$ S 21 253 B. T.

Oct. 18, 1957



FILED
RECEIVED

OCT 22 1957

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

400340

C. S. File No. 42/308-5