

T. 25S., R. 2W.

Renewal of section corner 15, 16, 21 & 22

After logging in all four sections I was unable to find the original marked stone corner. The bearing tree for section 15 is dead and down with scribing visible. The B. T. for section 22 is living, now 20" diam. The B. T.'s for sections 21 & 16 are gone.

At the true point of the corner I drove a $1\frac{1}{2}$ " iron pipe 36" long 20" in the ground, from which;

A hemlock 8" in diam. bears N. $28\frac{1}{2}^{\circ}$ E. 25.2 ft.

marked S 15 253 B. T.

A hemlock 20" in diam. bears S. 45° E. 26 links

(original B. T. not re-marked)

A hemlock 12" in diam. bears S. 21° W. 87.4 ft.

marked S 21 253 B. T.

A cedar 10" in diam. bears N. 43° W. 14.2 ft.

marked S 16 253 B. T.

Sept. 23, 1957



FILED
RECEIVED

OCT 10 1957

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.