

T. 25S., R. 2W., W.M.

Renewal of $\frac{1}{4}$ section corner 15 & 22

At this corner I found a stone answering the description of the original corner stone. However I could find no markings on it, probably due to erosion.

The original bearing tree for section 15 is in good condition, for section 22 a dead snag. I drove a $1\frac{1}{2}$ " iron pipe 36" long, 24" in the ground at the south edge of the corner stone and marked a new bearing tree for section 22. From the point of the corner,

A hemlock 30" in diam. bears S. 55°W. 21.7 ft.

marked $\frac{1}{4}$ S 22 253 B. T.

Oct. 18, 1957



FILED
RECEIVED

OCT 22 1957

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

440400

C. S. File No. 42/308¹