

T. 25S., R. 2W.

Renewal of $\frac{1}{4}$ S 23 & 24

Before logging I found the marked stone corner and the bearing tree for section 24 in good condition. The B. T. for section 23 was a dead snag with scribing visible.

After logging in the S. E. $\frac{1}{4}$ of section 23 and the N. W. $\frac{1}{4}$ of section 24, the B. T. for section 23 has been destroyed.

I drove a $1\frac{1}{2}$ " iron pipe 36" long 18" in the ground at the west edge of the corner stone, from which;

A hemlock 7" in diam. bears N. 78°W. 66.0 ft.

marked $\frac{1}{4}$ S 23 253 B. T.

Sept. 18, 1957



FILED
RECEIVED

OCT 10 1957

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

600340

C. S. File No. 42/308-2