

T. 25S., R. 2W., W.M.

Re-establishment of $\frac{1}{4}$ section corner 11 & 12.

Before logging I found the original marked stone corner in place, and the arbutus bearing tree for section 11 in good condition. The maple bearing tree for section 12 was gone.

After logging in section 11 and the N. $\frac{1}{2}$ of section 12 I was not able to find the corner stone. The arbutus bearing tree has been broken down and badly burned and its original position lost.

I found old transit hubs on my random E. & W. center line of section 12, which I had established in 1949. The terminus of this survey line was the $\frac{1}{4}$ corner 11 & 12. From station 53 \neq 39.1 I re-produced this line S. $89^{\circ}02'$ W. 145.6 ft.; thence, N. $12^{\circ}39'$ E. 15.1 ft. to the point of the original corner, where I drove a $1\frac{1}{2}$ " iron pipe 36" long 24" in the ground, from which;

A fir 40" in diam. bears S. $64\frac{1}{2}^{\circ}$ E. 23.7 ft.

marked $\frac{1}{4}$ S 12 253 B.T.

An incense cedar 18" in diam. bears S. $71\frac{1}{2}^{\circ}$ W. 81.1 ft.

marked $\frac{1}{4}$ S 11 253 B. T.

Oct. 16, 1957



FILED
RECEIVED

OCT 22 1957

COUNTY SURVEYOR
COUNTY OF DOUGLAS, ORE.
DOUGLAS COUNTY, ORE.

600 540

C. S. File No. 42/308-11