

**THE ROBERT DOLLAR CO.**

COW CREEK DIVISION  
GLENDALE, OREGON

TELETYPE GLENDALE 85

TELEPHONE 521

February 12, 1958

Douglas County Surveyor  
Court House Building  
Roseburg, Oregon

Dear Sir:

The northwest corner of Section 36, Township 31 South, Range 9 West, was found in poor condition and new witness trees were scribed.

The original bearing trees were, a 12" Fir, N 23 W, 20 links, an 8" Maple, N 80 E, 26 links, an 8" Fir, S 55 W, 54 links and a 10" Fir S 30 E, 11 links. Only rotten stubs were left of the three original Fir bearing trees, but scribing was still visible. The Maple bearing tree had disappeared but a clump of sucker maples was growing in the spot of the call.

This evidence of the original corner was seen by Lorne Swearingen, company engineer, Wallace Owen, assistant engineer and Robert Harris, instrument man.

New bearing trees were scribed as follows: For Section 25, a 30" Fir, N 72 3/4° E 44.9 feet was scribed S 25 T 31 S R 9 W LS424 BT; for Section 36, a 30" Fir S 70°E, 66.8 feet was scribed S 36, T 31 S, R9W LS424 BT; for Section 35, a 40" Fir S 14 1/2° W, 45.2 feet was scribed S 35, T 31 S, R9W, LS424 BT; for Section 26, a 6" Fir N 42° W 14.8 feet, was scribed S 26 T 31 S R 9 W LS 424 BT. Magnetic declination used was 19° 30' East for the corner a 3" x 3" x 4' Maple post was set and a 1/2" iron rod was driven.


Sincerely,

*Wallace D Owen*

Wallace D. Owen



*Wallace D Owen*



WITNESS:

*Lorne Van Swearingen*

*Robert A. Harris*