

REESTABLISHED CORNER FOR OREGON STATE BOARD OF FORESTRY

One Quarter corner common to Sections 3 and 10, T. 22S,  
R. 11W, W.M., Douglas County, Oregon

ORIGINAL (No evidence of original corner found)

REESTABLISHED

Var.  $20\frac{1}{2}^{\circ}$ E

Set  $1\frac{1}{2}$ " x 36" galvanized iron pipe with 3" bronze cap marked "OREGON STATE  
BOARD OF FORESTRY 1/4 S3 S10 1958 RS 359," 33 inches in ground, in mound  
of stone, and from which a:

24" Fir bears S52W 144.9 ft.; scribed 1/4 S10 BT.


21" Maple (clump) bears S41 $\frac{1}{2}$ W 101.0 ft.; scribed RS 359.

Set 4x4x48" white painted Cedar post 1.5' NW of pipe.

Oregon State Board of Forestry metal location poster on 25" Fir stump S66W  
68.5'.

Dated January 27, 1958.

Reestablished by Elbert Driver under my direction.  
Elbert Driver, Transitman



Present and witnessed by Derald Timmons  
Ron Witham

FILED  
RECEIVED

FEB 24 1958

COUNTY SURVEYOR  
DOUGLAS COUNTY, ORE.