

RESTORED CORNER FOR OREGON STATE FORESTRY DEPARTMENT

One Quarter corner common to Sections 19 and 30,  
T22S, R11W, W.M., Douglas County, Oregon.

ORIGINAL

Post (found rotten remains) from which a:

12" Chittum bears S12W 27 lks.; now uprooted 14" log, with 6" Chittum  
growing from same log 10 ft. from butt.

6" Vine maple bears N72W 85 lks.; 12" vine maple clump in place.  
Creek bears East 195 lks.; now in place.

Top of ridge bears West 230 lks.; now in place.

Original Line blaze approximately 4 chains West.

RESTORED

Set 1½" x 36" galvanized iron pipe with 3" bronze cap marked "OREGON STATE  
BOARD OF FORESTRY 1/4 S19 S30 1961 RS359", 33 inches in ground, and from  
which a:


34" Cedar bears N78W 75.5 ft.; scribed 1/4 S19 BT RS359.

48" Cedar bears S58W 71.4 ft.; scribed 1/4 S30 BT.

Oregon State Forestry Department metal location poster on 6" Chittum, S8W, 6.0 ft.  
Set 4" x 4" x 72" white painted Cedar post 1 ft. SE of pipe.

Dated August 18, 1961

Restored by



Present and witnessed by D. Steenson  
E. Poitras

FILED  
RECEIVED

SEP 15 1961

COUNTY SURVEYOR  
DOUGLAS COUNTY, ORE.

✓+ ✓ 42/403 -20