

CORRECTION REPORT

RESTORED CORNER FOR OREGON STATE BOARD OF FORESTRY

One Quarter corner for Section 14, T23S, R10W, (West side)  
W.M., Douglas County, Oregon.

ORIGINAL

Post (now missing) from which a:

- 8" Fir bears S5E 84 lks.; now missing.
- 8" Fir bears S2W 109 lks.; now missing.

RETRACEMENT by Levi C. Walker, June, 1905

Post (now missing) from which a:

- 12" Fir bears S77E 23 lks.; now 31", face exposed by unknown party, face rotted, original axe work visible.
- 10" Fir bears N80W 44 lks.; now 27" x 6" stub, face exposed by unknown party, original axe work visible on small portion of face on down log, most of face destroyed when tree blew down.
- Summit of divide, South 37 lks.; now in place.

RESTORED



Set 1½" x 36" galvanized iron pipe with 3" bronze cap marked "OREGON STATE BOARD OF FORESTRY 1/4 SL4 1959 RS359", 33 inches in ground, in mound of stone, and from which a:

- 30" Fir bears S60E 36.9 ft.; scribed 1/4 SL4 BT RS359.
- 20" Fir bears N57½E 50.1 ft.; scribed 1/4 S BT.

Oregon State Board of Forestry metal location poster on 16" Fir S88W 40.2 ft.  
Set 4 x 4 x 72" white painted Cedar post 1.5 ft. NW of pipe.

Dated January 15, 1959

Restored by George C. Shore, Jr. under my direction.  
George Shore, Transitman



Present and witnessed by Dennis Bagger  
John Hollingsworth  
Philip Lewellyn  
J.R. Mahoney

✓✓