



THE ROBERT DOLLAR CO.

FOREST PRODUCTS DIVISION

AREA CODE 503 TELETYPE 830-0460
TELEPHONES
OFFICE 832-5050 SALES 832-5820
GLENDALE, OREGON

HEAD OFFICE
311 CALIFORNIA STREET
SAN FRANCISCO

November 18, 1965

County Surveyor
Douglas County Courthouse
Roseburg, Oregon

Dear Sir:

The South quarter corner of Section 34, T31S, R9W W.M. was re-established by L. V. Swearinger (RE 4186) November 16, 1963. Of the two bearing trees established, the 12" Incense Cedar N15°E. 92.2' is in good condition; the 8" Fir S32½°E. 24.9' was destroyed in a clear cut logging operation. *Rem # 9*

I referenced a 10" Fir S17½°W. 88.0', scribed ½ S. RE 3642 BT. Although this tree is again in Section 3, T32S, R9W W.M., I felt it best suited the purpose.

A staff compass (declination 20°E) and chain were used for referencing. This work was witnessed by T. H. Mehl the third.

Very truly yours,

THE ROBERT DOLLAR CO.

Milner L. Larson
Milner L. Larson
Registered Engineer #3642

FILED
RECEIVED ○

NOV 19 1965

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

See ATTACHED SHEET

C. S. File No. 51/680 ^a



THE ROBERT DOLLAR CO.

LUMBER PRODUCTION DIVISION

TELETYPE 39 • TELEPHONE VERNON 2-5810

GLENDALE, OREGON

November 16, 1960

SAN FRANCISCO 4
HEAD OFFICE
311 CALIFORNIA STREET
NEW YORK 4, NEW YORK
1 BROADWAY
WASHINGTON 6, D. C.
716 TRANSPORTATION BUILDING

Douglas County Surveyor
County Court House
Roseburg, Oregon

Gentlemen:

The South Quarter Corner of Section 34, T31S, R9W, W.M. was destroyed during logging operations. Of the two original bearing trees, the 14" Fir N 27° W 15.2' is a stump with original scribing visible, the 12" Fir N 57° E 17.8' is a windfall deteriorated so badly that all evidence of scribing is gone.

I marked the corner with a 7/8" x 30" Hexdrill Steel, driven 20" in the ground from which I referenced a 12" Incense Cedar N 15° E 92.2' scribed S 34, 1/4 S 4186 B.T. Since all of Section 34 has been logged and the remaining trees are either too small or I felt they were not wind firm, I marked a 8" Fir S 32 1/2° E 24.9' scribed S 34, 1/4 S 4186 B.T. The 8" Fir is in Section 3 T 32S, R9W, W.M. and the 1/4 Corner is Not Common to this Section, but I felt that this tree would best perpetuate the corner as it should be wind firm and not cut when Section 3 is logged.

Bearing trees were referenced with a compass and chain declination 19 1/2° E, witnessed by Milner Larson.

Very truly yours,

THE ROBERT DOLLAR CO.

Lorne Swearingen

Lorne Swearingen

Registered Engineer #4186

FILED
RECEIVED

NOV 23 1960 LS:mt

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

C. S. File No. 51/68-10