

RESTORED CORNER FOR NATIONAL PLYWOOD, INC.

The section corner common to Sections 21, 22, 27 & 28, Township 30 South, Range 2 West, W. M., Douglas County, Oregon.

ORIGINAL

We found the stone established in the 1908 Retracement Survey, marked with 2 notches on the W edge and 3 notches on the E edge, 14 x 8 x 5 inches, 9 $\frac{1}{2}$ inches in the ground, and from which a:

Ponderosa pine, now blown down but with scribes visible, 12" diameter, bears N71 $\frac{1}{2}$ ^oE, 79 links distant.

Ponderosa pine root collar and chunk with scribes visible bears S46 $\frac{1}{2}$ ^oE, 25 links distant.

Ponderosa pine root collar and chunk with scribes visible bears S51^oW, 25 links distant.

Oak, 16 inches diameter, with faces visible, bears N44 $\frac{1}{2}$ ^oW, 20 links distant.

RESTORED

Left the original stone in place and from which a:


Douglas fir, 16" diameter, bears N70 $\frac{1}{2}$ ^oE, 46.9 feet, newly scribed "T30S R2W S27 BT".

Douglas fir, 8" diameter, Bears S64^oE, 20.3 feet, newly scribed "T30S R2W S27 BT".

Douglas fir, 22" diameter, bears S55^oW, 34.3 feet, newly scribed "T30S R2W S28 BT".



Bruce A. Shaner



Date: August 5, 1960
Declination of 20^oE

Present & witnessed by:

James B. Griffin
James B. Griffin

FILED
RECEIVED

AUG 23 1960

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

C. S. File No. 51/105-2