

# Shaner's Engineering & Surveying

ROAD ENGINEERING & LAND SURVEYING  
1717 S. W. McLain  
ROSEBURG, OREGON 97470

December 21, 1964

## LEGAL CORNER RESTORED FOR U.S. FOREST SERVICE

The Section Corner common to Sections 5, 4, 8, 9 of T26S, RLW, W.M., Douglas County, Oregon, found original Douglas Fir corner tree, now a 30" diameter, with old faces on all sides, from which tree a:

14" D. Fir, original bearing tree with scribes visible, bears N31°E, 7.3 feet.

Small D. Fir stump, probable original bearing tree, bears S63°E, 6.6 feet.

All other original bearing trees now missing.

30" D. Fir, I scribed "T26S, RLW, S9, BT", bears S71°E, 31.0 feet.

6" D. Fir, I scribed "T26S, RLW, S8, BT", bears S52°W, 29.6 feet.

26" D. Fir, I scribed "T26S, RLW, S5, BT", bears N62°W, 61.0 feet. *D#6*

## LEGAL CORNER FOUND FOR U.S. FOREST SERVICE


The Closing Corner common to Sections 3 & 4, T26S, RLW, W.M., Douglas County, Oregon, found original Douglas Fir corner tree, now a 18" diameter, with scribes visible, from which tree a:

32" D. Fir, original bearing tree with old face, bears S25°E, 29.0 feet.  
(Original record distance was 23.8 feet.)

30" D. Fir, original bearing tree with old face, bears *S71°W, 11.9 feet. 2 ✓*  
~~S71°W, 11.9 feet.~~



*B. Shaner*



FILED Copies to Douglas County Surveyor & U.S. Forest Service, Glide, Oregon.

RECEIVED

DEC 23 1964

COUNTY SURVEYOR  
DOUGLAS COUNTY, ORE.