

REWITNESSED CORNER FOR STATE OF OREGON--DEPARTMENT OF FORESTRY

Closing corner for Sections 22 and 23, South end, Township 22 South, Range 10 West, W. M., Douglas County, Oregon.

ORIGINAL

Stone 20" x 16" x 12" (found, 4 notches on N, 2 notches on E and CC on NE faces) from which a:

36" Maple bears N32W 72 lks.; now rotted uproot, sprouts growing out of trunk.

12" Maple bears N54E 107 lks.; remains of rotted stump alongside of five foot diameter clump, original tree lost downstream.

4" Vine Maple bears S15W 22 lks.; missing, sprouts in area.

Trail bears North 50 lks.; in place.

Mill Creek bears North 1.50 chains; in place.

Mill Creek bears East 4.30 chains; in place

Beginning of ascent bears West 70 lks.; in place.

RESTORED

Set 4" x 4" x 72" white painted Cedar post 2.0 feet South of corner stone in mound of rock, and from which a:

36" Hemlock bears N20 $\frac{1}{2}$ W 61.9 ft.; scribed T22S R10W CC S22 BT RS 359.

9' x 8' x 4' high boulder bears N80W 25.7 ft.; scribed XBO


24" Maple bears N73 $\frac{1}{2}$ E 51.9 ft.; scribed T22S R10W S23 CC BT by Allen G. Terry April 1956.

Oregon State Forestry Department metal location poster on 30" Cedar S32W 64.5 ft.

Dated March 30, 1966

Rewitnessed by

Present and witnessed by G. Shore
C. Renicher
R. Fox
R. Hardman



FILED
RECEIVED

APR 28 1966

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

April 29, 1966

Mr. Arnold G. Gibson
Area Engineer
State of Oregon
Dept. of Forestry
P. O. Box 2289
Salem, Oregon 97310

Dear Mr. Gibson:

In regard to your recent correspondence, April 27, 1966, and particularly the closing corner for Sections 22 and 23, south end, T. 22 S., R. 10 W., I have checked the map of the survey on file in this office made by Allen G. Terry and no doubt the location of your corner is different than Terry's. Did you make a tie from your corner to Terry's? If so, will you please send same to us so we can flag our records for future references?

Thank you in advance for this information.

Sincerely,
James W. Byron
County Surveyor

By Barton L. Nelson

BLN:ll