

RENEW SEC. COR. $\frac{525}{536}$ of TR55 R2W

Fd. ORIG. COR TREE, 26" Now 17" Hemlock
showing faint scars & O.B.T.s as follows-

ORIG. 30" Now 48" FIR S. 26° E. 205 ft.

alive - shows good scar.

ORIG. 6" Now 8" FIR, 25° W. 42 2/3 ft.

alive - scribe MKs visible on unhealed
Blaze.

ORIG. 6" Now 10" FIR N. 35 1/2° W. 17 8/9 ft.

alive - scribe MKs visible on unhealed blaze,
O.B.T. To N.E. Now gone. Set 3/4" I.R.

ON West side & at base of cor. Tree 1 ft.
from center. & MK. New BT -


8" W. FIR S. 43° W. 29 3/4 ft

Mkd. "TR55 R2W S 36 CS BT"

This cor. Lies 175 ft South
of old scoured man Jeep Road at
cutting cor. Logged To N.W.

May 31, 1967

V.R.T.
J.W.
D.W.



8
* #122-125-1W
* #80
D.W. J.W.B.

C.S. File No. 52/30-87