

LANE COUNTY RESTORED CORNER

#47

Index 1390

Corner Northwest Corner Section 18

Twp. 20 S R. 6 W

From original G. L. O. field notes, dated 1872

EVIDENCE FOUND: Aug. 19, 19 58


Corner Post
9" Fir N 46°E 21 lks 13.9'
 Witness 9" Fir N 85°W 60 lks 39.6'
 Marks 40" Fir N 06°E 11 lks 7.3'
60" Fir S 34°W 105 lks 69.3'

No Trace.
26" Dead Fir - Scribing visible. (Bearing should be S 46° E)
No Trace.
Now 48". Faces not chopped out.
64" tree. Faces not chopped out.

From reestablishment field notes, dated _____

EVIDENCE FOUND: _____, 19 _____

Corner _____
 Witness _____
 Marks _____



RETRACEMENT NOTES: Set 3" X 3" X 4' Vine Maple Post.
Plates & "W" nails

26" Dead Fir S 49°E 12.9' Orig. B.T.
48" Fir N 03°E 7.8' " "
14" Fir N 79°W 30.7' " "

Iyle E. Bonstead
 Signature

Oct. 13, 1958
 Date

Land Agent
 Title

CS 531-5

85-028-01