

1147  
Renewed  
Cor. No.  
#39

INTERNATIONAL PAPER COMPANY

Long-Bell Division

VAUGHN BRANCH

September 17, 1957

Mr. F. E. Waggoner  
County Surveyor  
Lane County Court House  
Eugene, Oregon

Dear Sir:

RE: Field Notes to Closing Corner  
Sections 2 & 3 (20-7)

In order to comply with the Bureau of Land Management's timber sale contract #14-11-001(9)-77, requiring a road to be constructed into the sale area as specified on Exhibit "D" of their contract, it was necessary to remove the monument (1-1/8" iron rod and two bearing trees) to the corner of Sections 2 and 3, T20S, R7W, W.M.; prior to removing the monument we marked new bearing trees as follows:

A Fir, 30 inches diameter bears S 69° 15' E, 83 LKS dist.  
marked T20S, R7W, S3 B.T.


A Cedar, 48 inches diameter bears S 53° 45' W, 137 LKS dist.  
marked T20S, R7W, S4 B.T.

Original bearing trees remain as follows:

A Fir, 64 inches diameter bears N 17° E, 75 LKS dist. plainly  
blazed and healed.

When the road construction was complete the monument (1-1/8" iron rod) was firmly set in the road bed, the top of which is flush with the top of the road subgrade.

Very truly yours,



W. F. Dailey  
Resident Logging Engineer

WFD/js

This work was done under my supervision and  
has my approval:



RECEIVED

OCT 9 1957  
LANE COUNTY SURVEYOR

CS 53/1-13