

LANE COUNTY RESTORED CORNER

Index 2306

Corner North quarter Corner Section 24

Twp. 22 S R. 4 W

From original G. L. O. field notes, dated 1884

EVIDENCE FOUND: December 2, 19 59

Corner Post

No trace

48" Fir South 45° East 2 links

52" Blowdown - Healed scars visible

Witness \_\_\_\_\_

Marks 36" Fir North 65° West 53 links

44" Blowdown - healed scars visible

From reestablishment field notes, dated \_\_\_\_\_

EVIDENCE FOUND: \_\_\_\_\_, 19 \_\_\_\_\_

Corner \_\_\_\_\_


Witness \_\_\_\_\_

Marks \_\_\_\_\_

RETRACEMENT NOTES: Set 1" x 30" alum. pipe and 3" x 3" x 5' yew post.  
Plates, "W" nails 20° Declination

46" Fir stump South 2° West 64.8 feet

36" Fir stump North 76° West 91.9 feet



Lyle E. Boustead

Signature

January 11, 1960

Date

Land Agent

Title

CS 53/1-49