

LANE COUNTY RESTORED CORNER

Index 2216

Corner Corner common to Sections 36/1 & 31/6

Twp. 20 & 21 R. 5 W & 6 W

From original G. L. O. field notes, dated _____

EVIDENCE FOUND: _____, 19____

Corner _____

Witness _____

Marks _____

From reestablishment field notes, dated _____


EVIDENCE FOUND: Orig. 30", now 54" Cedar N.36°E., 199

Corner 69.3 ft. I do not open. Orig. 20", now 40" Stump, good scribing visible "S" N.87°W. 79.2 ft.

Orig. 20", now 42" Stump, shows scar, S82°W. 58.7 ft. I do not open.

Witness Orig. S. E. BT. would be in roadway.

Marks _____



RETRACEMENT NOTES: Set Brass Cap at corner mkd: Doug C. Surveyor's, 1959

Note: Corner on South edge of logging road.

New BT's: 18" Laurel N. 13°W. 105.0 ft. scribed S36 T20S R6W CS BT.

14" R. Fir S.78°E. 24.5 ft. scribed S 6 T21S R5W CS BT

19" Cedar S.75°W. 97.0 ft. scribed S 1 T21S R6W CS BT.

14" R. Fir N.45°E. 32.4 ft. scribed S31 T20S R5W CS BT.

James W. Byron

Signature

Map File No. 49/89

Deputy

June, 1958

Date

Title

Douglas County Surveyor's Office

CS 53/1-89