

LANE COUNTY RESTORED CORNER

Index 2302

Corner Southwest corner of Section 18

Twp. 20 S R. 5 W

From original G. L. O. field notes, dated 1854

Corner Post
20" Fir North 44° East 70 links
 Witness 12" Fir South 87° East 67 links
 Marks 10" Fir South 13° West 104 links
4" Laurel North 40° West 20 links

EVIDENCE FOUND: January 15, 19 60

Gone
42" stump lower face visible
gone
gone
gone

From reestablishment field notes, dated 1934 C.S.


Corner 4" x 4" x 5' Fir post
38" Fir North 44° East 70 links
 Witness 9" Chinq. South 78° East 18 links
 Marks 16" Fir South 62° West 26 links
9" Laurel North 45½° West 28 links

EVIDENCE FOUND: January 15, 19 60

Fd rotted off
42" Blowdown stump lower face visible
Remains of decayed stump
20" Fir Scribing visible
10" Laurel scribing visible

RETRACEMENT NOTES: Set ½" x 18" G.I. pipe and old C.S. post

Plates and "W" nails Declination 20°
12" Fir North 7° East 59.3 feet
8" Fir South 26° East 22.5 feet
20" Fir South 63° West 16.7 feet C.S. B.T.
12" Fir North 75° West 6.2 feet



Lyle Boustead

Signature

March 9, 1960

Date

Land Agent

Title

CS 53/1-88