

LANE COUNTY RESTORED CORNER

Index 1526

Corner East $\frac{1}{4}$ Corner Section 32

Twp. 20 S R. 4 W

From original G. L. O. field notes, dated 1854

EVIDENCE FOUND: Dec. 11, 1958

Corner Post
20" Fir S 30°E 30 lks 19.8'

Gone
Wind thrown-axe marks and $\frac{1}{4}$ from $\frac{1}{4}$ - scribe visible in very rotten wood.

Witness _____
 Marks 15" Fir S 42°W 25 lks 16.5'

Stump. Traces of "BT" scribing after chopping out face.

From reestablishment field notes, dated _____

EVIDENCE FOUND: _____, 19 _____

Corner _____

Witness _____


Marks _____

Restoration
 RETRACEMENT NOTES: 2" X 5' Fir post & $\frac{1}{2}$ " Monel Pipe.

Set corner from BT in Sec. 32 by bearing and distance.

A Fir N 49°E 10.0'

A Fir S 01°W 24.0'



Douglas G. Calder
 Signature

Jan. 19, 1959
 Date

Engineer
 Title

CS 53/1-117