


SPRINGFIELD SURVEY FILE

PUBLIC LAND CORNERS

WEYERHAEUSER COMPANY
SPRINGFIELD BRANCH

TOWNSHIP 20 S RANGE 6 W
SECTION 22 CORNER SE
COUNTY Lane & Douglas OREGON



ACCESSORIES ADDED THIS DATE:

MAGNETIC DECLINATION 20°

	BEARING	FEET	ORIG. B.T.	"W" NAIL	PLATE	BRASS DISC
28" Fir	S 59° E	51.0	X	X	X	--
30" Fir	S 38° E	65.7	X	X	X	--
26" Fir	S 69° W	20.2	X	X	X	--
26" Fir	N 49° W	42.4	X	X	X	--

IDENTIFIED ON PHOTO:

INFORMATION ON LOCATION OF CORNER AS NOW SET:

GROUND COVER: Salal, bracken fern and 5 to 10-yr. fir reproduction.

(USING FORM LINES SKETCH TOPOG AT CORNER ON PAGE 2 PLAT)

SLOPE FACES (GIVE BEARING IN DEGREES) S 20° E ON MINUS (-) 5 %

NORTH: 0%; Logged 5 to 10 yrs. to West; Uncut O.G. fir to East

SOUTH: - 5%; 90' to Hi-Lead landing and end of dirt logging spur bearing SE 1/4, logged 10 yrs. to West; logged to East with scattered large residual 2nd Gr. Fir.

EAST: -10%;

WEST: - 5%

WORK DONE FOR W. CO.

FIELD NOTES IN BOOK:

BY: *William F. Hill* DATE: 6/19/61

ENGINEER SURVEYOR
Land Agent

ASSISTED BY: (none)

UNDER THE SUPERVISION OF:

COPIES SENT TO:

SEAL PAGE 3

GLO SURVEY RECORD

DATE: 1950
CORNER Brass Cap

PRESENT CONDITION - (DESCRIBE FULLY - USE PAGE 2 IF NEEDED FOR EXPLANATION.)

Found as described by G.L.O.

ACCESSORIES:

	BEARING-	LINKS-	FEET-	
26" Fir	N 60 1/2° E	78	51.5	Good condition; 28" Fir
26" Fir	S 37 1/2° E	101	66.7	" " 30" "
20" Fir	S 70 1/2° W	33	21.8	" " 26" "
22" Fir	N 48 45' W	67	44.2	" " 26" "

SURVEY RECORD
DATE:

PRESENT CONDITION:

CORNER SET: -----

MAG. DECL.: 20°

BEARING AND DISTANCE TO ABOVE IDENTIFIED SURVEY ACCESSORIES:

BEARING	FEET	SURVEY	
N 59° E	51.0	1950	Measured to face
S 38° E	65.7	"	" " "
S 69° W	20.2	"	" " "
N 49° W	42.4	"	" " "

CS 53/102-2