

PUBLIC LAND CORNERS


bvce

WEYERHAEUSER TIMBER COMPANY
 SPRINGFIELD BRANCH

TOWNSHIP 33 S RANGE 3 W #27

SECTION 18 CORNER W 1/4

COUNTY LANE-DOUGLAS LINE OREGON



GLO SURVEY RECORD

DATE: 1982

CORNER 50" Fir Scribed West Face

PRESENT CONDITION - (DESCRIBE FULLY - USE PAGE 2 IF NEEDED FOR EXPLANATION.)

Found here scribed W 1/4 West face of 50" Fir.

ACCESSORIES:

	BEARING-	LINKS-	FEET-
8" Yew	S 10° W	25	20.5
40" Fir	N 10° E	30	24.5

2 1/2" Yew corner
 10" Yew corner of high dead. Scribing visible.
 40" Fir, 1/4" scribed. 1/4" scribed. Possibly was
 here scribed, found here.

SURVEY RECORD

DATE: _____

PRESENT CONDITION: _____

CORNER SET: 50" Iron 1/4" W. 1/4" W. 1/4" W. 1/4" W. 1/4" W. MAG. DECL.: 20°

60" corner Fir Face of rod to W. 1/4" W. 1/4" W. 1/4" W. 1/4" W. bark scribing

BEARING AND DISTANCE TO ABOVE IDENTIFIED SURVEY ACCESSORIES:


BEARING-	FEET-	SURVEY -
S 10° W	20.5	10"
N 10° E	24.5	40"

Dist. 5 feet. Scribed on West face of 50" Fir.
 is scribed Yew.
 10" scribing of West face 10". Fir to 50" Fir.
 bearing probably should be N 10° W instead of N 10° E.

CS 53/107-21

MAGNETIC DECLINATION 20°

ACCESSORIES ADDED THIS DATE:



	BEARING	FEET	ORIG. B.T.	"W" NAIL	PLATE	BRASS DISC
36" Flx	N 22° E	35.0'		X	X	
48" Flx	S 45° E	37.0'		X	X	

IDENTIFIED ON PHOTO:

INFORMATION ON LOCATION OF CORNER AS NOW SET:

GROUND COVER: Sward Fern

(USING FORM LINES SKETCH TOPOG AT CORNER ON PAGE 2 PLAT)

SLOPE FACES (GIVE BEARING IN DEGREES) S 20° E ON MINUS (-) 1/2

FROM CORNER

NORTH: 37 75' - 20%

SOUTH: 37 75' - 20%

EAST: 37 75' - 20%

WEST: 37 75' - 20%

WORK DONE FOR W. T. CO.:

FIELD NOTES IN BOOK:

BY: Mc Chesney

DATE: Apr 11, 1958

ENGINEER - SURVEYOR

ASSISTED BY:

UNDER THE SUPERVISION OF:

COPIES SENT TO:

SEAL