


# PUBLIC LAND CORNERS

WEYERHAEUSER TIMBER COMPANY  
 SPRINGFIELD BRANCH

TOWNSHIP 24 S RANGE 2 W

SECTION 28 CORNER E 1/4

COUNTY DOUGLAS OREGON



## GLO SURVEY RECORD

PRESENT CONDITION - (DESCRIBE FULLY -  
 USE PAGE 2 IF NEEDED FOR EXPLANATION.)

CORNER POST DATE: \_\_\_\_\_

NOT FOUND

## ACCESSORIES:

	BEARING-	LINKS-	FEET-	
6" HEMLOCK	N 55° W	30	19.8	9' GREEN HEMLOCK
16" FIR	N 52° E	24	15.0	REMAINS BROKEN FIR STUMP

## WOSFORD SURVEY RECORD

PRESENT CONDITION: \_\_\_\_\_

DATE: 1953 1957

38" FIR	N 76° E	31.6'		SCREWED 1/4" x 2" x 53' BT	OK
22" FIR	S 73° W	14.5'		SCREWED 1/4" x 2" x 53' BT	OK

CORNER SET: 1-1/2" I.P. (WOSFORD'S) MAGNETIC DECLINATION: 20°

## BEARING AND DISTANCE TO ABOVE IDENTIFIED SURVEY ACCESSORIES:

BEARING-	FEET-		
N 53° W	18.8	9" HEMLOCK	ORIGINAL BT
N 52° E	15.0	FIR STUMP	ORIGINAL BT
N 76° E	31.6	38" FIR	WOSFORD BT
S 73° W	14.5	22" FIR	WOSFORD BT

CS 53/110-6

9

ACCESSORIES ADDED THIS DATE:

	BEARING-	FEET	ORIG. BT	W <sup>2</sup> -NAIL	PLATE	BRASS DISC
22" FIR	S 73° W	14.2		X	X	
38" FIR	N 75° E	32.5		X	X	

IDENTIFIED ON PHOTO:

INFORMATION ON LOCATION OF CORNER AS NOW SET:

DESCRIPTION OF GROUND COVER AND GROUND SLOPE AT CORNER: RHODO

CAT TRAIL

FROM CORNER NORTH: 25' LOGGED TO EAST, 30' TO WEST

SOUTH: 25' 330' TO CREEK FLOW EAST, LOGGED TO EAST, 30' TO WEST

EAST: 52' 120' DRAW COURSE N.W. 1/4, 30' TO LOG ROAD, LOGGED

WEST: 12' 100' CROWNED NEAR CREEK TO WEST, OPEN TIMBER

WORK DONE FOR W. T. CO.

BY: *Alan McCreary*  
ENGINEER - SURVEYOR

DATE: OCTOBER 24, 1957

ASSISTED BY: \_\_\_\_\_

UNDER SUPERVISION OF:

COPIES SENT TO: \_\_\_\_\_