


PUBLIC LAND CORNERS

WEYERHAEUSER COMPANY
 SPRINGFIELD BRANCH



TOWNSHIP 24S RANGE 2W
 SECTION 7 CORNER E $\frac{1}{2}$
 COUNTY Douglas OREGON

GLO SURVEY RECORD
 DATE: 1884

PRESENT CONDITION - (DESCRIBE FULLY -
 USE PAGE 2 IF NEEDED FOR EXPLANATION.)

CORNER Post

No evidence

ACCESSORIES:

	BEARING-	LINKS-	FEET-
7" Cedar	S84°E	37	24.4
9" Hemlock	N52°W	26	17.2

6" Cedar snag scribing visible
 7" Hem. snag on ground & 10' down
 hill from call distance

SURVEY RECORD
 DATE: _____

PRESENT CONDITION: _____

CORNER SET: Set from Brg. & dist. from 6" Cedar snag MAG. DECL.: 20°E

BEARING AND DISTANCE TO ABOVE IDENTIFIED SURVEY ACCESSORIES:

BEARING-	FEET-	SURVEY -	
S84°E	24.4	1884	Measured to face

2-130

ACCESSORIES ADDED THIS DATE:

MAGNETIC DECLINATION

20°E

	BEARING	FEET	ORIG. B.T.	"W" NAIL	PLATE	BRASS DISC
16" Hemlock	N69E	63.4	-	x	x	-
18" Cedar	S64 $\frac{1}{2}$ ° E	73.2	-	x	x	-

IDENTIFIED ON PHOTO:

INFORMATION ON LOCATION OF CORNER AS NOW SET:

GROUND COVER: Old growth Fir and Hemlock

(USING FORM LINES SKETCH TOPOG AT CORNER ON PAGE 2 PLAT)

SLOPE FACES (GIVE BEARING IN DEGREES) N80°W ON MINUS (-) 35 %

Corner falls in E of CG 380 Road Sta. 48 + 50

NORTH: 0 %

SOUTH: + 20 %

EAST: + 40 %

WEST: - 40 %

FROM CORNER -

WORK DONE FOR W. CO.

FIELD NOTES IN BOOK:

BY: Bruce V. Wood DATE: Dec. 10, 1965
ENGINEER - SURVEYOR

ASSISTED BY: Gary Hird
Carl Peters

COPIES SENT TO:

UNDER THE SUPERVISION OF:

SEAL

PAGE 3

C.S. No. 53/110