


PUBLIC LAND CORNERS

25

**WEYERHAEUSER COMPANY
SPRINGFIELD BRANCH**

TOWNSHIP 24S RANGE 3W
SECTION 24 CORNER S $\frac{1}{2}$
COUNTY Douglas OREGON




GLO SURVEY RECORD				PRESENT CONDITION - (DESCRIBE FULLY - USE PAGE 2 IF NEEDED FOR EXPLANATION.)	
DATE: <u>1883</u>					
CORNER <u>Post</u>					
ACCESSORIES:					
BEARING-	LINKS-	FEET-			
24" Fir	N25°E	33	21.8	28" Fir face not cut out but "face" line visible on top of stump.	
36" Fir	S60°E	25	16.5	36" Fir stub - 10' high; face not grown, scribing visible	
Weyerhaeuser Co. SURVEY RECORD				PRESENT CONDITION:	
DATE: <u>1944</u>					
28" Fir	N30°E	18.1'	Same trees as above		
36" Fir	S56°E	14.0	* See page 2		

CORNER SET: 1" x 30" Aluminum Pipe MAG. DECL.: 20°E

BEARING AND DISTANCE TO ABOVE IDENTIFIED SURVEY ACCESSORIES:

BEARING-	FEET-	SURVEY -	
N32°E	21.8	1883	Distance measured to face
S64°E	16.5	1883	Distance measured to face
* See page 2 for		1944	Weyerhaesuer Co. survey information.
#14			

SECTION 24 TOWNSHIP 24S RANGE 3W



— // — // — // — LINE MARKED BY NOTCH CUT IN BLAZE.

○ — KNOWN CORNER.

⊗ — REFERENCED CORNER
BY WEYERHAEUSER
METHOD.

* The information placed on the original BT's by the 1944 Weyerhaeuser Co. survey did not agree with the original 1883 survey. I accepted the original BT's, disregarded the 1944 data and set the corner on the basis of the original "call" distances.

Donald H. Jordan

Oregon Registered Land Surveyor

#692

ACCESSORIES ADDED THIS DATE:

MAGNETIC DECLINATION 20°E

	BEARING	FEET	ORIG. B.T.	'W' NAIL	PLATE	BRASS DISC
28" Fir stump	N32°E	21.8	x	x	x	-
36" Fir stub	S64°E	16.5	x	x	x	-

IDENTIFIED ON PHOTO:

INFORMATION ON LOCATION OF CORNER AS NOW SET:

GROUND COVER: Logged 1963

(USING FORM LINES SKETCH TOPOG AT CORNER ON PAGE 2 PLAT)

SLOPE FACES (GIVE BEARING IN DEGREES) N45°W ON MINUS (-) 60 %

NORTH: - 35%

SOUTH: + 35%

EAST: + 25%

WEST: - 25%

FROM CORNER -

WORK DONE FOR W. CO.

FIELD NOTES IN BOOK:

BY: D.H. Jordan DATE: 12-2-65
Asst. ENGINEER - SURVEYOR

ASSISTED BY: Carl Peters

COPIES SENT TO:

UNDER THE SUPERVISION OF:

SEAL

53/111

PAGE 3